

FINAL REPORT
ON
AUGMENTATION OF BOMBAY CITY'S
WATER SUPPLY
(April 1948)

VAITARNA-CUM-TANSA-SCHEME
(PART I & II)

BY

N. V. MODAK, ESQR. C.I.E., J.P.,
B.E., M. Inst. C.E., M.I.E. (Ind.), M.I.M.&Cy.E., F.R. San. I., &C.,
Special Engineer, Bombay Municipality.

D85.231.35B
H8
023721

MUNICIPAL PRINTING PRESS
BOMBAY.

Para.

1	Introduction	
2	Items covered by survey work	
	Investigating alternative sites for the dam	... 4
	Investigating more convenient alignment for the three sections of the tunnel	... 2
	Fixing the most suitable alignment for the new pipe line	... 3
	Extending the existing cross drainage works	... 3
	Fixing suitable routes for the trunk inlet mains	... 3
	Balancing reservoir at Ghatkopar	... 4
	Temporary bunds on the Vaitarna river and Tasu Nalla	... 4-5
	Determining the alignment of new service roads	... 5
	Quantity of earth work, metal etc., for the roads	... 5
	Materials survey	... 5-8
	Fixing sites for temporary camps	... 8
	Pipe line to convey water of the Vaitarna reservoir independently of Tansa	... 8
3	Preliminary works	... 9
4	Results of bore holes taken at the site of the dam and the waste weir	...10-12
5	Estimate of maximum flood discharge	...12-14
	Practice followed by the P.W.D. Engineers in the past	...14-15
	Formula evolved by the Hydro-Dynamic Research Station, Khadakwasla	...15-16
6	Factors which influence the choice of the type of the waste weir	...17
	Ordinary overflow type	...17
	Side channel	...17
	Syphon Spillway	...17-18
7	Lengths available for different types of spillway	...18
	Side channel spillway	...18
	Syphon spillway	...19
	Central Spillway	...19-20
8	Why useful storage of 17,000 million gallons was suggested	21-22
9	Necessity of reviewing the position regarding the useful storage	...22
10	Extent of storage likely to be obtained from the Vaitarna River at the site 'D'	...23-24
11	Storage available with F.S.L. at 535 T.H.D.	...25
	Provision for silting up	...25
	Water spread of the Vaitarna Reservoir	...26
12	The extent of the daily supply that can be made available with the useful storage of 46,000 million gallons	26-27

Para	Pages
Major Tulloch's estimate of the run-off for Tansa catchment and the dependable supply therefrom	...27
Co-relation ratio between the yields of the Vaitarna and Tansa catchments and how it was fixed	...28
13 Size of the tunnel	...28-29
14 Dependable combined supply per day for various F.S.Ls. of the Vaitarna Reservoir	...30
Supply available with a useful storage of	
17,000 million gallons	...30
Do. 24,000 million gallons	...31
Do. 26,000 million gallons	...31
Do. 34,000 million gallons	...31
Do. 46,000 million gallons i.e.	...31
the ultimate development of the source	...31
15 Works to be constructed now must be capable of being developed to obtain a combined dependable supply of 220 million gallons per day	...33-34
16 Economical way to convey the supply of 220 million gallons per day to the City and the suburbs	...34-41
17 No additional outlets in the Tansa Dam will be necessary	41-43
18 Advantages to be gained by creating a useful storage of 46,000 million gallons	...43-46
19 What type of Spillway would be suitable if the scheme were developed from its very commencement to secure an ultimate supply available therefrom	...46-47
20 Financial justification for undertaking the whole scheme from the very commencement	...47
Cost of a scheme for given an ultimate combined supply of 160 million gallons per day as originally suggested	...47-55
Cost of diverting the waters of Vaitarna River into the Tansa lake to ensure a supply of 110 million gallons per day therefrom including the cost of conduits, etc.	...56-57
Comparison with Bhivpuri Scheme for obtaining a supply of 60 and 100 million gallons per day	...57-58
Cost of water per 1,000 gallons for different schemes	...59
21 Cost per million C.ft. of water stored for different reliable supplies	...60
22 Necessity of undertaking the work of improving the internal distribution system simultaneously	...60-61
23 Internal distribution system immediate needs	...62
24 Detailed estimates can be submitted after the receipt of tenders for various items	...63
25 Contractors likely to quote higher rates and if so, the work should be carried out departmentally	...63-64
26 Desirability of getting the designs checked by Experts	...64-65
27 Desirability of sending young Engineers abroad for training	65-66
28 Staff required for the execution of the scheme	...66

Para		Pages
29	Desirability of giving additional powers to the Municipal Executive for the speedy execution of the scheme	..66
30	Time required for completion	..67
	Relief likely to be obtained by the City as the work on the dam and the pipe line progresses	..68
31	Summary of the scheme	..69-71
32	Financial consideration	..71-73
33	Sanction of the Corporation required for	..73-74

GENERAL NOTES ON MAJOR PARTS OF THE SCHEME.

Part II.

CHAPTER Nos.	Para Nos.	Pages
1 DAM	1-25	75-94
2 TUNNELS	1-6	94-98
3 PIPE LINE	1-10	98-109

Part III.

—APPENDICES.—

(to be published separately)