

972
7

REPORT
ON THE SURVEYS
FOR
PROTECTIVE IRRIGATION WORKS
IN THE
DECCAN
BY
H. F. BEALE, Esq., M. INST. C. E.,
Superintending Engineer,
AND ITS
REVIEW

BY
A. HILL, Esq., C. I. E., M. INST. C. E.,
Chief Engineer for Irrigation, Bombay.

PRINTED AT THE
BRITISH INDIA PRESS, BYCULLA, BOMBAY.

1909.

D26. 231

D9

~~15504~~

CONTENTS OF THE VOLUME.

		Pages.
1.	Review by Mr. A. Hill, C.I.E., Chief Engineer for Irrigation ...	... { i to iv & 1 to 63
2.	Report by Mr. H. F. Beale, Superintending Engineer ...	... 65—68
3.	„ on the Tapti Valley Surveys	... 69—87
4.	„ „ Godaveri Valley Surveys ...	... 89—111
5.	„ „ Mula Valley Surveys ...	... 113—128
6.	„ „ Bhima Valley Surveys ...	... 129—160
7.	„ „ Krishna Valley Surveys ...	... 161—175
8.	„ „ Ghatprabha Right Bank Canal Project—Dadda Storage.	177—206
9.	„ „ „ „ „ „ Surveys ...	... 207—337
10.	„ „ Malprabha Valley Surveys ...	... 339—347

REPORT ON THE RESULTS OF THE IRRIGATION
SURVEY OF THE DECCAN

BY

MR. A. HILL, C. I. E.,
Chief Engineer for Irrigation, Bombay.

INDEX TO THE REPORT

on the Results of the Irrigation Survey of the Deccan,

BY

MR. A. HILL, C.I.E., *Chief Engineer for Irrigation, Bombay.*

PARA.	PAGE.
1 Submits report on the results of the Irrigation Survey of the Deccan ...	1
2 Review divided into two parts	1
Part I.	
3 Description of Index map	1
4 { Table I. of all projects, possible	2 to 6
{ Table II. of best projects	
5 Method of calculating irrigation possible	6
6 Rates adopted in Table I.	6
7 Rates adopted in Table II, including perennial rate	6 to 7
8 Method of calculating area of irrigation in Table II.	7
9 Method of assessing revenue	7 to 8
10 Period within which revenue may be expected	8
11 Knowledge of the supply of water	8
12 Shows that determination of the cost per acre is a very convenient method of judging the value of a project	8 to 9
13 Miscellaneous profits not included in estimate of revenue	9
14 State of preparation of projects	9
15 The most important of the famine protective works not included in Table II. is the <i>Kadva Project</i> in the Nasik District	9
16 Names the rivers on which small productive works are possible	9 to 10
17 No small project to be allowed to interfere with the great protective projects	10
18 Compares the works investigated on the Tapti River with those investigated on the Ghat stream of the Deccan	10 to 11
18 A Successful results due to Mr. Beale	11

Appendix to Part I.

Duty of water	11 to 14
----------------------	----------

Part II.

1 Arrangement of Part II.	15
----------------------------------	----

Tapti Valley.

2 Description of Tapti Valley	15 to 16
3 Survey, preliminary, of Tapti Valley	16

Girna (Tributary of the Tapti).

4 Selection of site of storage on the Girna	16
5 Nature of foundations	16 to 17
6 Supply available	17
7 Canal alignment	17
8 Instructions for guidance when further survey is ordered	17 to 18
9 Main features of the project recommended	18
10 Probable irrigation and revenue	18

The Panjhra (Tributary of the Tapti).							PAGE.
PARA.							
11	No satisfactory project found on the Panjhra River	...	...	...	...	...	19
Tapti (Main Stream).							
12	Main River Tapti examined	...	...	...	...	...	19
13	Hatnur site for storage and perennial crops	...	...	...	...	...	19
14	Susti site for an 8-month canal	...	...	...	...	...	19 to 20
Aner (Tributary of the Tapti).							
15	Aner River	...	...	...	...	...	20
General Remarks on Tapti Valley.							
16	General results of survey of Tapti Valley	...	...	...	...	...	20 to 21
17	Plans to be printed in connection with Tapti storage and Girna Project...	...	...	...	...	...	21
Godaveri Valley.							
18	Good command obtained in the Godaveri Valley, and Godaveri canals are sanctioned	...	...	...	...	...	21
19	All projects practicable in the Godaveri Valley are required for irrigation in the British Territory	...	...	...	...	...	21 to 22
20	The Palkhed Project	...	...	...	...	...	22
21	The Nasik storage at Gangapur	...	...	...	...	...	23
22	The Aundh storage	...	...	...	...	...	23
23	The Darna Dam under construction	...	...	...	...	...	23
24	The Darna Right Bank Canal Project	...	...	...	...	...	23
25	The Pravara Project	...	...	...	...	...	24
26	The Mula Project of Ahmednagar	...	...	...	...	...	24
27	This project commands excellent land...	...	...	...	...	...	24
28	Key to the survey work of the Mula Project	...	...	...	...	...	24
29	Description of the Mula Project	...	...	...	...	...	24 to 25
30	Storage sites, &c., for this project	...	...	...	...	...	25
31	Best arrangement for works for this project	...	...	...	...	...	25
32	Plans to be printed	...	...	...	...	...	25
Bhima Valley.							
33	Physical features of the Bhima Valley	...	...	...	...	...	25 to 26
Kukadi Project.							
34	Key to the survey work of Kukadi Canal	...	...	...	...	...	26
35	Mina water easily delivered into Kukadi	...	...	...	...	...	26
36	Ghod water can also be obtained	...	...	...	...	...	26 to 27
37	Records of discharge insufficient	...	...	...	...	...	27
38	Main features of the Kukadi Canal system practicable	...	...	...	...	...	27
39	Separate projects for Ghod, Mina and Kukadi Rivers prepared before importance of Kukadi command was realised	...	...	...	...	...	27
39-A	Mina Project—Approximate cost	...	...	...	...	...	27 to 28
40	Approximate cost of Kukadi Project	...	...	...	...	...	28
41.42	Recommendation for preparation of a project when further observations of discharges are available	...	...	...	...	...	28 to 29
42-A	Reports to be printed as accompaniments	...	...	...	...	...	29
42-B	Plans to be printed for the Kukadi Project	...	...	...	...	...	29

Para.	Bhima Project.	Page.
43	General description of the Bhima Project	29 to 30
44	Recommendation for survey when again undertaken	30
44-A	Bhima Tributaries that cannot be used for Protective Irrigation	31
44-B	Small Productive Projects seem possible	31

Mutha (Tributary of Bhima).

The Mutha Canal Extension.

44-C	Mutha Supply well-known for 33 years	31
44-D	Great protective advantage of the Mutha River only recently ascertained.	31
44-E	Proposals for storage for the Mutha Extension Project	32
44-F	Reference to details will be found given in the attached report by the Chief Engineer, Irrigation, and in the preliminary report submitted to the Government of India	32
44-G	Mutha Extension can relieve tail of the Nira Left Bank Canal	32
	Report on the Mutha Extension Project submitted to the Government of India with this Government letter No. W. I.—763, dated 18th March 1909... ..	32 to 36
	Report by the Chief Engineer, Irrigation, on the Mutha Extension Project submitted to Government with Chief Engineer, Irrigation's No. 16, dated 11th January 1909	37 to 43

Nira River.

The proposed Nira Right Bank Canal and the existing Nira Left Bank Canal.

44-H	Magnitude and importance of the Nira Project	44
45	Length of Nira Right Bank Canal to be limited to 150 miles	44
46	Storage at Bhatgarh—Lake Whiting	44
47	Storage at Vir Basin	44
48	Nira Right Bank Canal is likely to be productive	45
49	General abstract of projects in the Bhima Valley	45
50	Plans to be printed in connection with the Mina Storage and Bhima Project	45

Krishna Valley.

51	The abundant supply of water of the Krishna cannot be conveyed on to the famine lands	45
52	Physical features of the Krishna Valley	45 to 46
53	Pumping necessary to get water on to the famine lands	46
54	Head-waters of the Krishna River cannot conveniently be taken into Nira Valley	46
55	Productive works of small command possible on the Krishna River	46 to 47
56	The best productive work would have storage at Helvak on Koyna	47 to 48
57	Storage at Dhoni on Krishna would probably suit a productive work	48
58	Tributaries of the Krishna in the Kolhapur State	48
59	Statement of projects possible in the Krishna Valley	49
60	Reports and plans to be printed	49

Ghatprabha Valley.

61	The whole of the supply of the Ghatprabha can be utilised for irrigation.	49
62	The Gokak Canal on the Left Bank	49 to 50
63	The detailed plans for the Canal to start from the Gokak weir, ready for sanction	50

Ghatprabha Right Bank Project.

64	The Ghatprabha Right Bank Canal. A canal can be taken through the hills by Gokak and command 825,000 acres	50
65	Ghatprabha can use storage for Gokak and additional storage for Gokak can be obtained at Ajra	50 to 51

PARA.	Ghatprabha Right Bank Project—(contd.)	PAGE.
66	The Markandya supply could be used... ..	51
66-A	Report on the Ghatprabha Project and Chief Engineer's comments and opinions of Revenue Department officers are attached	51
67	Report, plans and estimates to be printed	51
	Note by the Chief Engineer, Irrigation, on the Preliminary Report on the Ghatprabha Right Bank Canal	51 to 55
	Report by the Chief Engineer on the same subject	55 to 57
	Letter from the Collector of Belgaum, No. 9496, dated 30th November 1908	57
	Letter from the Collector of Bijapur, No. 1045, dated 26th February 1909	57 to 58
	Letter from the Commissioner, Southern Division, No. 791, dated 10th / March 1909	58

Malprabha Valley.

68	Physical features of the Malprabha Valley	59
69	Command of Canal on the Right Bank (south) can be obtained	59 to 60

Tungabhadra Valley.

70	Northern tributaries not reliable	60
71	The Wardha is the first reliable stream	60
72	Madag Tank on the Kumudvati River	60 to 61
73	Best command on the left or northern bank	61

Gujerat.

74	Information in connection with Gujerat is scanty	61
75	Mahi River offers the best means of Irrigation in Gujerat	61
76	Another river that may be useful is the Sabarmati River	62
77	Smaller streams	62
78	A contour survey of the low lands of Gujerat is required	62
79	The Index map 8 miles to the inch to be corrected to agree with this Report	62