# Department of Mines, India

# REPORT'

OF THE

# CHIEF INSPECTOR OF MINES IN INDIA

UNDER THE INDIAN MINES ACT (VIII OF 1901)

FOR THE YEAR ENDING


# 31st December 1919

BY

R. R. SIMPSON, M.Sc.
Offg. Chief Inspector of Mines in India



CALCUTTA
SUPERINTENDENT GOVERNMENT PRINTING, INDIA



# Department of Mines, India

# REPORT'

OF THE

# CHIEF INSPECTOR OF MINES IN INDIA

UNDER THE INDIAN MINES ACT (VIII OF 1901)

FOR THE YEAR ENDING

# 31st December 1919

BY

R. R. SIMPSON, M.Sc.
Offg. Chief Inspector of Mines in India



CALCUTTA
SUPERINTENDENT GOVERNMENT PRINTING, INDIA

# Agents for the Sale of Books published by the Superintendent of Government Printing, India, Calcutta.

#### IN EUROPE.

Constable & Co., 10, Orange Street, Loicester Square, London, W.C.

Kegan Paul, Trench, Trühner & Co., 68-74, Carter Lane, E.C., and 25, Museum Street, London, W.C.

Bernard Quaritch, 11, Grafton Street, New Bond Street, London, W.

P. S. King & Sons, 2 & 4, Great Smith Street, West-minster, London, S.W.

H. S. King & Co., 65, Cornhill, E.C., and 9, Pall Mall, London, W.

Grindlay & Co., 54, Parliament Street, London, S.W.

Luzac & Co., 46, Great Russell Street, Loudon, W.C.

W. Thacker & Co., 2, Creed Lane, London, E.C.

T. Fisher Unwin, Ltd., 1, Adelphi Terrace, London, W.C.

Wm. Wesley & Son, 28, Essex Street, Strand, London.

B. H. Blackwell, 50 & 51, Broad Street, Oxford.

Deighton Bell & Co., Ltd., Cambridge.

Oliver & Boyd, Tweeddale Court, Edinburgh.

E. Ponsonby, Ltd., 116, Grafton Street, Dublin. Ernest Lerong, 28, Rue Bonaparte, Paris.

Martinus Nijhoff, The Hague, Holland.

#### IN INDIA AND CEYLON.

Thacker, Spink & Co., Calcutta and Simla.

Newman & Co., Calcutta.

R. Cambray & Co., Calcutta.

S. K. Lahiri & Co., Calcutta.

B. Banerjee & Co., Calcutta.

The Indian School Supply Depot, 309, Row Bazar Street, Calcutta, and 226, Nawabpur, Dacca.

Butterworth & Co. (India), Ltd., Calcutta.

Rai M. C. Sarcar Rahadur & Sons, 90/2A, Harrison Road, Calcutta.

The Weldon Library, 57, Park Street, West, Calcutta. Standard Literature Co., Ltd., Calcutta.

Lal Chand & Sons, Calcutta,

Higginbotham & Co., Madras.

V. Kalyanarama Iyer & Co., Madras.

G. A. Natesan & Co., Madras.

S. Murthy & Co., Madras.

Thompson & Co., Madras.

Temple & Co., Madras.

P. R. Rama Iyer & Co., Madras.

Vas & Co., Madras.

E. M. Gopalakrishna Kone, Madura.

Thacker & Co., Ltd., Bombay.

A. J. Combridge & Co., Bombay.

D. B. Taraporevala, Sous & Co., Bombay.

Mrs. Radhabai Atmaram Sagoon, Bombay.

Sunder Pandurang, Bombay.

Gopal Narayan & Co., Bombay.

Ram Chandra Govind & Son, Kalbadevi, Bombay;

The Standard Bookstall, Karachi.

Mangaldas Harkisandas, Surat.

Karsandas Narandas & Sons, Surat.

A. H. Wheeler & Co., Aliahabad, Calcutta and Bombay.

N. B. Mathur, Suptia Nazir Kanun Hind Press, Allahabad.

Bai Sabib M. Gulab Singh & Sons, Mufid-i-Am Press, Labore and Allahabad.

Rama Krishna & Sons, Lahore.

Supdt., American Baptist Mission Press, Rangoon.

Manager, the " Hitavada," Nagpur.

S. C. Talukdar, Proprietor, Students & Co., Coeeb Behar.

A. M. & J. Ferguson, Coylon.

Manager, Educational Book Depôts, Nagpur and Jubbulpore. 9

Manager of the Imperial Book Depôt, 63, Chaudney Chauk Street, Delhi.\*

Manager, "The Agra Medical Hall and Co-operative Association, Ltd." (Successors to A. John & Co. Agra).\*

Supdt., Basel Mission Book and Tract Depository, Maugalore.\*

P. Varadachary & Co., Madras.\*

H. Liddell, Printer, etc., 7, South Road, Allahabad.

Ram Dayal Agarwals, 184, Katra, Allahahad.

D. C. Anand & Sons, Peshawar. . .

Manager, Newal Kishore Press, Lucknow.

Agonts for the sale of Legislative Department publications only.

### - CONTENTS.

											1 102
Introductios-											
Relates to administration of the Act	•	•	-	•	•	•	•-	•	• •	•	1
Other mining statistical publications	•	•	•	•	•	•	•	•	•	•	1
Scheme of report	•	•	•	•	•	•	•	•	•	•	1
SECTION I.—PERSONS EMPLOYED-						•					
Average figures of labour		•		•		•	•		•	•	1
Increase compared with previous year		•	•	•	•	•	•	•	•	•	1 2
Supply of Labour in Jharis and Raniga		-field∎	•	•	•	•	•	•		•	2
Sardari recruiting in Assam Supply of Isbour in Central Provinces	. 1	•	•	•	•	•	:	:	•	•	2
" " Tayoy District .	•	•	•	•	•	•	•		•	•	2
Ticket-of-leave labour in Tavoy proved	efficiont	t .	•	•	•	•	٠	•	•	•	2
SECTION II.—OUTPUT OF MINEBALS-		٠,									
Coal output in various provinces .		•			•		•		•	•	2
" " increase on previous year	•	•	•	•	•	•	ě	•	•	•	2
" " opening and closing stocks	•	•	•	•	•	•	•	•	•	•	2
, despatches	•	•	•	•	•	•	- <b>•</b>	•	•	•	2 2
,, ,, colliery consumption amount delivered to coking	-	•	4	•	•	•	•	•	•	•	2
of soft and hard col			:	:	•	•	•	•	•	•	2
, , , or sold that hard con-			ngal :	and B		ields	•	•	•	•	3
, increase in Bengal and Biha						•	•	•	•		3
, , Central Province		•				•	٠	•	•	•	3
,, ,, decrease in North-West Fro		rovine	é and		•	•	•	•	•	•	3
" " " Baluchistan .	•	•	•	•	•	•	•	•	•	•	3
, , , Assam , percentage of total output r		. Dano	alam	a Dil			•	•	•	•	3 3
non nonnon auralavad in Indi				d Din	т. еп.	- 01.15	3 <b>0</b>	•	•	•	3
, per person employed in the				:		:	Ċ	:		•	3
,, demand and supply .			•	•	•	•		•		Ţ	3
Mica output	•			•	•	•	•	•			3
" " decrease compared with prev			•	•	•	•	•	•	•		3
" " " in Bihar and Orissa			•	•	•	•	•	•	•	•	8
" " increases in Madras and Raj Manganese output, increase in .	-		fields	•	•	•	•	•	•	٠	3
annumed with surviv	• \TE V00	•	•	•	•	•	•	•	•	•	4
, demand not as good as in pre-			•	•	•	•	•	•	•	•	4
" prices lower than previous yes			•				•	:		•	4
Wolfram output, decrease in	•	-	•	•	•	•	•	•	•		4
compared with previous	s year	•	•	•	•	•	•	•	•		4
, depression in the industry .	•	•	•	•	•	•	•	•	•	•	4
Gems output, decrease in	•	•	•	•	•	•	•	٠	• '	•	4
Rabies prices improved	.41.	•	•	•	•	•	•	•	•	•	4
. Supphires, native producers increase	od.	•		:	:	•	:	•	•	•	<b>4</b> 4
, prices improved .		•	•	•		•	•	•	:	:	4
Gold output, decrease in		•			•	•			•	:	4
,, ,, compared with previous year	r	•	•	•	•	•	•	•.	•		4
Copper output, large increase in .	•	•	•	•	•	•		•	•	•	4
,, ,, compared with previous y ,, industry adversely affected by uni		• .bla	• •e	•	•	•	•	•	•	•	4
Limestone output, increase in .	lavoure	tote 117	ra or	excna	inge	•	•	•	•	٠	4
Chromito , decreaso	:	•	•	•	•	•	••	•	•	•	5 5
Clay , , ,		•		•	•	•	•	•	•	•	5
Tin " " "	•			•	•	•	•	•	•	•	5
Slate ,, ,, ,	•	•	•	•	•	•	•	•	•	•	5
Salt output, increase in	•	•	•	-	•	•	•	•	<b>4</b> ,		5
Bauxite , herease in .	•	•	• •	•	•	•	•	•	• •	•	5 ·
Galena , decreaso .	•	•	•	•	•	•	•	•	•	•	5
Steatito , , , , ,	•	•	•	:	:	•	:	•	•	•	<b>5</b> 5
Fuller's earth output, increase in .	•	•	•	•	•	•	•	•	•	•	. 5

														PAGE,
TION II.—OUTP		BALS	contd	•					•					
Silver output, d		•	•	•	•	•	•	•	•	•	•	-	•	5
Graphite output		,•	•	•	•	•	•	•	•	•	•			5
Iron ore output		· •	•	•	•	•	•	•	•	•	•	•	•	5
Molybdenite ou Samarskite	• .	•	•	•	•	•	•	•	•	•	٠	•	•	5
Oahaa	)) ))	73	•	•	•	•	•	•	•	•	•	•	•	5
Appatite	,, docrease	)) 1)		•	•	•	•	•	•	•	•	•	٠	5 5
Barytes	); <b>400</b> ; 6400	3) 3)	•	•	-	•		•	•	•	•	•	•	. <b>5</b>
Potash ·	<i>y y</i>	"	•	•	•	•	•	•	÷	•	•	•	•	. <u>.</u> 5
CTION III.—Aco	idents—													-
Accidents, incre	aso in .	•										_		5
,, comp	ared with pr	e <b>vio</b> w	s year			•			Ŧ	•		•	:	ŏ
" loss (	of lives invol		acrease	on pi	reviou	s year	•	•	•	•		•	•	5
			•	•	٩,	•	•	•	•	• •	•	•	•	5
" incre	ase of, by fal			l side	es ´	•	•	•	•	•	٠			5-
39 33	••		•	٠	•	•	•	•	•	•	•	•	٠	5
11 11		nfte	•	•	•	•	•	•	•	•	•	•	•	6
-	ectricity	•	•	•	•	•	•	•	•	•	•	•	•	5
Death-rates per	iredamp	•	• 		T. J:	•	•	• .	•	•	٠	•	٠.	5
_	_						almi	nes or	.7	•	•	•	•	5
11 11 35 25	·31	"	1)	<b>33</b>	"					oal mi	•	-1-	•	5 5
••	nillion tons o			••		•	•			ART 1777	- OO U	mry.	•	5
,, ,,,		, ,,				Kingd	lom	•	•	•	•	•	•	5
Number of deat						•		•			•		.•	6
Deaths classifie	d	•	•	•		•	•	•			•	•	•	6
,, non-sta	tistical .	•	•		•			•	•					6
" in Beng	gal and Bihar			•	•	•	•	•	•	•	•	•	•	6
11 12 P	n #	com	pared w	ith p	revio	us yea	r.	•	٠	• •	•	•		6
Accidents comm	nented upon	•	•	•	•	•	•	•	•	•	٠	•	•	6
Explosions of fire	e: amab													
Accident at the	-	Com	nany T.	mita	a's N	odika	40al =	nima						•
	Kuardih Coa								•	•	•	•	•	6
	Burrakur Co									•	•	•	•	6, 7 7
** **	Bengal Coal									•	:	•	•	7
alls of roof:		•			•						•	•	•	-
Accident at the	Tales Calli	<i>C</i> .	· · · · · · · · · · · · · · · · · · ·	T.i.	م' المعان	Quina		l mina						
	Bongal Nag	_				_				mina	•	•	•	7 7
» » »	Nodiha Coal	-		_				_		, mino	•	•	•	7
	Tata Iron as								ine	•	·	•	•	7
77 27 27 13 28 19	Hurriladih (		-				_				·	•		8
n n n	Nodiha Coal			•			_		•	•	•			8
Falls of side: —					•	-								
Accident at the	Bangra Coal	Com	pany, L	imite	ďs T	oposi (	oal n	nine				_		9
	Bengal Iro								•	•	٠		•	g 9
•											·			_
In shafts—Rope: Accident at th				on. I	imite	đ <sup>r</sup> a Soi	ath K	ustore	coal	nine				9, 10, 11
				•						•		•	_	-, - <b>-, -</b> .
In shafts—While								L •	•	•				• -
Accident at the	o Equitable ( 15 <b>u Kunj</b> a Bi								mine	•	•	•	•	11 11, 12
_		•		•										,
In shafts—Misco		3 61	0	_ #.	<b></b>	.96.39-	D		<b>.</b>					10 10
Accident at the	e Inta Iron o	na St	691 CO <b>m</b>	pany	/, LIT	1166 <u>0</u> .8	rufu	ač trom j	par co	u mine	,	•	•	12, 13
Explosives:-	<b>~</b> ~	~		<b>,</b> .	4 . 30 . 3	n. 1 1	TT*11	•						10
Accident at the	о Са <b>ро С</b> орро	er Con	npany, l	Limi'	ted s	Kakha	Hille	mine	•	•	4		•	13

			-			PAGE.
Section III—Accidents—confd.			•	•		
Hanlage: — Accident at the Aldih Coal Company, Limited's Bhutgoria coal mine	•	•		-	:	13
", ", Maharaja of Kossimbazar's Ekra Khas coal mine	•	•	•	•	•	13
Sundries underground-						
Accident at Mesers. Hoare Miller and Company's Muktia mica mine	•	•	•	• ,	•	13
SECTION IV.—PROSECUTIONS AND ADDITIONS TO THE ACT-						
Prosecutions under the Indian Mines Act-			_	_		1.1
Gunpat Ram Marwari's Keshubganj coal mine	•	•	•	•	•	14 14
Banerji Santan's Jotojanski coal mine W. C. Bhattacharji and Sarada Prosad Dey's Egarcoor coal mine	•	:	•		•	11
J. Boisogomoff and Company's Dobrana coal mine	•	·	•	•	•	14
22	•	•	•	`•	•	14
Radhaballavpur coal mine	•	•	•	•	•	14
Jalota Lachipur Coal Company's North Lachipur coal mine	•	•	•	•	•	14 14
Prithvi Raj's Gujamara mica mine	•	•	•	•	:	14
S. N. Mittra and Brothers' Ranidih coal mine	•	•	•	•	•	14
J. P. Lalla's Turdu Khas coal mine	•	•	•	•	•	14
Baba S. C. Roy's Kalimati coal mine	•	•	•	•	•	15 15
Shampore Coal Company, Limited's Shampore coal mine W.C. Bhattacharji and Company's Egarcoor coal mine	•	•	•	•	•	15
Babus Naba Chandra Chatterji and Soorath Nath Banerji's Bhatudih	mica '	mine	•			15
Babu Bhagwandas Agarwalla's Singhacola mica mine	•	•	•	•	•	15
Mr. Lingamollu Venkataramiah's Kalualainlaya mica mine	•	•	•	•	•	15 15
Pandra Coal Company's Pandra coal mine	•		•	•	•	15
East Indian Agency, Limited's Makeli coal mine	·	·	•	•	·	15
Baba Kusum Kumar Mukherji's Veeratand coal mine	•	•	•	•	•	15
Babu Monmohan Ghosh's West Salanpur coal mine	•	•	•	٠	•	15
E. Meyer and Company Limited's Kalipahari coal mine	•	•	•	•	•	15 15
Tarmee Coal Company's Tarmee coal mine  Babu Blagwandas Agarwalla's Lakthaia mica mine		• i •	•	:	•	15
" " Mohesmara mica mine	•	•	•		•	15
Mr. Matat Jugjiwanpuri's Bernghat Steatite mine	•	•	•	•	•	15
Babu A. K. Chatterji's Mahalakshmi mica mine	•	•	•	•	•	15
Babu Bancha Nidhi Praya's Hanaman mica mine  Babu Manji Hira's Koradih coal mine	•	•	•	•	•	l5 15
Babu Manji Hira's Koradin coat mine	•	•	•	•	•	15 15
Bibar Mica Mining and Trading Company's Serni mica mine .	•	•	•		•	16
M. N. Dutt and Gunga Bux Kabra's Chattadanga coal mine	• _	•	•	•	•	16
Mr. B. Channayya's Tarmee coal mine	•	•	•	•	•	16
Prosecutions under Special Rules— Equitable Coal Company, Limited's Dishergarh coal mine						• •
Pench River Coal Company, Limited's Eklehra coal mine	•	•	•	•	•	16 16
Upper Pench Coal Company, Limited's Jatachappa coal mine	·	•	•	,		16
Abdul Karim and Brothers' Kapasara coal mine	•	•	•			16
New Beerbhum Coal Company, Limited's Joyramdanga coal mine	-•	•	•	•	•	16
Bengal Iron and Steel Company, Limited's Nooncodih coal mine .  New Beerbhum Coal Company, Limited's Joyramdanga coal mine	•	•	•	•	•	16
Equitable Coal Company, Limited's Dishergarh coal mine		•	•	•	•	16 16
Bengal Coal Company, Limited's Damodarpur coal mine		•	•		·	16
Bengal Nagpur Coal Company, Limited's Bhuggutdih coal mine .	•	•	•	•	•	16
Messrs. R. M. Pal and U. M. Pal's Rajpura coal mine  Messrs. M. L. and K. D. Laik's Hatnol coal mine	• ′	•	•	•	•	17
Assam Railways and Trading Company, Limited's Namdang coal min	14	•	•	•	•	17 17
Assam Railways and Trading Company, Limited's Ledo Valley coal 1		•		•	•	17
Permits cancelled	•		•	•	•	17
Additions to the Indian Mines Act—						
Section 21 -Establishment of Special Rules at coal mines	•	•	•	•	•	17
Section VGeneral Remarks— Health and Sanitation—						
Health and Sanitation— Assausol Mines Board of Health—						
Number of meetings		_	`.		_	17
Change in personnel of unofficial members.	•		•	•		17
Amendment to Regulation 10 of the regulations for the prever	ıtion	of sm	all-po	k in	the	
Asansol mining settlement			٠.			17

		•							1	P.
SECTION V.—GENERAL REMARKS—contd.										
Mealth and Sanitation—contd.						-				
Asansol Mines Board of Health—contd.										
Lectures on Sanitation and Hygiene continued							_			1
Investigation into Hook-Worm disease	•	•	•	•	•	•		•	•	1
Anti-malaria survey of settlement commenced	•	٠	•	•	•	•	•	•	•	1
Epidemio deseases	•	•	•	•	•	•	•	•	•	1
Jharia Mines Board of Health-				•						
Number of meetings	•	•	•	•	•	•	•	•	•	1
Epidemic Diseases Act remains in force .	•	•	•	•		•		•		1
Mugma area brought within jurisdiction of J!			Sett	loment	•	•	•	•		1
Number of cases of, and deaths from, epidemic	e giaes	608	•	•	•	٠	•	•	¢	1
EPIDEMIO DISBASES—										
Number of deaths in various provinces, from e	pidemi	c dison	ses		•				-	1
RAINFALL STATISTICS-				_						
New Jharia Water Works and Coal-fields of J	haria.	Giridil	and	Rouis	anj	•				1
					•		-	-	-	_
Mining Education -										
Report of Professor of Mining at Bengal Engi		_	oge	•	•	•	•	•	•	1
	•	•	•	•	•	•	•	•	•	1
	•	•	:		•	•	•	•	:	1
Annual Mining camp	held	by	•	•	•	•	•	•	•	1:
Change in personnel of mining instructors	•	•	•	•	•	•	•	•	•	1
Lecture in coal-fields, result of sessional exami	nation	•	•	•	•	•	•	•	•	1
1 1		•	•	•	•	-	•	•	•	•
BOARD OF EXAMINERS FOR COAL MINE MANAGES	BS' CE	RTIFIC	AT BS	_						
Personnel of Board	•	•	•	•	•	•	•	•	•	1
Number of meetings held	anted	in lieu		Inglish		ficates	•		•	1
Certificates of service granted		•		•			•			1
Result of examination for colliery managers'		ates of	com	petency	1	• `	•	•	•	1' 1!
Local Examiners, and Secretaries  Amendment of the Boards regulations, abolitio	n of th	he rule	8 207	eraing	the c	grant :	• of cer	 liñcate	s	1)
of service	•	•	,,		•	•	•	•	•	18
MINING BOARDS-										
Bengal, Bihar and Orissa and Central Province	19									20
Number of meetings held		:	:		:	:	:	:	:	21
Business transacted	•	•		•	•	:		•		20
Non-official members • • •	•	•	•	•	•	•	•	:	•	2(
MINING AND GEOLOGICAL INSTITUTE OF INDIA-										
Mombership										2
Number of meetings held		•		•	•	•	•	•		2.
Geological map of Jharia coal-field completed	•	•	•	•	•	. •	•	•	•	2: 2]
Award of Government prize	•	•	•	•	•	•	•		:	2)
•	·	Ÿ	-	•	•	•	•	•	•	
Association of Colliery Managers in India-	_									
Momhership	•		•	•	•	•	•	•	•	2; 2;
Questions engaging attention of Council . Rules for mine gates and Register of workers	in coal	I main or	•	•	•	• "	•	:	:	21
Remarks on true meridian lines in the coal-fiel	ds	•	•	•	•	•	•	•	•	21
LAND ACQUISITION (MINES) ACT, 1885-										
Number of cases disposed of under Act .	• .	•	•	•	٠.	•	•	•	•	29
OFFICIAL DUTIES—	_									
Personnel	•	•				•		•	•	22

CONTE	<b>ਪਾਰ</b> _	annold	
LUNIE	N 18-	(:/\mathfrakeria)	

														Pag
Appendi:	r I.—S	STATISTICS OF MI	NES AND M	INERAL	<b>8</b> —									
Table	No. 1.	Number of mi	nes and worl	kere and	outp	at of	Min	nerals	٠	•	•	•		23-
n	" 2.	—Analyses of fig	ures relating	z to out	put o	f con	l	•		•	•	•		38-
,,	" 3.	-Number of mis	nes opened a	nd close	d	•	•	•	•	٠	•	•		40-
70	" 4.	-Fluctuations of	foutputs				•	•	•	٠	•	•		4.
ts	" f.·	—Coal raised and	death rates			•	•	•	•	•	•	•	•	4
Appendi	x II.—	Accidents in 1	ines—					-						
Table	No. 1.	-List of fatal ac-	ridents											45
		-Fatal and serio				•		•	•	•		•		81—
**		-Fatal accidents			lacco	ordin	z to	age an	ıd sez			Ň	٠	86-
,,		-Fatal accidents					_	•	•	•	•	•	•	88
A prendix	. 111													
Prose	cutions	under the Act						•					•	89
Appendia	: <b>IV.—</b> ]	Miscellaneous-	_											
Stato	ment N	o. 1.—List of ins	nection circle	04 -			_	_						91
٠,,		2List of cert					•	•	•	•	•	•	•	91
, **	"				and	Coll	eges	appro	ved	b⊽ G	overn	ment <b>f</b>	or	
		purposes	of Rules 32	and 33	of th	e Act	;	•	•	•	•	•	•	94
99	1)	4.—Bengal En	zincering Co	llege m	ining	clas	es	•		•				95
17	**	5.—Mining Inc	struction in	Bengal :	and I	Bihar	and	Orissa	B.	•	•	•		969
29	"	6.—Regulations						•	•		•	•		98
13	n	7.—Governmen	t of India 1	Votificat	ion r	egard	ling	cancell	lation	ofn	ales g	overni		
		grant of cer					•	. •	•	•	•	•		100 — J
*1	17	8.—Particulars	to be furnis	thed und	ler S	ection	4, I	and .	Acqu	isition	ı (Mi	nes) 🛦	ct,	
		1000		_						_				101

#### APPENDIX I.

#### STATISTICS OF MINES AND MINERALS.

Table No. 1.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919.

	1		**	BER OF	New	BER OF		Δ.	VERAGE N	UMBER OF	Persons	EMPLOTE	D DAILT I	M AND AM	OUT THE	MINKS,
-		Number of mines		R81	DUE	FO THE	ŀ		Bilow	0107 <b>11D.</b>	,		Arorz	BOCKD.		
Риоченов.	District and mineral field.	under the scope of the Act.	Worked by mecha- nical power,	Not worked by mecha- pical power,	Number of mines inspected.	Number of Inspec- tions.	TOTAL OUTPUT.	Adult males.	Adult females.	Children (ander 12),	Total below ground,	Adult males.	Adult females.	Children (under 13).	Total above ground,	Grand total below and above ground,
	Lakbimpur	6	;   <b>4</b>	2	4	A.—C0	Tons.	1,661	160		1,830	636	214	58	908	2,738
Assam	Noga Hills	1	;   900	1	1	1	29,941	204	2	4	210	179	21		- 205	415
l,	Sibsagar	1	•••	1		<b> </b>	1,541	20			20	25	•••		25	45
,	Total .	8	4	4	5	9	291,134	1,885	171	4	2,060	810	235	63	1,138	3,198
(	Lozalai	1		1	***		165	20			20	15			: 15	35
Baluchistan	Quetta-Pishin	6	300	6			<b>5,25</b> 6	114	*44		114	. 25	•••		25	139
\	Sibi-Khost	6	. 3	4	<b></b>		23,703	368	•••		368	338	8	14	. 360	728
· .	Total .	13	2	11	•	•••	29,124	502	•••		502	378	8	34	400	902
	Bankura, Raniganj	, <b>2</b>	***	2	1	1	6,950	34	23	***	57	20`	16	1	37	. 94
Bengal	Birbhum "	1	***	1			1,910	20	25	**1	45	6	3		9	5-1
Ų	Burdwan ,,	213	165	48	101	181	5,768,772	18,707	11,349	215	80,271	11,280	6,598	842	18,223	48,494
	Total .	216	165	51	102	182	5,777,632	18,761	11,397	215	30,373	11,306	6,617	316	18,260	48,642

#### STATISTICS OF MINES AND MINERALS-contd.

Table No. 1-contd.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

-	,	}		er of	MINAS 11	STROP		A1	PERAGE N	UMBER OF	PERSONS	EMPLOYE	D DAILY I	BA DKA N	OUT THE	MINES.
		Number of mines	MI	E6	KIEDG LE	g ter M			BELOW	GROUND.			ABOTE	6307¥p.		<u> </u>
Province.	District and mineral field,	under the scope of the Act.	Worked by mecha- nical power,	Not worked by mecha- nical power.	Number of miues inspected,	Number of inspec- tions,	Total Outros.	Adult males.	Aduli females.	Children (under 12),	Total below ground.	Adult males.	Adult females.	Children (under 13).	Total above ground,	Grand total below and above ground.
	•				Δ.	-COAL	-concld.								4	
•	Bokaro-Ramgarl	6	2	4	1	1	Tons. 722,682	9,302	2,457	15	5,774	1,625	1,354	43	3,022	8,796
`	Hazaribagh Giridih .	. 8	. 4	4			950,045	5,468	2,629	1	8,098	2,062	779	12	2,853	10,951
Ì	Jharia .	9	5	4	8	3	176,937	492	439	10	941	402	361	25	788	1,729
÷	[Jharia .	335	178	162	123	254	11,968,981	31,097	25,676	297	57,070	23,451	12,137	1,426	37,014	94,084
ır and Orissa	Manbhum { Raniganj	97	16	81	37	60	1,033,702	8,640	2,274	33	5,947	2,803	1,823	189	4,815	10,762
	Palamau, Daltonganj .	. 1	1	444	1	. 2	63,250	265	133	24	422	251	62	35	848	770
	Sambalpur, Hingir-Rampur	. 3	1	2	·	***	45,574	360	201	-	561	258	110	***	368	929
	Sonthal Jainty	. 4	4	*** *	1	2	152,941	<b>3</b> 69	494		863	509	264	76	849	1,712
	Parganas. (Raniganj	. 3	٠ ,,,,	-8	<b>,</b> .		3,792	28	, 23	-	. 51	18	6	***	21	75
	TOTAL	466	206	260	166	322	15,117,903	45,021	34,326	980	79,727	31,379	16,896	1,806	50,081	129,808
	Chanda, Ballarpur	. 8	6	2	2	4	126,366	789	123		912	587	171	17	775	1,657
atral Provinces	Chhindwara, Pench Valley	. 12	8	4	6	6	285,356	1,552	662	56	2,370	445	275	54	774	3,141
iciai Liovinces	Narsinghpur, Mohpani Yeotmal	. 1	. 1	•••			85,299 	601 •••	384	***	985	556 3	31 	•••	587 3	1,672 3
	TOTAL	. 22	16	6	8	10	497,021	2,912	1,169	56	4,167	1,591	477	71	2,139	6,306

	u
.4	

									•									-
North-West Frontier Province.	Hazara			1	•••	1		• •••	20 	5	•••	•••	5		•••	400		6
	Jhelum			. 10		10		•••	35,845	489	26	52	567	341		<b>3</b> 3	379	946
Panjab	Mianwali			2		2		. * •••	5,822	40			40	83	·	•••	83	123
	Shahgur	.• •	• •	3		3	•••	***	5,226	53		***	53	69		•••	. 69	193
		· Te	OTAL .	- 15		15		•••	46,893	582	. 96	52	660	493	•••	38	531	1,191
,	GRAND	тотаь (С	COAL) FOR 1919 .	741	393	348	281	623	21,759,727	69,698	47,089	707	117,494	45,987	24,233	2.338	72,558	190,052
	"	OEDIN	PRE-	719	367	352	389	724	19,847,039	65,433	48,447	681	109,581	42,857	21,547	2,804	66,708	176,269
		DIFFERE	NCE .	+22	+26	4	. <b>—108</b>	<b>—2</b> 01	+1,912,688	+4,265	+3,642	+26	+7,983	+3,130	+2,686	+31	+5,850	+13,783
•						•		B.—M:	CA.	-		••						
إ	α .			45		45		·	Cwts. 5,007	639	430	97	1,16 <b>6</b>	0.4	225	93		1 +00
11	Gaya .			452	61	<b>3</b> 91	19	24	25,678	6,085	8,052	•	1	244	'	•	562	1,728
11	Hazaribagi		•	1		1			. 20,078	1	3	1,180	10,317	2,376	1,676	1,078	5,130	15,447
į /	Manbhum			1			***	***	4.	1	l		7	2	2	**1	. 4	11
11	Mongdyr	• •	• •	27	1	26		***	1,580	317	134	4	455	142	117	60	319	771
Ų	Sambalpur	• . •	• •	. 1	•••	1	''y 		15	50	25	δ	80	21	15	21	60	140
		То	TAL .	526	62	464	19	24	32,290	7,095	8,644	1,286	12,025	2,785	2,035	1,255	6,075	18,100
ŗ	Kistna		. ,	1		1	, ins		57	16	16	***	32	1	7	. 2	10	43
Mindras	Nellore	•	• •	106	18	88	***		7,858	1,601	903	117	2,801	410	410	207	1,036	8,83
U	Salem			3	<b>,</b>	. 8	•••	·	. 323	39	.,,		89	56	71	14	1	186
		To	TAL .	110	18	92			8,238	1,746	1,009		2.872	467	-	223	-	<u> </u>
		T <sub>0</sub> 1	TAL ,	<b>110</b>	18	92		<u> </u>	8,238 res for Samarsk	1,746	1,009	117	2,872	467	407	223	1,187	

### STATISTICS OF MINES AND MINERALS-voni

Table No. 1—contd.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

,			. News	ER OF		RR OF MEFECTED	•	74	VERAGE N	UMBER OF	PERSONS	EMPLOYE	D DAILY	IN AND AL	BOUT THE	MINES
		Number of min-s	<b>1</b> 11	¥25,		G TEE		•	BELOW	GRÓTED.		,	Ayove	GROUND.		
Province.	District and mineral field.	under the scope of the Act.	Worked by mechani- cal power,	Not worked by mechani- cal power.	Number of mi es inspected.	Number of inspec- tions.	Total output.	Adolt males.	Adult females.	Children (a:.der 12).	Total bel:w ground.	Adult males.	Adult females.	Children (ander 12).	Total above grou d.	Grand total below and above ground,
			,		В	.—MICA	-concld. Cwis.					    -	•		•	
sjputana	Ajmer-Merwara	37 1		37 1	***		1,079 76	28i 7	85 2	34 1	403 10	67 _ 1	2 <b>2</b> 		89 - 1	492°
	Total .	38	***	38	•••	•••	1,155	201	87	35	413.	68	22	•••	<b>9</b> 0	503
·	GRAND TOTAL (Mica) FOR 1919.  "OF PRECEDING YEAR.	674 623	80 77	, 594 548	19 58	24 60	41,683 51,572	9,132 10,894	4,740 4,353		15,310 16,814	3,320 <b>3,766</b>	2,554 2,825		,	22.662 25,592
	Distression	+51	+3	+48	59	-36	-9,889	<b>—1,762</b>	+357	-129	-1,501	. <b>—41</b> 6	371	-609	-1,423	<b>- 2,</b> 93 <b>0</b>
					С	-MANG	ANESE. Tons.									
ombay	Panch Mahals	2	2			<b>,</b>	22,510	536	312	118	996	216	53	15	284	1,280
Central Provinces	Balaghat	26 3 2 22	1  2 2	25 3  20		3	199,089 23;465 52,555 112,777	2,388 244 224 1,1 · 9	2,370 270 280 3,188	102 28 11 21	4,856 542 515 2,528	550 101 191 619	475 33 74 410	116 4 12 70	1.151 138 257 1, 99	6,007 680 712 3 427
	Total .	53	5	48	2	3	387,806	3,875	4,114	252	8,241	1,471	972	203	2,345	10,883

Madras :	Vizagapatam	4	***	4			2,778	71	46	7	124	74	49	10	133	257	
•	GRAND TOTAL (MANGANESE)	59	7	52	2	3	420,184	4,482	4,502	377	9,361	1,761	1,074	227	280,8	12,423	
	" ING TEAS.	58	.5	<b>53</b>	•••		415,357	5,390	5,160	316	10,896	1,733	1,031	193	2,917	13,643	
	Difference	+1	+2	-1	+2	+3	+4,827	003	-659	+31	-1,535	+28	+43	+41	+115	-1,420	
				·	D.	_LIME	STONE. Tons.		_			-		,		•	
(	Bilaspur	1	***	1	•	_	4,396	29	62	3	94	22	10		32	126	
Central Provinces	Jebalpur, Kaini	29	1	28			123,016	659	1,130	35	1,824	103	243	10	427	2,251	
	Total .	30	. 1	29	•••	     	137,412	658	1,1; 2	34	1,918	187	253	19	45:	2,377	
Panjab	Hoshiarpur	1	•••	1			v,428	23	***		23	25	•••	2	27	80	
	GRAND TOTAL (LIMB- STONE) FOR 1919.	81	1	30	,,,		146,840	711	1,192	38	1,941	212	253	21	486	2,427	27
	· ,, ,, OF PRECED- ING YEAR-	26	r	25	***	***	131,451	573	921	32	1,526	240	260	24	524	3,050	
	Difference .	+5		+5		·	+15,380	+138	+271	+6	+415	-28	-7	-3	-38	+377	
·			;			E SA	LT.				-					\ <del></del> 	
٠ ، (	Jhelum	2	. 1	1	•••		Tone, 154,168	419	325	56	800	72	1		73	873	
Panjub '	Mianwali	1		1			5,520	38	•••	11	49		,	]   •••		49	
	Shahpur	1	1		•••		15 277	45	31	5	81		·	<u></u>		81	. •
	GRAND TOTAL (SALT) FOR 1919.	4	2	2	•••		174,974	502	356	72	930	72	1		73	1,003	
. ,	OF PRECED- ING YEAR.	4	1	3	3	5	158,513	508	321	80	909	1		ļ·	71	980	_
•	Difference .	•••	+1	<b>—</b> I	. —3	-5	+16,431	6	+35	-8	+21	+1	+1		+2	+28	

#### STATISTICS OF MINES AND MINERALS-contd.

Table No. 1—contd.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

Province.										<b>.</b>	ER OF	None	ER OF			ERAGE N	OMBER OF	PERSONS	EMPLOYI	ED DAILY	IN AND AI	OUT THE	MINES.	
•						,	Number of mines	MI	KES.	DURIN	SPECTED G THE AB.			Brrow	GROUND.			AB <sub>0</sub> TB	GROUND.					
	Provide.	ecř.	,	Dist	trict a	and ma	ineral	field,		under the scope of the Act.		Not worked by mechani- cal power.	Number of mines inspected.	Number of inspec- tions.	Toral Surpur.	Adult males.	Adult females,	Children (under 12).	Total below ground.	Adult males.	Adult females.	Children (under 12).	Total above ground.	Grand total below and above ground.
				<del></del> -										FG			[			•				
•			. 1	Mogok			•			ز. ز			,	(s) Rul   	Carate. 88,847	) )		,					•	
				· .					•			<del></del>		(b) Sapp	hires.				<del></del>			-		
m a	٠.	•		Mogok			•			4	2	2	3	4	47,286	850	<b></b> .		850	469			469	1,319
		•	ı			-		-	•					(c) Spi	nels.		<del></del>			<del></del>				
			· i	Mogok	•	•	•	•	•	j				l	22,444	j 								
							To	FAL	•	4	2	2	3	4	158,577	850	····.		850	469			469	1,319
				GRAND	OT)	TAL	(GE	(eu	FOB 1919	4	2	2	3	4	158,577	850	***		850	469			469	1,319
		-		,,	91	•		PBE No 3	CED-	3	2	. 1			164,115	778	***		778	522		*	522	1,800
		·	•		3	Dipp	9B61	S C E		+1	***	+1	+8	+4	-5,538	+72	***	<u></u>	+72	53	•••		53	+19
	_													G.—81	LATE.									_ <del></del> _
har o	nd Ori	i588	· ·	Monghy	r .		-	-	•	5	*	. 5	104		Tons. 3,033	148	161	29	838	67			67	405
anjab				Gerdasp Gurgaor Kangra	ur 1	•	:	•	•	1 5		1 5 4	. ,,,,	***	84 2,651 5,323	6 109 1.2	***	 65	6 174 112	 35 20		 8 16	 43 68	. 6 217 180

	Total .	. 10	i	10	· ···		8,038	227		65	2:12	55	33	24		403
	GRAND TOTAL (SLATE) FOR 1919. ,, , OF PERCEDING YEAR.		***	15. 15	•••	•••	11.091 9,935	375 <b>34</b> 3	161 78	94 77	630 498	122 115	32 51	24 26	178	808
•	Difference -				,••		+1,156	+32	+83	+17	+132	+7	-19	-2	-14	: +118
						HG(	OLD.									
Bihar and Orissa	Singhbhum	1	1		•••	·   •••	Ozs. 173	59	. 17	•••	76	62	88	7	152	228
Madras	Anantapur	3	3		••••		11,018	114		***	114	329	60	51	110	654
	GRAND TOTAL (GOLD) FOR 1910, , , of preceding traf.	4	3	 1	***	***	11,191 19,916	. 173 530	17 11	•••	190 541	391 440	143 140	58 66	59 <u>9</u> 646	782 1,187
	Difference	•••	+1	-1	• •••		-8,725	857	+6	***	-351	-49	-8+		-54	-405
•					I	.—IRON	ORE.									
Bihar and Orissa	Singhbhum	2	1	1	,•••	•••	Tons. 100,210	362	291	73	726	175	80	δ	260	986
Central Provinces	Jabalpur	1,	•••	1	14.		1,112	20	55	15	90	20	10	10	40	130
Rajputana	Ajmer-Merwara	ı		1	***	·		2	•••	•••	2		• ·	•••		2
	GRAND TOTAL (IRON) FOR 1919. "" OF PRECED- ING YEAR.	4 5	1	3 4	***	***	101,322 115,890	381 482	34 <b>6</b> 358	88 72	818 912	195 523	90 67	15 7	300 327	1,118
,	DIFFERENCE	-1		,—1	'	***	—14,568	-98	-12	+16	-94	- 328	+23	+8	<b>—27</b>	121

\*Includes figures for silver.

#### STATISTICS OF MINES AND MINERALS-contd.

Table No. 1-contd. .

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

	1	i	None	IE OF	MINES IS	ER OF .		,A\	ERAGE N	CMBER OF	Personb	EMPLOYE	D DAILY	IN AND AB	OUT THE	HINES.
Province,		Number of mines	, ¥11	FPs.	A A POPIN	GTER			Below	GROUND, '		,	AVOEA	ground.		Grand total
Pedvines,	District and mineral field.	ander the scope of the Act.	Worked by mechani- cal power.	Not worked by mechani- cal power.	Number of wines inspected.	Number of Inspec- tions.	TOTAL OUTPUT.	Adult males,	Adult females.	Children (under 12).	Total below ground.	Adult males.	Adult females.	Chi'd-en (under 12).	Total above ground,	bel w and al ore ground.
					J	.—WOL	FRAM. Cwts.									
nar and Orissa .	. Singhbhum	. 1					30	9	2	•••	. 11	. 8	1		9	20
	Mergui	. 2	,,,,	2	,	•••	<b>3</b> ,055	224	•••	***	224	284	22	***	808	530
rma	Tavoy	109	4	105	6	7	54,394	4,810	27	8	4,845	3,150	240	92	8,491	8,336
•	Thaton	. n	1	• 10			630	355	75	28	458	215	130	25 .	370	828
	Total	. 122	. 5	117	6	.7	58,079	5,389	102	36	6,527	3,658	392	117	4,167	9,694
	GRAND TOTAL (WOLFBAM FOR 1919	123	5	118		7	58,109	5,398	104	36	5,538	3,666	398	117	4,176	9,714
·	, , of treced		5	109	33	81	72,189	5,376	133	50	5,559	4,279	407	133	4,810	10,378
	Diffzence .	. +9		+9	27	-74	-14,030	+22	-20	-14	-21	-613	14	-16	(113	- 661

		•		1 1	•			ì	1	ſ	1	j	.	ì	1	,	
					<b>K</b>	-Magi	ESITE.	[			1	Ì					
Medran	Salera	1	·	1	•	***	Tons. 13,013	' 221	169	361	691	60	•••	27	87	738	
	Total of placeding year .	1	<b></b>	1	1	1	5,773	105	85	131	321	26		6	33	95\$	
•	Difference		•••	· <b></b>	<b>⊸</b> 1 '	<del>-</del> 1	+7,239	+116	+84	+189	+330	+34	••.	+21	+ 55	+385	
			,									ļ					
					<b>L</b>	-CHRC	MITE.							į			
Baluchistan.	Zhob • • • •	22	***	22	•••	•••	264,467	<b>2</b> 26	•••	•••	226	53	•••	•••	53	279	31
Bibar and Orissa	Singhbhum	4		4	•••		16,876	42	51	7	100	4,7	91	15	86	186	, ,
				·												•	
	GRAND TOTAL (CERCHITE) FOR 1919.	26	409	26	224	) Jos	281,343	268	51	Ť	326	98	31	.15	139	465	-
•	p OF PERCEDING YEAR.	27	***	27	611	111	480,590	203	102	10	315	93	4	ì	98	418	•
	Difference	-1	414	1	. ***		-199,247	+ 65	-61	. —3	. +11	(	+27	+14	+41	+53	

# STATISTICS OF MINES AND MINERALS—contd.

Table No. 1-contd.

# Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

			Num	ER OF		ER OF		<b>A</b>	VERAGE N	UMBER OF	PERSONS	ЕЛЬГОАІ	ED DAILY	IN AND AI	OUT THE	Mikés.
·		Number of mines	נוע	res.	או שטם	G TER			Baron	DROUED.			Anove	GROUND.		
Province.	District and mineral field.	under the scope of the Act.	Worked by mechani- cal power.	Not worked by mechani- cal power.	Number of mines inspected.	Number of inspections.	Total outpur.	Adalt males.	Adult females,	Children (under 13).	Total below ground.	Adult males.	Adult females,	Children (under 12).	Total above ground.	Grand total below and above ground,
					М.	_COPP	ER ORE.	•				,				
	·					( ·	Tons,								,	
lihar and Oriesa	Singhbhum	1	,1		1	3	32,756	642	***		, 642	1,152	782	52	1,986	2,628
	Balachat	1		1				. 10	12	4	26	4	6	2	12	<b>3</b> 8
Central Provinces	Balaghat												. *		• • • •	
	GRAND TOTAL (Copper) FOR 1919.	2	1	1	1	8	32,756	652	12	4	668	1,158	788	54	1,998	2,666
•	" " OF PRECEDING TEAR.	3	. 1	.3	.1	. 2	3,619	198	9		207	794	312	43	1,149	1,356
	DIFFERENCE	_ı	•••	-1	•••	+1	+ 29,137	+454	+3	+4	+461	+862	+476	+11	+649	+1,319
				1	:	N.—BAI	IXITE.					<u> </u>	\	— ·		
,						ļ	Cwts.	ł	,	1 !		j	l			
Central Provinces	Jabalpur	1		11			33,640	52	<b>6</b> 8	1	121	4	•••		<u>.</u>	125
	TOTAL OF PRECEDING YEAR .	1		1		•••	23,840	45	70	1	. 116	4		•••	4	120
	Difference						+9,800	+7			+5	118	·			+5

1	1		1	1	ן ,	0.—CI	CAY.		i I				ı 1			
•	Bhagalpur • • •	. 2		2			Tons. 551	60	31		91	78	51	21	153	214
Bihar and Orissa	Manshum	. 1	, 1		<b></b>		31,381	72	56	24	152	96	80	48	204	376
Diam and Oliver	Palamau	1		1			6,274	27	13	11	51	51	31	20	108	159
· · · · · · · · · · · · · · · · · · ·	TOTAL	4	1	3			38,400	159	100	35	291	5-18 	168	80	485	779
Central Province	Jahalpur	4	2	2			60,637	7/3	571	30	1,025	48			48	1,073*
Dolhi	Delhi	1		1	•••	•••	714	8	***	•••	8	8	•		12	20
	GRAND TOTAL (CLAY) FOR 1919.	9	3	в			99,760	579	674	74	1,327	284	172	89	545	1,873
•	" ", OF PRECEDING	9	2	7	•••		91,392	318	<b>3</b> 61.	53	682	222	181	14	417	1,079
	<b>D</b> 109квинсв		+1	1	,,,		+8,368	+26t	+383	+21	+ 665	+62	-9	+75	+ 128	+793
	}					PGA	LENA.									······································
Central Provinces	Drug	1	. <b></b>	1	•••		Cwts.	. 5	10		15	5	10	.,	15	30
•	TOTAL OF PRECEDING YEAR.	1		1			60	4	10	••	14	. 2	10		. 12	26
	Difference		•••	•	•••		-10	+1	••• 1	•••	+1	+3	•••	**.	+3	+4
	•					Q.—T	IN.									· <del></del>
Biling and Origen	Hazaribagah	1	1		,	}	Cwts.	84	31	28	93	81	20	22	79	179
. (	Mergui	2	•••	2.	. ,		669	37	6		43	10	3		13	. 56
Darma .	Tuvoy	4	1	ន	•••		12,741	47	10	4	61	88		•••	88	149
· ·	Thaton	1		1		•••	601	15	10	5	30	5		•••	6	35
•	Total .	7	1	6	,,,	••	14,011	99	26	0	134	103	3		106	240
	GRAND TOTAL (Tin) FOR 1919.	8	2	в		***	14,011	138	57	37	227	134	29	23	185	412
	, , OF PRECEDING TRAR.	4	1	.B. -\		6	12,023	188	10		198	198	24	5	225	423
1	DIPPERENCE	+4"	+1	+3	-3	<b>—</b> 6	+1,988	55	+47	+37	+29	-62	+5	+17	10	-11

#### STATISTICS OF MINES AND MINERALS -contd.

Table No. 1—contd.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—contd.

			None	EE OF	MINES I	BER OF	,	.Δ'	Verage n	UMBER OF	PERSONS	EMPLOYE	D DAILY	IA AND AI	BOUT THE	Mines.
•		Number of mines	, xc	re of		FO THE			BELOW	eroupd.			ABOVE	GROTYD.		1
Province,	District and mineral field.	under the scope of the Act.	Worked by mechani- cal power,	Not worked by mechani- cal power.	Number of mines inspected.	Number of inspec- tions.	Total Curpus.	Adult males.	Adult females.	Children (under 12).	Total below ground.	Adult males.	Adult females.	Children (under 13).	Total above ground.	Grand total below aud above ground, .
· · · · · · ·		<u> </u>		<u>·</u>	I	R.—STE	ATITE.	<u> </u>			•			<u> </u>		
entral Provinces .	Jabalpur	. Š	•••	3.			Cwts. 29,041	61	40		110	17	41	11	69	179
rdras .	Kurnool	. 1		1			81	3	7		10	4	2		6	16
	GRAND TOTAL (STEATITE FOR 1919 " OF PRECED- ING YEAR	4	ļ	4		•••	29,122 61,119	67 63	53 46	2	120	21 24	43	11 7	75 76	195 187
	DIFFERENCE						——————————————————————————————————————	+4	+7	2	+9	-3	_2	+4	<b>-1</b>	+8
				s	.– FULI	LER'S E	ARTH.				<del></del>	<del></del>	•			
							Tons.				,					•
Central Provinces .	Jabalpur	• • • • • • • • • • • • • • • • • • • •		•••			247	ļ	(Lakor	ir figures i	inc3ud+ते	with those	for Jaha 	dour Lin 	ecstone)	•••
	TOTAL OF PRECEDING YEAR						218	···			•••		•••	``		***
	DIFFERENCE		·				+29				••					

က

	1	1	, , ,	1 1	1 1	T.—SIL	VEB.		. 1	1 '	1 /	1	, }	, 1	ı . l	İ	
Madras	Anantapur				•	""	Ozs. 753		(Labo	i <i>pur figures</i> I	   a included 	with the	e for Ana	intopur ge I	ત્રવ-)	•••	
,	TOTAL OF PRECEDING YEAR .					. •••	1,169						•••			<b>646</b> -	
,	DIFFSHERCE				:••	***	416	<i>′</i>						•••		100	
•					ΰ	-SAMA	RSKITE.										
Madras	Nellore · · ·						21/2		(Lal	bour ligur 	res include	d with the	ase for Ne	Hore mic	a)		
	TOTAL OF PRECEDING YEAR .				•		11	.,,	<b>.</b>		•••		 			•••	
	DIAASERGE	•••		<b>'</b>	-		+1	•••	•••				4		***	av.	
· .			,		V	GRA	PHITE.		_ <del></del>								
Rajputana	Ajmer-Merwara	4		4	<b></b>		103	12	5	•	17	4	1	<b></b>	5	23	. 3
	TOTAL OF PRECEDING YEAR	2		. 2	•••		20	8		•	8	2	. 5	3	10	18	
	DIFFERENCE	+2		+2			+83	+4	+6		+9	+2	-4	-3	. <b>−</b> 2	+4	
		·.			<u> </u>	W.—oc	Tons.										
Bihar and Orissa	Puri	1	1				- 181	12	•••		12	18		18	31	43	. •
	TOTAL OF PEECEDING YEAR .	1	1				93	10			10	12	<b>,</b> ,	7		20	<del>-</del>
•	DIFFERENCE	<b>!</b> }			,		+91	+2		,	+2	+6	***	+6	+12	+14	
	1	_ <del></del> ,			<b>x</b> .—	MOLYF	BDENITE. Cwts.								}		
Burms	Tavoy	1	•••	1			41	5			5	5	•••		5		
	TOTAL OF PERCEDING YEAR .	1		1			. 4	10	107		10	5			5	15	`, <del></del>
	DIFFERENCE	·			]		+3	-5			5	<b>i</b> ,		<b></b>	. +	-5	

### STATISTICS OF MINES AND MINERALS-concld.

Table No. 1-concld.

Number of mines regulated by the Indian Mines Act, 1901, number of workers and output of minerals, during the year 1919—concld.

PROVINCE,		i ¹ -	Nom	BER OF	- MINES I	BER OF Neprected		AV	ERAGE NU	MBER OF	PERSONS	ЕЛЬГОЛЕ	DAILY I	N AND AB	OUT THE 1	(INES.
		Number of mines under the	Mx	KES	וובטם	o yak Ma			BELOW G	BOUND.			Двотв	SEOURD.		Grand tatal
PROVINCE.	District and mineral field.	under the scope of the Act.	Worked by mechani- cal power.	Not worked by mechani- cal power.	Number of mines inspected.	Number of i-spec- tions.	Total Guiput.	Adalt males.	Adult females.	Children (under 12).	Total belon ground,	Adnit males.	Adult females.	Children (under 12).	Total at-ove ground.	Grand total below and above ground.
. •					<del>-</del>	Y AP.	ATITE.									
Sihar and Orissa .	Singhbhum	1		1			Tons.	115	65		180	30	40	•••	70	250
<del></del>	Total of Preceding Year	. 1	***	1			5,100	. 45	. 30	4	79	41	25	5	71	150
	Difference			•••			- 4.600	+70	+35	-4	+101	—11	+15	5	-1	+100
	•		1			Z.—PC	TASH.			- <del></del>						`
Parjab	J belum	•••	•••				83		(Lahou)	  - figures i: 	ncluded w	rith those.	for Jaclu	m sall, see	page 27.	)
	TOTAL OF PRECEDING YEAR		497	•••			135	***	***	•••	/	•	•••	•••	•••	•••
	DIFFERENCE					•	<b>—</b> 52				•••		•••		***	***

,		1	ſ	1	<u> </u>	AA.—B	ARYTES.		1	1	i 1			  •		
•					-		Carts.							·		
Madran .	. Kurnool	1		1		***	4,610	4		6	10	3	7	1	10	20
	TOTAL OF PRECEDING YEAR	1		1	•••	.,.	24,000	13	7	·	19	6	16	•••	55	41
	Difference				, <del>"</del>		-19,300	8	3	+6	-9	-4	-9	+1	-12	—91 —————
	GRAND TOTAL (ALL Minerals) 1919.	1,719	502	1,217	312	564	Tons. 22,760,680  Cwts. 462,708  Carats. 158,577  Troy ounces. 11,944	}93,830	59,671	3,240	156,741	58,011	29,894	4,510	92,415	249,156
	GRAND TOTAL OF PRECEDING YEAR.	1,627	467	1,160	498	879 {	Tons. 20,784,515  Cwts. 725,418;  Carate. 164,115  Troy cunces. 21,085	91,516	55,442	3,106	150,064	55,703	27,050	4,821	87,674	237,738
	Difference	+92	+35	+57	-186	-315	Tons. +1,976,165  Cwts262,7101  Carats5,538  Troy ounces9,141	+2,314	+4,229	+134	+6,677	+2,303	+2,514	-411	+4,741	+11,418

Table No. 2.

Analyses of figures relating to output of coal.

Province.	District and mineral field.	Orrhino	STOCKS,	RATERN	rge,	Tor	it,	· Drspår	CHES.	COLLIERY C.	OKSUMPTION.	COAL DE	ETAERED	Crostag	STOCKS,	COER	MYDS'	
	1759state and Humping seid,	Steam.	Slack,	Steam,	Slack.	Steam,	Slack.	Steam,	Slack.	Steam.	Black,	Steam.	Slack.	Steam.	Slack.	Hard coke,	Soft coke.	
	·	Tons.	Tons.	Tons.	Tons.	Tons.	Tons.	Tous.	Tons.	Tons.	Tons.	Tons.	Tons.	/Pa		Tons.	<b></b>	
ŗ	Lakbîmpur	1,919		259,652		261,571		254,530		8,073	•	493	-	Tons.	Tons.	164	Tons.	
lesam	Naga Hills	411	***	29,941		30,352	6 P S	29,221		229	*14	<u> </u>	4	902	••• ,	i		٠
	Sibsagar		30	. 1,541		1,541	30	1,541	••• 30		•••				,	,		
	Total .	2,330	30	291,134		293,464	30	285,292	30	8,302		493		4,377	- rés	161		
									<del></del> -	<del></del>		ļ	<u>'</u>	<b> </b> -				
Baluchistan	Loralai	10	<b></b> ,	165	•••	175	,,,,,	155	•••		;••			20	<b></b>			
Dandeniscan	Quetta-Pishin	446	987	842	4,914	788	5,901	374	4,454	45	26	' <u></u> ·		369	1,421			
į	Sibi-Khost	205	429	C,156	17,547	6,361	17,376	6,277	12,787	20	4,851			64	338		   •••	
	TOTAL .	661	1,416	6,663	22,461	7,324	23,877	6,806	17,241	65	4,877		***	463	1,759		•••	
	Bankura-Raniganj	•••	921	5,024	1,926	5,024	2,847	4,182	13	834	1,084	,		8	1,750			
Bengal	Birbhum ,,	219 270,715	12 44,025	1,434 4,819,063	476 949,709	1,653 5,089,778	48 <b>8</b> 993,734	1,879 4,092,571	19 390,776	174 127,656	469 522,676	 89,×8 <b>3</b>	12,372	100 778,663	 (7,910	 1,556	 60,614	
	TOTAL .	.270,984	44,958	4,825,521	952,111	<b>5,</b> 096,4 <b>5</b> 5	997,069	4,098,132	<b>39</b> 0,508	128,664	524,229	89,888	12,072	770,771	69,660	1,550	80,614	

C.
ē.
•

. [	Rogaro Ramgar		9,529	500,100 500,100	223,816	739,721	131,549	715,503	107,955	1,737	7,586		8,519	31,431	3,150	20	5,691	
,	Hazaribagh Giridih	13,522	3,539	726,199 150,998	25,939	192,690	227,384 36,741	101,636	100,681	1,318	56,498	20	60,199	22,5%0	4,006	45,862	9	
	[Jharis	41,692	10,803	10,007,055	1,961,926	10,988,120	2,116,358	7,411,202	5,915	8,771	8,183	150	4,627   338,195	82,183	-	1,765 222,847	100	
	Manbhum { Jharia	991,065	36,577	854,682	179,020	1,022,493	2,110,338	510,853	725,105 82,949	303,180	709,798	i	- 1	٠. ا		. !	140,240	
Bihar and Orissa	Raniganj.	784	956	53,938	9,312	54,722	10,263	49,252	6,350	55,538	69,503	ı <b>1</b>	19,356	302,741		i	101,911	
	Pulaman-Daltonganj .		29	36,750	8,924	36,650	8,953	26,397	4,123	5,112	3,841 4,801	***	***	358	47	: " ]	•••	
•	Sambelpur-Hingie Rampur	19,030	766	134,727	18,214	153,757	18.350	127,364	4,715	10,262 6,658	7,030	•••	***	14	29		100	
}	Santal-Par- Jainty .	1,456	569	3,417	375	4,573	911	3,654	·	, ,		144	•••	19,835	7,173	***		
ι	Raniganj .	1,450	. 500	3,117	• • • • • • • • • • • • • • • • • • •	9,070	911	3,034	306	181	***	•••		1,035	63\$	***	***	
			ļ	<u> </u>					· ·							·		
	TOTAL	1,242,748	211,605	12,566,734	2,551,169	13,809,482	2,762,774	9,559,289	1,041,319	422,810	867,606	490,919	431,496	3,336 <b>,4</b> 64	419,353	<b>276,75</b> 3	247,951	
	Chanda	. 821	1,621	97,741	28,625	98,562	30,246	95,010	13,917	2,546	13,683		· ,,,	1,006	2,646		•••	
ł I	Chhindwara	. 909	. 1,181	243,199	42,157	244,168	43,338	241,186	19,926	1,814	21,123			1,218	2,289		·	
Central Provinces	Narsinghpur	. 311	1,558	58,640	26,659	58,951	28,217	54,915	14,053	4,007	8,540	,		29	6,624	\  \	•••	
Į	Yeotmal					•••		***	•••		***		,	441,		•••	***	
			<u>-</u>		<del></del>	ļ <del></del>	<u> </u>		- <del></del>	<u></u>	<del></del>	<u></u>	\- <del></del> -		\	\ <del></del>		
	TOTAL	. 2,101	4,360	399,580	97,411	401,631	101,801	<b>391,0</b> 61	47,896	8,367	43,346	٠		2,250	10,559			
	<b>'</b>		,	! !									}				\	
					<u> </u>		-			- <del></del> -	<u> </u>	·			·	<del></del> -		
North-West Frontier Province.	Hazara			` 20		20	268	20		-		•••		***	•••		214	_
	Jhelum		3,009	2,398	83,447	2,398	36,456	2,138	32,937	260	1,471			•••	2,048		••• ,	
Panjab	Mianwali	.]	238	641	5,1 <del>8</del> 1	641	5,419	641	4,270	<b></b>				***	1,149			
- 11	Shabpur		1,120	228	4,998	228	6,118	228	4,937	}	87				1,044	\	,	
							,			İ	ł	<b>}</b>	1		} '	· [		
		<b> </b>			<b> </b>		<u> </u>		<del></del>	<b></b>	<del> </del>		-	<del></del>	·	-	<del></del>	•
1	TOTAL	.	4,367	3,267	43,626	9,267	47,993	8,007	42,194	260	1,558	,	<b>\</b> ` <b>:</b>	•••	4,241			
	GBAND TOTAL 1919	1,518,774	266,786	18,052,919	8,666,808	19,611,693	3,933,514	14,343,607	1,542,488	563,468	1,441,616	581,300	-140,808	4,120,31	8, 605,572	278,473	308,565	<u></u>
		1					1 1		, .	1 .	1 ' ' /		1 ' ' '	1 ' '	1		1	

Table No. 3,

Number of mines opened and closed during the year ending 31st

December 1919.

<b>;</b>	December 1919.	•	,
Province,	District,	Number of mines opened.	Number of mines
Assam	ACOAL.	<b></b>	1
			·
BALUCHISTAN	Loralai	***	1
			<u> </u>
	Total .		2
BENGAL	Bankura	•••	1
• (	Burdwan-Raniganj	13	13
	TOTAL	13	14`
	Jharis   Hazaribagh	1 •	1
	Giridih	1	***
BIEAE AND ORISSA	(Jharia Manbhum	21	30
1	Ranigunj .	9	4
	Sonthal Parganas, Jainty	•••	1
-	Total .	32	43
CENTRAL PROVINCES	Chanda	1	1
SENTEAL FROVINCES	Chhindwara	1	4
•	Total .	2	5
Panjab	Jhelum	2	•••
North-West Prontier Province	Hazara	ete .	. 1
	TOTAL (COAL)	49	. 65

Table No. 3—contd.

Number of mines opened and closed during the year ending 31st

December 1919—contd.

Province.	District.	Number of mines opened.	Number of mine closed.	
	B.—MICA.			
(	Gaya	9	19	
Bihar and Orissa	Hazaribagh	109	124	
, l	Monghyr	3	20	
	TOTAL .	121	163	
Madras	Nellore	28	13	
Rajeutana • • • •	Ajmer-Merwara	28	0	
•	TOTAL (MICA) .	177	185	
	C.—MANGANESE.	-		
a	Balaghat	•••	. 5	
CENTRAL PROVINCES {	Nagpur	1	2	
,	Total .	1	7	
Madras	Vizagapatam	1	1	
	Total (Manganese)	2	8	
	DGEMS.			
Всвиа	Magok	1	, t.,	

Table No. 3—contd.

Number of mines opened and closed during the year ending 31st

December 1919—contd.

Province.	District.	Rumber of mines opened.	Number of mine s	
Central Provinces	E.—LIMESTONE, Jabalpur	2	4	
Biwar and Orissa	F.—WOLFRAM.	***	1	
BURNA	Tavoy	14	87 4	
	TOTAL BURMA .	16	<b>6</b> 1	
	Total (Wolfbam) .	16	- 42	
Madrie	G.—GOLD.		2	
CENTRAL PROVINCES	H.—COPPER. Balaghat	1		
BIHAR AND ORISSA	I.—CLAY. Bhaghalpur	1	1	
BIMAR AND ORISSA	J.—APATITE. Singhbhum	<b>?</b> ·	1	
CERTRAL PROVINCES	K.—BAUXITE.	8395	1.	

# Table No. 3—concld. Number of mines opened and closed during the year ending 31st December 1919—concld.

Province.	District.	Number of mines of speed.	Number of mines
Madras	L.—BARYTES.	1	
NADEAB	Auracol		
	YGALENA.		•
CENTRAL PROVINCES	Drug	1	1
,	n.—tin.	·	
BIHAR AND ORISSA	Hazaribagh	1	:
BURMA	Tavoy	1	1
	Total (Tin) .	2	1
	O.—GRAPHITE.		
RAJPUTAKA	Ajmer-Merwara	. <b>i</b>	1
	GRAND TOTAL (ALL MINES) .	257	833

#### Table No. 4.

The following table shows the fluctuations in the output of the principal minerals raised from mines classed under the Indian Mines Act, 1901. The other minerals raised are gems, slate, magnesite, tin, steatite, clay, galena, bauxite, fuller's earth, silver, graphite, molybdenite, ochre, samarskite, apatite, potash, and barytes.

Year,	Coal,	Manganese.	. Mica. Limestono. Salt, Wolfram.		Gold.	Copper ore.	Iron ore.	Chromite		
	Tons.	Tons.	Cwts.	Tons.	Tons.	Cwts.	Troy ozs.	Tons.	Tons.	Cwts.
1910 .	11,367,716	468,669	21,375	81,258	119,867	18	3,260	864	17,616	6,440
1911 .	12,048,726	441,426	31,686	92,602	124,603	8,394	8,277	2,079	36,601	5,380
1912 .	14,041,368	423,464	41,660	91,784	131,233	25,401	7,269	8,984	79,383	12)
1913 .	15,486,918	637,391	43,650	71,259	138,510	27,520	11,019	3,639	98,371	68,280
1914 .	15,727,631	555,672	88,189	146,505	135,518	31,526	19,873	4,400	167,600	60,120
1915 .	16,952,480	378,172	24,063	64,179	141,770	39,432	24,320	8,010	126,617	29,300
L916 .	16,419,082	568,032	35,978	45,290	160,357	59,094	23,235	2,671	142,606	100,080
1917 .	17,326,984	497,052	35,896	82,340	152,542	79.312	22,991	20,108	178,303	345,3:9
1918 .	10,817,039	415,957	51,572	131,461	158,513	72,189	19,916	3,619	115,890	480,5:0
1919 .	21,759,727	420,184	41,683	146,840	174,974	58,109	11,191	32,756	101,322	281,343

Table No. 5.

The following table shows the amount of coal raised, the average number of persons working daily and the death-rates during the years 1910 to 1919 in respect of coal mines under the Indian Mines Act, 1901:—

							DEATH-RAYES.						
	Year.					Ygan, Amonot of of persons working daily below and above ground.				of persons working daily below and	Number of deaths below and above ground,	Per 1,000,000 tons rated,	Per 1,000 per- sons working daily below and above ground.
1910		•		11,387,716	105,285	169	. 14:05	1.52					
1911		•		12,048,720	106,598	148	12.28	1.38					
1912			.	14,044,308	121,302	157	11.17	1-29					
1913	•			15,486,318	133,042	185	11.95	1.39					
1914	,			15,727,631	137,851	145	9.22	1:05					
1915				16,352,480	145,537	166	10.12	1.14					
1916				16,410,082	143,459	169	10:20	1.18					
1917	•	•		17,926,984	153,689	103	9:41	1.06					
1918		•		19,947,039	176,269	. 197	9-93	1.12					
1919				21,759,727	190,052	. 260	11.95	1.37					

### APPENDIX II.

### ACCIDENTS IN MINES.

Table No. 1.

### List of Fatal Accidents in mines regulated by the Indian Mines Act, 1901, during the year 1919.

Ferial number.	(Fate and hour of accident,	Name and situation of mine.	Name of owner.	Name, sex, are and occupation of person killed.	Name of mineral wrought.	Cause of accident and remarks.
. 1	4th December, -7-30 A.M.	Nodiha mine, Beshergarh P. O., Bihar and Orissa.	EXPLOSION ( Nodiha Coal Co., Itd.	OF FIRE-DAMP (1 dec   Sufal Manjhi,   (m.), 35,   Coal-cutter.		Deceased, carrying an open light, ignited a small accumulation of fire damp in an unventilated gallery and was scriously burnt about the body. He died seven days later. Fire-damp had previously never been found at the colliery. Open lights were in use. Inspection and inquiry made. (See Report, page 6.)
				OF AND SIDES (170 s of roof (95 deaths).	deaths).	
2	lst January, 1-30 P M.	Charki-Khanahie mine, Ganwan P. O., Hazaribagh.	F. F. Chrestien & Co., Ltd.	Kewal Gope, (m.). 19, Driller.	Mica .	Whilst deceased was drilling a shot hole, a mass of schist, weighing about 500 lbs., fell from a height of six feet causing injuries to which he succumbed three days later.
3	let January, 2-15 a.M.	Craddock mine, Pench P. O., Central Provinces.	Central Ponch Coal Co., Ltd.	(1) Anta Gond, (m.), 36, Coal-cutter. = (2) Mintoo Gond, (m.), 32, Coolie.	Coal	The two deceased, with another man who was injured, were leading coal in a pillar-cutting area, when a mass of stone, measuring about 30'×5'×1' 0", fell from the roof killing them instantly. The injured man sustained a fracture of the leg.
4	11th January, 11-30 a.m.	Harinachak mine, Bansjota P. O. Bihar and Orissa.	Jhnria Coal Association .	Uchnb Deswali, (m.), 40, Coal-cutter.	Coal .	Deceased passed through a fence, and, whilst cutting coal in the face of a gallery, was killed by a mass of stone, 13'×7'×3" to 3" thick, which fell from the roof 8 feet above. Inspection and inquiry made.
5	12th January, 7-45 a.m.	Sripur mino, Kalipahari P. O., Bengal.	Lodua Coul Co., Ltd.	Bhadri Kora, (m.), 19, Bhaju Kora, (m.), 32, Coal-cutters.	Coal .	The two deceased and a woman, who was injured, went down an incline early in the morning before the sirdar had made his inspection, and commenced cutting coal from a 'stook' on the edge of a goaf. A piece of coal fell over from the side of the pillar, knocked out three props and released a mass of roof coal, measuring 12'0"×4'0"×0'10", which fell from a height of 9 feet. The two deceased were buried under the fall and sustained serious injuries to which they succumbed immediately. The woman sustained a fracture of the left leg. Inspection and inquiry made. (See Report, page 7.)

Serial number,	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, srx, age and occupation of person killed,	Name of mineral wrought.	Cause of accidents and remarks.
			FALLS OF ROOF AND SIDES—contd.  (a) Falls of roof—contd.		d.	
6	23rd January, 7 A.M.	Dadkha mine, Asansol P. O., Bengal.	Dadkha Coul Co.	Khagu Roy, (m.), 45, Underground sirdar; Bhudu Kol, (m.), 31, Coal-cutter.	Coal .	The deceased persons went into a goaf from which the timbers had been with- drawn. A mass of roof fell without any warning over an area of 3,200 square feet and buried them. Inspection and inquiry made.
7	26th January, 12 midnight.	Chanch mine, Chirkunda P. O. Bihar and Orissa.	Bengal Coal Co., Ltd,	Gonesh Manjhi, (m.), 33, Coal-cutter.	Coal .	Deceased was working in the face of a gallery, when a triangular mass of stone, measuring 10' 0"×4' to 5'×1' 6", fell away from a concested "slip" at a height of 6 feet. He was struck down and sustained a fracture of the right thigh, and serious internal injuries to which he succumbed one hour later. Inspection and inquiry made.
8	3rd February, 9 r.m.	Chowrassie mine, Dishergarh P. O., Bihar and Orissa.	Equitable Coal Co., Ltd	Phalu Bauri, (m.), 24, Coolie.	Conl .	Deceased was helping to withdraw timbers from a goaf when some of the props were swayed out. He tripped and fell as he was running to safety and was struck by one of the falling timbers. He sustained serious injuries and died two days later. Inspection and inquiry made.
9	11th February, 4 P.M.	Baraboni mine, Ranigunge P. O., Bengal.	Baraboni Coal Concern, Ltd.	Gopal Bauri, (m.), 60, Coal-cutter.	Coal .	Deceased went through a fonce and commenced cutting coal from the side of a pillar, when a mass of overhanging coal, measuring 15'0'x7'0'x2'0', fell upon him from a height of 7 feet. He was killed instantly. Inspection and inquiry made.
10	16th February, 1-30 A.M.	South Bulliari mine, Kusun!a P. O., Bihar and Orissa.	East Indian Coal Co., Ltd.	Kartic Singh, (m.), 22, Coal-cutter.	Coal .	Deceased passed through a fence and robbed coal from the corner of a pillar. He was killed by a mass of about two tons of roof coal which fell from a height of 7 feet. Inspection and inquiry made.
11	1st March, 9-45 A.M.	Choitodih mine, Kutrasgarh P. O., Bihur and Orissa.	Tata Iron and Steel Co., Ltd.	Kuha Manjhi, (m.), 32; Dukhan Manjhi, (m.), 29, Coal-cutters.	Coal .	The two deceased broke down a fence and began to cut coal in the face of a gallery at a fault. They were struck down by a mass of stone, weighing about two tons, which felt from between "slips" in the roof, 9 feet above. Kuha was killed on the spot, and Dukhan died in hespital a few hours afterwards. Inspection and inquiry made.
12	3rd March, 3 a.m.	Sodepur mine, Dishergarh P. O., Bongal.	Bengal Coal Co., Ltd	Ramsai Mahato, (m.), 30, Stone-cutter,	Coal .	A gang of stone-cutters were making height for an endless had age landing.  The timbers had been removed and the roof blasted down. While they were making holes in the side for the fresh timbers, a mass of stone, 12 0" ×7' 0"×1' 6", fell from the roof at a height of 9 feet, and killed deceased

13	5th March, 4-30 P.M.	North Singaran mine, Toposi P. O., Bengal.	5. Chowdhury	Tusu Mojhian, (f.), 24, Coal-carrier.	Coal .	Deceased was killed by a small piece of soal which fell from a height of about 20 feet, shortly after roof coal had been blasted. The stone struck her on the head and caused injuries from which she died five hours later. Inspection and inquiry made.
14	7th Marth, 6 a.m.	Alkusa (South) mine, Kusunda P. O., Bihar and Orissa.	Raniganj Coal Association, Ltd.	Jata Bhakta, (m.), 26, Coal-cutter.	Coal .	Deceased was employed in an area where pillars 20 feet in height were being extracted. He was driving a "split", 6 feet in height, through the lower part of a pillar, and had just holed through into the goaf, when a mass of coal, weighing about 5 cwis., fell from between "slips" in the roof. He was struck on the head and killed instantly. Inspection and inquiry made.
15	10th March, 1 a.m.	Baraboni mine, Ranigunge P. O., Bengal	Baraboni Coal Concern, Ltd.	Lakhi Manjhi, (m.), 25, Coal-cutter.	Coal .	Deceased, who was sleeping on the side of a gallery, was struck by a mass of roof coal, which fell without warning from a height of 12 feet. He was killed instantly. Inspection and inquiry made.
15	27th March,* 4 r. st.	Nandi mine, Nandi P. O., Bengal-	Nandi Coal Association .	Sambhu Manjhi, (m.), 29, Coal-cutter.	Coal .	Deceased went through a fence into a disused gallery for the purpose of recovering some coal brought down by a fall of "local" roof. A further fall occurred, part of which struck him, causing serious injuries to which he succumbed fourteen hours later. Inspection and inquiry made.
17	28th March, 4-30 P.M.	Sutikdih mine, Bhujudih P. O., Bihar and Orissa.	Sutikdih Coel Co., Ltd	Benl Banri, (m.), 36, Coal-cutter.	Coal .	Deceased was withdrawn from a gallery on account of unsound roof. He disoreyed orders and returned to the place. He was killed by a mass of stone, 12' 0"×2' 0"×1' 3", which fell from the roof 6 feet above. Inspection and inquiry made.
18	20th March, 2 a.m.	Deoghar mine, Karmatar P. O., Bihar and Orissa.	Deoghar Colliery, Ltd.	IBabu Lal Dhobs, (m.), 36, Rouf-dressing ecolic.	Coal	Deceased went over a fencing wall into a disused gallery and lay down to sleep.  A mass of shaley roof stone fell from a height of five feet, and a piece of it, measuring 2 0"×1" 0"×0" 6", struck him on the head, inflicting serious injuries to which he succumbed almost immediately. Inspection and inquiry made.
19	29th March, 9-30 P. M.	Gopalichuck West mine, Kuanda P. O., Bihar and Orissa.	Gopalichuck Coal Co., Ltd.	Lakhiram Mahate (m.), 30, Coal-cutter.	Coal .	Deceased was employed in cutting side coal in a gallery. A mass of roof coal, measuring 6'0'×4'0'×2'0', fell from the roof and killed him. Inspection and inquiry made.
20	31st March, 6-30 a.m.	Bamanband mine, Cnora P. O., Bengal.	Bamanhand Coal Co., Ltd.	Madhusudan Manjki, (m.), 36, Coal-cutter.	Coal .	Deceased presumably went through a fence into a disused gallery for the purpose of getting some easy coal. His body was found underneath a piece of stone measuring 5' 6"×1' 6"×1' 3" which had fallen from a height of eight feet. Death must have been instantaneous. Inspection and inquiry made.
21	4th April, 1 P.M.	Chattadanga mine, Mugna P. O., Bihar and Orissa.	Satya Bhusan Bancrice	Guhiram Korah, (m.), 25, Coal-cutter.	Coal .	Deceased was standing on a stool wedging down some roof coal in a gallery 10 feet in height when a piece of coal, measuring 5'4"×5'U"×2'4", fell out of a 'pot hole overhead and killed him instantly. Inspection and inquiry made.
22	7th April, 7-80 г.м.	Binadikatta mine, Samdi P. O., Bengal	Shew Narayan Marwari .	Boul Manjhi, (m.), 35, Sirdar; Suku Manjhi, (m), 32, Coal-outler.	Coal .	The two deceased went inside a fence into a disused gallery at the edge of a quarry, in order to get some easily won roal from the edge of a pillar. The weakened pillar collapsed and brought down a mass of overlying strate, which killed them instantly. Inspection and inquiry made.

Serial namber.	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, sex, ago and occupation of person killed,	Name of mineral wrought.	Cause of accident and remarks.
<del></del>				ROOF AND SIDES-	contd.	
23	12th April, 10-30 A.M.	Jharia Khas mine, Jharia P. O., Bihar and Orissa.	Standard Coal Co., Ltd.	Sukia Kurmi, (m.), 30, Coal-cutter.	Coal .	Deceased was in the act of setting a ladder for the shot-firer to examine the roof, after a shot had been fired in roof coal. Several small pieces of roof coal fell on his head and his back from a height of 22 feet, causing injuries from which he died two hours later. The shot-firer had ordered deceased not to go back to the place until further orders, as the roof sounded rather heavy. The shot-firer was in another part of the mine when the accident occurred. Inspection and inquiry made.
, 24	14th April, 10 a.m.	Manng Pok mine, Tavoy P. O., Burma.	The London Burmese Wolfram Co., Ld.	Law Lee, (m.), 45; Law Loo, (m.), 40, Miners.	Wolfram .	The two deceased were everhand stoping, against orders, in a place where work had been suspended, as it was unsafe. They were killed instantly by a heavy fall of roof.
25	17th April, 5 A.M.	Ena mino, Jharia P. O., Bihar and Orissa.	North-West Coal Co., Ld.	Agnoo Meab, (m.), 40, Coal-cutter.	Coal,	Deceased was cutting floor coal with two other men, when a piece of the roof, about 8'0" × 6'0" × 3'6", fell out from a 'slip' at a height of about 12 feet.  The overman, who was present at the time, heard the roof crack and shouted a warning. The two other men escaped, but the deceased was caught and was killed on the spot. Inspection and inquiry made.
26	25th April, 10-30 a.M.	Nyndee and North Kusunda mine, Kusunda P. O., Bihar and Orissa.	Kusunda and Nyadee Collieries, Ld.	Gendia Chamarin, (f.), 43, Coal-carrier.	Coni	A miner was dressing top coal and was standing on a stool about 6 feet high, and deceased was filling coal at the foot of the stool. A piece of coal, weighing about 80 lbs., suddenly came away. It knocked over the stool and fell upon deceased. She died on the following day. The miner was slightly injured. Inspection and inquiry made.
27	28th April, 9 r.u.	Alkusa (South) mine, Kusanda P. O., Bihar and Orissa.	Raniganj Coal Association, Lel.	Jalie Mosal, (f.), 20, Coal-carrier.	Coal	Decersed went through two fences and up to the edge of a goal, when a slab of 100f coal, 20'×6'×8', fell upon her from the roof, 6 feet above. She was killed on the spot. Inspection and inquiry made.
28	20th April, 4-30 a.m.	Bhagrand mine, Salunpur P. O., Bengal.	Borrea Coal Co., Ld	Jungi Mejhian, (f.), 21, Coal-carrier.	Coal	Deceased, in the absence of the sirdar, went through a fonce for the purpose of filling loose coal on the edge of a goaf. A fall occurred which knocked out a prop on the goaf edge. Deceased was struck on the head by the falling prop and killed instantly. Inspection and inquiry made.
. 29	30th April, G P.M.	Joymmpore mine, Jharia P. O., Bihar and Orisa.	Joynarnyan Ramjash Agurwala.	Jhoomak Singh, (m.), 44, Carpenter.	Coal	Deceased was setting a prop when a piece of coal, weighing about 40 lbs., fell on him from a height of 20 feet. He died a few days later. Inspection and inquiry made.

4
-5
$\overline{}$

30	2nd May, 12-30 p.m.	West Chandrabad mine, Jharia P. O., Bihar and Orissa.	Ramjash Agarwalla .	Manu Kora, (m.), 35, Coal-culter.	Coal	Deceased left his working place and went into a dip gallery, which had been stopped and fenced off for nearly a mouth on account of bad roof. He went through a fence and was caught by a fall of roof stone, 6'0' × 2' 6" × 2' 6", which felt from a height of 5 feet. He was killed on the spot. Inspection and inquiry made.
31	6th May, 3 A.M.	Chowrassie mine, Dishergarh P. O., Bihar and Orissa.	Equitable Coal Co., Ld.	Dhana Manjhi, (m.), 16, Coal-cutter.	Coal .	Deceased was filling a basket of coal close to a pillar in course of extraction, when a portion of the roof on the edge of the goaf broke away and swayed out some timbers. One of the falling props struck him on the head. He died two hours later. Inspection and inquiry made.
32	. 13th May, 11-30 A.M.	Damadapur mine, Nandi P. O., Bengal.	Bengal Coal Co., Ld.	Nathuni Ram, (m.), 42, Stone-cutter.	Coal .	Deceased was ordered to dress down a projecting piece of shale on the side of a gallery. He went underneath it in order to examine it prior to getting it down when it fell on to him without warning. He sustained a fractured spine and died a few hours later. Inspection and inquiry made.
33	13th May, 2 P.M.	Damarkunda mine, Chirkunda P. O., Bihar and Orissa.	Bengal Coal Co., Ld.	Makai Mejhian, (f.), 23, Coal-carrier.	Coal	A portion of the roof, close to a pillar under extraction, was found to be unsound. The sirdar fenced the place off, pending the erection of timbers. Whilst the carpenter was preparing props, a stone, measuring 4'0" × 4'0" × 4'0" × 4', fell from a height of 7 feet and struck deceased who was standing close to the fence. She was killed instantly. Inspection and inquiry made.
34	16th May, 3-30 p.m.	Choitodih mine, Katrasgarh P. O., Bihar und Orissa.	Tata Iron and Steel Co., Ld.	Dukhu Bauri, (m.), 27, Coal-cultor.	Coal	Whilst deceased was working at the face of a gallery. 12 feet wide and 6 feet high, a mass of roof stone, 80'0" × 7'0" × 3'0", fell from between two parallel 'slips.' He was killed instantly. Inspection and inquiry made.
35	17th May, 6 a.m.	Bhuggutdih mine, Jharia P. O., Bihur and Orissa.	Bengal Nagpur Coal Co., Ld.	(m.), 24, 2. Fagoo Meah, (m.), 24, 3. Bonary Meah, (m.), 25, Coal-cutters; 4. Koodia Mahatan, (f.), 25, Coal-carrier.	Coal	A gang of eight persons, entered a goaf which had been abandoned and fonced off four days before. They passed through a fence and whilst engaged in loading fallen conl, a mass of roof coal, 20' 0' × 20' 0' × 3' 6", fell upon them. The four deceased were killed instantly and one other man was seriously injured. Inspection and inquiry made. (See Report, page 7.)
<b>36</b>	22nd May, 5 P.M.	West Tetturiya mine, Katrasgarh P. O., Bihar and Orissa.	West Tetturiya Collieries, Lal.	Budloo Meab, (m.), 37, Mining Sirdar.	Coal .	Deceased was drawing timber from a place which had just been stopped on account of bad roof. He withdrew safely all the props except one, upon which a great deal of weight was thrown, but which he persisted in trying to draw in spite of warnings from his, assistant. The roof suddenly came down breaking the prop and killing deceased on the spot. Inspection and inquiry mode.
37	23rd May, 10 p.m.	Craddock mine, Pench P. O., Contral Provinces.	Central Pench Coal Co., Ld.	Hirjoo Gond, (m.), 35, Timber Mistry.	Coal	. Whilst deceased was drawing timber from a goaf, a piece of stone, measuring 14'0" × 5'0" × 0'5", fell from a height of 6 feet. A portion broke away from the main stone and struck deceased, fracturing his skull and killing nim instantly.
## E	30th May, 10 s.u.	Joyramdanga mine, Asansol P. O., Beugal.	New Beerbhum (Coal Co., Ld.	1. Ramsi Bhooian, (m.), 15, Coal-carrier; 2. Mogal Bhooian, (m.), 26, Coal-cutter.	Coal	The roof coal in a working place in a goaling district was found to be unsafe and orders were given for timbers to be set underneath it before allowing miners to work. Several props were set and in the absence of the sirder, who was measuring others, the deceased contrary to orders commenced to cut down a portion of the unsound roof. A mass of coal, measuring, 10'0" × 7'0" × 1'3", fell from a height of 12 feet on to them killing one of them outright and severely injuring the other who died within a few hours. Inspection and inquiry made.

Serial number.	Date and hour of accident,	Name and situation of mine.	Name of owner.	Name, sex, ago and occupation of person killed.	Name of mineral wrought,	Cages of accident and remarks.
			FALLS OF RO	OFS AND SIDE -con	<i>id</i> .	
		·	(a) Fall	is of roof—contd.		
39	30th May, 1-45 P.M.	Burelia mine, Chora P. O., Bengal.	Burrakar Coal Co., Ld.	Joy Kumar Roy, (m.), 38, Propping carpenter.	Coal .	Deceased was engaged in getting down a slab of stone, measuring .3' 0" × 0' 7", from the roof of an underground pump room. The stone brok away, fell from a height of 7 feet to the ground and rolled over pinning his left foot against the pump seating. He died of tetanus thirteen days later Inspection and inquiry made.
40	3rd June, 3-40 P.M.	Tikak mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ld.	Gheraw Musalman, (m.), 85, Sirdar.	Coal .	Deceased was killed by a mass of 6 tons of coal which fell suddenly from the roof at a cross road. Inspection and inquiry made.
<b>' 41</b>	11th June, 8-30 P.M.	Jamuria mine, Nandi P. O., Bengal.	Equitable Coal Co., Ld.	Jota Manjhi, (m), 30, Coal-cutter.	Coal .	Deceased, when in the act of leading a basket with coal, was struck by a mass of roof coal, measuring 8'0" × 3'0" × 3'0", which fell without warning from a 'slip' at a height of 9 feet. He was killed instantly. Inspection and inquiry made.
42	13th June, 3-3(· A.M.	Akhalpur wine, Nandi P. O., Bengal.	Hurriladih Coal Company, Ld.	Lakhi Mejhiau, . (f.), 30, Coal-carrier.	Coal	Some miners were engaged in cutting roof coal on the edge of a large goat. The roof in the goaf came on weight', swayed out aixly props, and releases a mass of roof stone. Deceased was trapped under the fall before she could escape and was sufficiented. Inspection and inquiry made. (See Report, page 8.)
43	16th June, 11 A.M.	Bhutgoria mine, Jamadoba P. O., Bihar and Orissa.	Aldih Coal Company, I.d.	Jhagroe Mainto, (m.), 35, Prop setter; Sukhoe Manjhi, (m.), 21, Coal-cutter.	Coal	The deceased Jhagroo, a prop setter, although warned not to do so, was sitting under some bad roof stone, preparing timber and the deceased Sukhoo a coal cutter, was sitting near him. A slab of stone, about 18'0"×5'0' × 0'8", fell suddenly from a height of 7 feet, killing both the deceased instantly. Another man was injured. Inspection and inquiry made.
41	17th June, 4-30 P.M.	Jamdiha mine, Mohoda P. O., Bihar and Orissa.	Jamdiha Coal Company	Ali Baurin, (f.), 30, Coal-carrier.	Coal .	Deceased removed a fence and entered a gallery which had been stopped and fenced on account of bad roof. Whilst she was leading slack coal, a piece of stone 6'0" × 3'0" × 1'6" fell from a height of 7 feet, killing her instantly. Inspection and inquiry male.
45	23rd June, 10 P.M.	Tikak mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ld.	Amaram Gharty, (m.), 25, Coal-carrier.	Coal .	Whilst carrying a basket of coal from a "chamber", 80' 0" × 20' 0" × 7' 0" deceased was killed by the sudden fall of about 2 tons of coal from the roof.
46	2nd July,	Narsamuda mine, Asansol P. O., Bengal	Sitarampur Coal Company, Ld.	Tioi Bantin, (f.), 13, Bailer.	Coal .	Deceased was one of six women who were bailing water out of a dip gallery. A mass of shale, measuring 10' 0" × 6' 0" × 0' 0", broke away from the roof at the entrance to the gallery and struck deceased killing her instantly. Inspection and inquiry made.

Deceased entered a working place whilst it was temporarily stopped for timbering, and, whilst the miners and their leaders, of whom she was one, were sitting in a gallery near by, waiting for the carpenter to put up timber, some roof and stone, about 5' 0' × 2' 6" × 1' 0", fell out at some 'slips' from a height of about 7 feet. She sustained injuries to which she succumbed 5 days later. Inspection and inquiry made.	٠
Deceased was standing on a stool, 8 feet high, cutting an ironstone nodule out of roof coal when his pick glanced off and he over balanced himself and fell off the stool. The nodule which he had released also fell a moment afterwards and struck him on the back of his head killing him instantly.  The nodule was 2'0" × 1' 6" × 1' 3" and weighed about 400 lbs. It foll from a height of 14 feet. Inspection and inquiry made.	
Deceased, whilst carrying a basket of coal along a travelling road, was struck by a piece of coal, 4'0" × 2'0" × 0'10", which fell from the side of a pillar at a height of 14 feet. She was killed instantly. Inspection and inquiry made.	
Deceased, contrary to orders, went through a fence and commenced to rob coal from a wedge shaped 'stook', 8' 0" × 1' 6" × 11 feet high. The 'stook' collapsed and deceased was struck by the falling coal before he could escape. He died from his injuries three days later. Inspection and inquiry made.	,
Deceased was loading into a basket some coul, robbed from the bottom of a pillar, when a nodular piece of coal, weighing about 3 0 lbs., fell from the roof at a beight of 13 feet and struck him on the back fracturing his spine. He died shortly after. Inspection and inquiry made.	0
Deceased was picking up coal in the face of a gallery, when a piece of shale, measuring 6 0"×8" 0"×2" 0", fell without warning from the roof at a height of 7 feet and struck her, killing her instantly. Inspection and inquiry made.	
The deceased were instructed to dress down some overhanging coal in a galiery. One of them, contrary to orders, commenced undercutting at the side of a pillar, beneath the overhanging coal. He thus released a mass of roof coal, measuring 5'0'×9'0"×8'0", which fell on to him from a height of 6 feet, killing him instantly. His companion, on hearing the coal breaking away, attempted to drag him into safety and was himself struck by the fall and sustained serious injuries to which he succumbed two hours later. Inspection and inquiry made.	
Whilst tubs were being pushed in a gallery, 12 feet wide and 8 feet high, one of the tubs knocked out a prop and brought about a fall of roof stone, 1'6" thick over an area 29 feet long and 8 feet wide. The two deceased were killed instantly, one other man was seriously injured and two others were slightly injured. Inspection and inquiry made.	
Deceased was filling a basket of coal close to a pillar in course of extraction when a piece of overhanging shale, measuring 2'6"×1'6"×0'4", fell from a height of 6 feet and struck him. Ho sustained serious injuries and died on the following day. Inspection and inquiry made. (See Report, page 7.)	

on the following day. Inspection and inquiry made. (See Report, page 7.)

. Deceased entered a working place whilst it was temporarily stopped for timber-

40 51 I 3rd July.

4th July,

6 A.M.

11th July,

12th July,

30th July,

8-30 A.M.

6th August.

11th August.

2.30 P.M.

1st September,

2nd September,

1 P.M.

10 A.M.

11-30 P.M.

5-30 P.M.

12 noon.

12 midnight.

Central Kurkend Coal | Chuni Kaharin,

Bengal Coal Company, Duli Mejhian.

Company,

Company, Ld.

Ld

Bengal

Ld.

Bongal Ld.

Motiram Coal Company

Coal

New Beerbhum Coal Co.,

Chatabar Colliery, Ld.

Coal Company,

New Tetturiva Coal Co.,

Nodiha Coal Co., Ld.

(f.), 43,

Coal-carrier.

Manarath Roy,

Coal-cutter.

(f.), 28, Coal-carrier.

Jagu Meah.

(m.), 42,

Coal-cutter,

Dhona Manjhi,

Coal-cutter.

Noni Mejhian.

Coal-currier.

Bhakta Manihi.

Hopna Manjbi,

Manshi Dosadh.

Line coolie.

Budhon Manjhi,

Coal-carrier.

(m.), 12,

(m.), 26,

Gan loo Teli, (m.), 45, Bailing coolie,

(m.), 27;

(m.), 28, Coal-cuiters.

(f.), 10,

(m.), 40,

(m.), 40,

Central Kurkend mine,

Bihar and Orissa.

Kusunda P. O., Bihar and Orissa.

Sodepur (Outerop) mine,

Sitarampur P. O.,

Bengal.

Damudapur mine,

Nandi P. O.,

Bengal.

Baraboni mino,

Bengal.

Chatabar mine,

Chanch mine,

Chirkunda P. O.,

Now Totturiya mine,

Katrasgarh P. O.,

Nodiha mine.

Dishergarh P. O.,

Bihar and Orissa.

Bihar and Orissa.

Bihar and Orissa.

Mugma P. O.,

Bihar and Orissa.

Agangol P. O.,

Knannda P. O.,

Kirkend mine.

Coal

Coal

Coal

Coal

Coal .

Coal .

Coal

Coal .

Coal .

	Serial number,	Date and hour of accident.	Name and situation of mine,	Name of owner.	Name, ser, ace and occupation. of person killed.	Name of mineral wrought,	Cause of accident and remarks.
	<b>s</b> (		,	_	COOF AND SIDES—confalls of roofcontd.	nid.	
	<b>56</b>	7th September, 12-30 P.M.	Dishergarh mine, Dishergarh P. O., Bengal.	Equitable Coal Co., Ld.	Patu Maharaj, (m.). 48, Underground Sirdar; Megna Napit, (m.). 38, Line mistry.	Coal	The deceased were engaged in erecting a timber cog on a hankage incline when a mass of roof coal, about one ton in weight, fell without warning from a height of 14 feet. They were struck by the falling coal and sustained serious injuries to which they subsequently succumbed. Inspection and inquiry made.
• .	<b>67</b>	10th September, 1 A.M.	Nandi mine, Nandi P. O., Bengal.	Adjai Coal Company, Ld.	Choti Suki Mejhian, (f.), 12, Coal-carrier.	Coal	Deceased and four other women were leading fallen roof coal in a gallery when a mass of shale, measuring 14'0"×6'0"×0'8", fell on to them from the roof at a height of 11 feet. Deceased died one hour later as a result of her injuries. The others escaped with minor injuries. Inspection and inquiry made.
	68	25th September, 2-15 P.M.	Nodhia mine, Dishergarh P. O., Bihar and Oriesa,	Nodhia Coal Co., Ld.	Helu Bauri, (m.), 36, Protap Bauri, (m.), 28, Panu Bauri, (m.), 50, Kangal Mullick, (m.), 40,	Coal	The last pillar of a panel was being extracted in a seam having an inclination of 24°. Five miners and three coal-carriers were at work in the place. A mass of 'local' roof, 2 feet in thickness, broke away without warning from a height of 7 feet, completely swayed out the timbers, and buried the deceased. Subsequently a further fall occurred which prevented the rescue party from saving those who were not killed outright by the first fall. Inspection and inquiry made. (See Report, page 8.)
					Coal-cutters; Purna Mullickain, (f), 35, Kumoda Mullickain, (f), 16, Nuri Mullickain, (f), 48, Coal-carriers.		
•	<b>B</b> 9	30th September, 11-80 A.M.	Murulidih mine, Mohuda P. O., Bihar and Orissa.	Bengal Coal Co , Ld	Harkoo Napit, (m.), 22, Timbering coolie,	Coal , ,	Deceased was cutting a hole for a prop to be set under some shaley coal when some of this band, about 8' x 4' x 3" thick, auddenly fell off at a 'slip' from a height of 6 feet. Some of the pieces struck him on the head and fractured his skull, killing him instantly. Inspection and inquiry made.
	60	7th October, 5-80 r.m.	Rampur mino, Jheresguda P. O., Bihar and Orissa.	Hingir Rampur Co., Ld.	Birato Gandain, (f.), 35, Tub loader,	Coal , .	Deceased entered a gallery immediately after a shot had been fired. She was struck by a fail of roof, 6' 0"×3' 0"×1' 0", and succumbed to her injuries two hours later. She was one of a gang of loaders that had been warned by the shotfirer not to enter this gallery until the roof had been

Ċ1

۰	٠,
3	•
r	٠.

				_	•		
	61	8th October, 3-30 A.M.	Kendwadih mine, Kusunda P. O., Bihar and Orissa.	East Indian Coal Co., Ld.	Ram Manjhi, (m.), 20, Coal-cutter.	Coal .	Deceased and another coal-cutter were employed in cutting roof coal in a gallery 11 feet high. Whilst they were filling coal into baskets, a mass of coal and shale, weighing about 13 cwt., fell upon them. Deceased died a few hours later. The other man was seriously injured. Inspection and inquiry made.
	62	17th October, 3 a.m.	Rajhara mine, Bajhara P. O., Bihar and Orissa.	Bengal Coal Co., Ld.	Jhouria Noonia, (m.), 16, Coal-cutter.	Coal . '.	Deceased left his proper working place, and, breaking down two fences, went into an area of pillars which had been fenced off some months before. He began cutting coal from the side of an old pillar and brought about a fall of roof stone and side coal from a height of 9 feet. A portion of this fell upon him and killed him instantly. Inspection and inquiry made.
•	63	20th October, 1 P.M.	Sijua mine, Sijua P. O., Bihar and Orissa.	Tata Iron & Steel Co., Ld.	Badar Ali, (m.), 45, Coal-cutter.	Coal .	Deceased passed through a fence and was robbing coal from the corner of a pillar. This brought about a fall of roof stone, nearly a ton in weight, from a height of 9 feet. He was killed instantly. Inspection and inquiry made. (See Report, page 7.)
	64	1st November, 12-30 г.м.	Sudamdih mine, Bhujudih P. O. Bihar and Orissa.	Sudamdih Coal Co., Ld.	Kurjon Roy, (m.), 36, Coal-cutter.	Coal .	Deceased left his working place and, passing through a fence, entered an area of disused workings. Whilst he was robbing coal from a pillar, an area of roof stone, measuring 12' 0"×12' 0"×1' o", fell upon him from a height of 15 feet. He died shortly after. Inspection and inquiry made.
,	65	4th November, 7 a.M.	Nandi mine, Nandi P. O., Bengal.	Adjai Coal Co., Ld. ,	Lafar Mahato, (m.), 32, Carpenters' Coolie.	Coal	Timbers were being withdrawn on the edge of a goaf when a fall of roof occurred inside the goaf. A piece of stone rolled down and knocked out one of the props which struck the injured man before he withdrew to safety. He sustained serious injuries to the skull from which he died two days afterwards. Inspection and inquiry made.
		Oth November, 9-45 A.M.	Lodna mine, Jharia P. O., Bihar and Orissa.	Lodna Colliery Co., Ld.	Gonesh Turi, (m.), 48, Timber-man.	Coal .	Whilst deceased was taking out timber, preparatory to dropping roof coal, he was partly buried by a mass of roof coal, which fell upon him from a height of 6 feet. He succumbed to his injuries a few hours later. Inspection and inquiry made.
	67	12th November, 9 A.M.	Khas Jayrampur mine, Jharia P. G., Bihar and Orissa.	Khengarji Trikoo and Co.	Ram Manjhi, (m.), 45, Miner's Sirdar; Bojnath Kamar, (m.), 35, Coal-catter; Rasmi Kamin, -(f.), 20,	Coal	A miners' sirder, with two coal-cutters and two coal-carriers, entered a fenced off goaf, from which the timber had been drawn the day before, in order to steal some fallen coal. An overman and a sirder finding them there, went to call them out. A fall of roof coal and stone, about 30'0" × 30'0" × 3'0" thick occurred, killing four of these persons and seriously injuring two others, one of whom died the next day. Inspection and inquiry made.
					Mani Manjhian, (f.), 25, Coal-carriers; Sona Manjhi, (m.), 46, Sirdar;		
• •					Kadru Manjhi, (m.), 20, Coal-cutter.		
,	<b>68</b>	21st November, 9-40 A.M.	South Bulliari mine, Kusunda P. O., Bihar and Orissa.	East Indian Coal Co., Ld.	Kub Lal Mosal (m.), 40, Head fitter.	Coal	Deceased was levelling an iron girder at the inset at the bottom of a shaft, when a piece of roof stone and coal, 7'0"×1'6"×5'0" thick, fell from the lip of the shaft, 8 feet above, and killed him instantly. Inspection and inquiry made.
_			j '	<u> </u>		<u> </u>	

. . .

## Fatal Accidents, 1919—contd.

erial mber,	Date and hour of accident,	Name and situation of mine,	Name of owner,	Name, sex, age and occupation of person killed.	Name of mineral wrought,	Cause of accidents and remarks,
		<del></del>	FALLS OF RO	OF AND SIDES-con	id.	-
			(a) <b>F</b> a	lls of roof—concld.		
69	6th December, 7-30 A.M.	Salarwal mine, Pind Dadan Khan P.O., Punjab.	Ishar Das Kspur and C, Bevan Petman.	Babadur, (m.), 28, Carpenter.	Coal .	Whilst engaged in timbering, deceased was struck by stone falling from the reat a 'slip'. He sustained injuries which terminated fatally three mont later.
70	17th December, 2-30 A.M.	New Kessurgurah mine, Nowagarh P. O., Bibar and Orisea.	New Kessurgnrah Coal Co., Ltd.	Chandi Manjhi, (m.), 35, Coal-cutter,	Coal	Whilst two coal-outters were sitting down at rest near their working galleria slab of shale, 2'×1' 6"×6" thick, fell upon them from the roof; at a heig of 6 feet. Deceased sustained injuries to the leg and thigh which resulted death two days later. The other man escaped with a severe out on the thigh Inspection and inquiry made.
<b>71</b>	28th December, 2 P.M.	Thitkado mine, Tavoy P. U., Burma.	Osman Mustikhan & Co	Bijar, (m.), 50, Coolis.	Wolfram	Deceased was killed by the collapse of a tunnel while he was examining to vein.
			(b) Falls of side	(75 deaths).		<u>.</u>
72	1st January, 2-30 P.M.	Gajarmara mine, Hazaribagh P. O., Bihar and Orissa.	Prithir Raj	Sheikh Tanu, (m.), 35, Minor; Sukra Bhuiya, (m.), 16, Sugia Jolahin, (f.), 24, Stone-carriers,	Mica .	Whilst twelve persons were at work in the bottom of a small quarry, 28 f. deep, a mass of soft schist. 14 0"×8" 0"×3" 6", fell upon them from overhanging side. They were killed on the spot. Inspection and inquimade.
73	3rd January, 8-15 A.M.	Tirap mine, Margherita P. O., Assam.	Assam Railways and Trad- ing Co., Ld.	Eee Hin Fat, (m.), 42, Baska Wallah,	Coal	Deceased was killed by a fall of side coal in an opening. About two tons to from an unseen 'slip.'
74	10th January, 12-15 p.m.	Chaudametta mine, Pench P. O., Central Provinces,	Pench Valley Coal Co., Ld.	Harilal Mansa, (m.), 23, Stone-cutter,	Coal .	Deceased was killed by a mass of 14 cwts. of shale, which fell from the cof a sinking shaft, at a height of 8 feet from the bottom.
76	18th January, 3 a.m.	Fularibad mine, Jharia P. O., Binar and Orissa.	Khas Jharia Coal Co.	Guru Charan Kora, (m.), 42, Coat-cutter,	Coal	Deceased was one of a gang of coal-cutters engaged in extracting a pillar 14 fee in height. Hearing a slight noise he looked upwards, and a piece of coalbout one pound in weight, fell from the top of the pillar and struck him to the nose. He became unconscious, but recovered and was able to walk of the mine unaided. He died some 12 hours later. Inspection and inquinted.

Ç

C	
¢	
	č

70	25th January,	Widnes mine, Tavoy P. O., Rurms-	High Speed Steel Alloys Mining Co., Ld.	Ah. Chu., (m.), 20, Coolie.	Wollram	Deceased was killed by a fall of side, 3' 6" × 10" × 5' 6" (deep), which fell from the overhanging wall of a lode and broke his back.
77	26th January, 5 a.m.	Sudreadih mino, Nowagarh P. O., Bihar and Orissa.	Jainarain Ramjash, Agarwalla.	Jangli Roy, (m.), 35, Sirdar.	Coal .	Deceased broke down a fence and, whilst engaged in robbing coal from a pillar was struck down by a mass of coal, weighing some 10 tons, which fell from the roof and side at a height of 10 feet. His skull was fractured and he died 5 hours later. Inspection and inquiry made.
78	1st February, 5 r.m.	New Kessurgurah mino, Nowsgarh P. O., Bihar and Orissa.	New Kessurgurah Coal Co., Ld.	Charan Manjhi, (m.), 34, Coal-currier.	Coal .	Deceased was employed in corrying coal cut from a bench of roof coal, 7 feet thick, in a gallery already 8' high. Whilst the miner was cutting coal, the deceased, unknown to him, began to load a basket below. About 1 cut. of coal fell upon deceased causing injuries to which he succumbed six hours later. Inspection and inquiry made.
79	oth February, 9 r.m.	Bullisri mine, Jamsdoba P. O., Bihar and Orissa.	Enst Indian Coal Co., Ld.	Kharu Ghatwal, (m.), 16, Coal-loader.	Coal .	Deceased and another coal-cutter were employed in cutting a bonch of roof coal 3 feet thick, in a gallery 9 feet high. About 6 cwts. of coal fell from the side at a beight of 10 feet. Deceased sustained an injury to the spine which proved fatal within two hours. Inspection and inquiry made.
80	14th February, 8 4.28-	Hpaungdaw mine, Tavoy P. O., Burma.	The High Speed Steel Alloys Mining Co., Ld.	Yup Chan, (m.), 34, Tributer.	Wolfram	Decoased, who was a tributor, was working in an open out, against the express orders of his foreman. During a heavy shower of rain, which loosened the ground, about a ton of earth fell on him from the side of the open out Ho was killed on the spot. Inquiry held.
81	22nd Fobruary, 4 P.M.	Tagu Mine, Tagu mine P. O., Morgui, Burma.	E. Ahmod	Lock Taung, (m.), 60, Miner.	Wolfram	Deceased was killed by a fall of side in an open out.
82	22nd February, 4-15 mm.	Fularibad mine, Jharia P. O., Bihar and Orissa.	Khas Jharia Coal Co.	Balo Kora, (m.), 94, Cont-cutter.	Coal .	Four coal-cutters were engaged in extracting a pillar in a coal scam, 14 fee thick. A rib of coal had been left unworked to keep back fallen stones lying in the "goaf." A massive slah of roof stone rolled down against the rib broke through it, and kneeked out three props. One of the props struct decessed on the head and killed him on the spot. Inspection and inquiry made.
83	23rd February, 12-30 P.M.	Ramnagar mine, Kulti P. O., Bengal.	Bengal Iron & Steel Co., Ld.	Jitoo Kol, (m.), 48, Amoya Kol, (m.), 86, Coal-cutters; Sujiya Kolia, (f.), 40, Coal-carrier.	Coal	The three deceased left their working place in a quarry and went to cut in another place. They were killed by a fall of side coal, 9' U"x1' U x2' U', which fell from a neight of 10 feet. Inspection and inquiry made.
84	26th February, 9 P.M.	Bhalgora mino, Jharia P. O., Bihar and Orissa.	Bhalgora Coal Co., Ld.	Radha Kanu, (m), 40, Coal-carrier.	Coal	A pillar of coal, 30 feet square and 25 feet high, was under extraction. The first out was being taken from a platform fixed near the roof. Some of the coal-cutters, however, commenced to rob coal from another side of the pilla near the floor. A mass of 8 tens of coal fell from the side, at a height of 10 feet. Deceased was struck by the coal and killed on the spat. Inspection and inquiry made.
85	11th March,	Tikak mine, Margherita P. O.,	Assam Railways & Trad- ing Co., Ld.	Lanting Chainaman, (m.), 98,	Coal	. Whilst loading a tub deceased was struck by a fall of clay band. He succumbed to an attack of pneumonia 11 days later.

.

	Serial ramber,	Date and hour of accident,	Name and situation of mine,	Name of owner,	Name, sex, age and occupation of person killed,	Name of mineral wrought.	Cause of accident and remarks.
				· ·	OOFS AND SIDE-	contd.	
•			'	(b) Faile	s of side—contd.		
	. 86	27th March, 6-30 A.M.	Joyrampur mine, Jharia P. O., Bihar and Orissa,	Jainarain Rawjash Agar- walla.	Sadhram Chamar, (m.), 40, Coal-cutter; Jhilat Chamarin, (f.), 35, Coal-carrier.	Coal	Deceased were employed in a mine where pillars, 22 feet in height, were being extracted. They passed through a fence and whilst cutting and loading coal there, were struck down by a mass of some 4 tons of coal, which fell from a height of 18 feet. They were killed instantantly. Inspection and inquiry made.
	87	29th March, 9 A.M.	Khas Jharia mine, Jharia P. O., Bihar and Orissa.	Jogannath Ramjash Agar- walla.	Nando Lul Chamar, (m.), 36, Miner's Sirdar.	Coal .	Deceased went through a fence into an unused gallery, and whilst he was there, a mass of some 18 tens of coal fell from the corner of a pillar, 35 feet high. He sustained injuries to which he succumbed about an hour later. Inspection and inquiry made.
	88	24th April, 1 P.M.	Wagon mine, Tavoy P. O., Burma.	Wagon Pachanng Wolfram Mines, Ld.	Ah Yon, (m.),29, Miner.	Wolfram .	Deceased was killed instantly by a fall of earth from the side of an excavation, from a point fifteen feet above where he was working.
•	89	9th May, 11-30 A.M.	Derichoung mine, Tavoy P. O., Burma.	Messrs. Tata Sons, Ld.	Bigan, (m.), 35, Mine Coolie.	Wolfram .	Deceased was instructed to dislodge a large boulder which was hanging from the lode. He appears to have seen some wolfram in the lode, below the boulder, and attempted to get it. In doing so, the boulder fell on him, from a height of 6 feet and killed him.
	<b>90</b>	11th May, 1 P. M.	Het Kantra mine, Bhojudih P. O., Bihar and Orissa.	Govinda Chandra Bose .	Konti Mallik, (f.), 25, Coal-carrier.	Conl :	Deceased was employed in a quarry. She passed through a fence and entered a disased part of the quarry. A large fall of side occurred and she was buried beneath it. Her body was recovered a month later. Inspection and inquiry made.
•.	91	13th May, 1-45 P.N.	Adlajhari mines, Bharweli P. O., Central Provinces.	Khan Bahadur Byrawji Pestuvji.	1. Chotoo Koli, (m.), 15, 2. Lachman Lohar, (m.), 25, Earth-cutters; 3. Sona Lohar, (f.), 23, 4. Goneshi Gond, (f.), 30, Carriers.	Manganese .	The four deceased and two other persons were ordered to dress down a dangerous overhanging portion of the foot-wall in an open cast mine. In the absence of the mate, they went underneath it and were engaged in getting ore when a portion of the foot-wall, 6 feet in height, broke away and fell over on to them. Lachman Lohar and Sena Lohar were killed on the spot and Chotoo Koli and Goneshi Gond died on their way to Hospital. The two other persons were injured. Inspection and inquiry made.
	02	14th May, 6 P.M.	Benahir mine, Jharia P. O., Bihar and Orissa.	Standard Coal Co., Ld.	Ramdhari Misir, (m.), 36, Coal-cutter.	Coal	Deceased was standing on a ladder and dressing the side of a pillar. 27 feet in height. Some of the coal which he dislodged fell upon and broke the ladder, He fell to the ground and was killed instantly. Inspection and inquiry made.

•	Ů
	•

93	10th May, 2 r.m.	Fadaqk mine, Tavoy P. O., Burma.	Tata Sons, Ltd.	Balli, (m.t, 35, Coolie.	Wolfram .	Deceased was killed in an open cast working by a fall of boulders, which were probably loosened by heavy rain. Another man sustained injuries which necessitated the amputation of his leg.
94	23rd May, 10 A.M.	Kalonta mine, Tavoy P. O., Burma.	Tavoy Concessions, Ltd.	Sardar Khaut, (m.), 45, Coolie.	Wolfram .	Deceased was killed by a fall of half a ton of earth from the side of an open- cut, 5 feet above him.
95	24th Mny, 2-30 P.M.	Merwera (Plots Nos. 1147 and 1150) mine, Katni P. O., Central Provinces.	Thakur Rampiwas Sinha	Kuser, (m.), 65, Labourer.	Limestone .	Deceased was sitting by the side of a quarry where blasting operations had previously been carried out. About 4 owts. of earth, which had apparently been loosened during the blasting, came away, from a height of 3 or 4 feet, and killed him.
98	20th May, 11 A.M.	Loyabad mine, Bansjora P. O., Bihar and Orissa.	Barakar Coal Co., Ld	Jito Bouri, (m.), 30, Sinker.	Coal	Deceased, with nine other sinkers, was engaged in dressing the aides of a sinking shaft. A piece of stone, weighing about 10 lbs., fell from the side of the shaft and struck him on the head, killing him instantly. Inspection and inquiry made.
97	31st May. 8-30 a.m.	Bamboni mine, Asansol P. O., Bengal.	New Beerbhum Coal Co., Ltd.	Birdhan Manjhi, (m.), 27, Coal-cutter.	Coal	Deceased under out the side of a pillar. A mass of coal, measuring 10' 3"×8' 4"×3' 3", broke away from a 'stip' and fell over on to him, killing him instantly. Inspection and inquiry made.
08	4th June, 8-30 a.m.	Kurhurbaree mine, Giridih P. O., Bihar and Orissa.	East Indian Railway Company.	Tilki Kolin, (f.), 14, Coal-carrier,	Coal	Deceased passed through a fence into an area of disused workings. She was struck by coal falling from the side of a pillar, and sustained injuries to which she succumbed shortly afterwards.
90	4th June, 1-30 p.m.	Jamaldi mine, Kulti P. O., Bengal.	New Beerbhum Coal Co., Ltd.	Chandra Bauri, (m.), 35, Trammer.	Conl	Deceased with a companion was sitting down, sheltering from the sun, at the bottom of a quarry when a portion of the side, which overhung slightly, broke away and fell upon him, from a height of 5 feet, killing him instantly. His companion escaped with a few minor injuries. Inspection and inquiry made.
100 ·	8th June, 4 a.m.	Sitalpur mine, Sitarampur P. O., Bengal.	Bengal Coal Co., Ltd	Gopal Manjhi, (m.), 30, Coal-cutter.	Coul	Deceased was found lying under a fall of 2\frac{1}{2} tons of side coal which occurred in a disused and fenced gallery. He sustained serious injuries to the left arm and foot and died five days later. Coal had been robbed from the side of the pillar where the fall occurred. Inspection and inquiry made.
161	0th June, 2 r.m.	Paonin mine, Dongri P. O., Contral Provinces.	Central Provinces Pros- pecting Syndicate, Ld.	1. As oo,	Manganese .	While coolies were removing an old dump of boulder earth, a portion of the dump, measuring 14'0" × 5'0" × 8'6", fell away. The three deceased were buried under the fallen earth and killed.
102	11th June. 7 r.m.	Alkusa South mine, Kusunda P. O., Bibar & Orissa.	Rancegango Coal Association, Ltd.	Bhatto Rayani, (m.), 30, Coal-cutter.	Coal	Deceased left his working place and passing through a fence, began to rob coal from the corner of a pillar. A mass of coal, 9' 0"×6' 0"×2' 0", fell from the corner of a pillar, 20 feet high, and killed him on the spot. Inspection and inquiry made.
103	22nd June, 8 a.m.	Jambad (East) mine, Chora P. O., Bungal.	East Jambad Coal Concern	Muchiram Manjhi, (m.), 35, Coal-outter.	Coal	Deceased broke down a fonce and wont into a disused gallery to rob coal from the side of a pillar. A mass of side coal, weighing about 2 tons, foll ever and a portion of it struck him. He died eighteen hours later of heart failure. Inspection and inquiry made.

-	Takas Mondonis, 1010-00mm							
Serial number.	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, sex, age and occupation of person killed,	Name of mineral wrought.	Cause of accidents and remarks,		
		-	FALLS OF	ROOFS AND SIDE-	contd.			
		}	(b) Fal	ls of side—contd.	•			
104	27th June, 3 a.m.	Toposi mine, Toposi P. O., Bengal.	Bansara Coal Co., Ltd	Mohuri Baurin, (f.), 19, Kusami Baurin,	Conl	The three deceased went through a fence to collect slack coal in some disused workings. A piece of coal, about 2 tons in weight, fell on to them from the side of a pillar, at a height of 25 feet, killing them instantly. Inspec-		
				(f.) 21), Mohini Bausin, (f.) 25, Coal-carriers.		tion and inquiry made (See Report, page 9.)		
				· .		· · · · · · · · · · · · · · · · · · ·		
· 105	28th June, 3 A.M.	Karmatand mine, Nowagarh P. O., Bihar & Orissa.	Srivam Coal Company .	Jiton Mahato, (m.), 29, Coal-cutter.	Coal	Doceased, accompanied by his carrier, went through a fence and began to cut coal from the side of a pillar, 20 feet in height. He was killed by a mass of coal, weighing about 10 tons, which fell from the side, at a height of 12 feet. His carrier was seriously injured. Inspection and inquiry made.		
106	30th June	Palauk mine, Palauk, Mergui, Burma	E. Ahmed	Nga Tun Shwe, (m., 30, Mining Coolie.	Wolfram ,	Deceased was killed by a fall of earth from the side of a hill which was being hydraulically sluiced.		
107	5th July, 9 A.M.	Kanbauk mine; Tavoy P. O., Barma.	Kanbauk (Burma) Wolf- ram Mines, Limited.	Lee Nges, (m.), 32, Miner.	Wolfram	Deceased whilst at work in an open cut, was killed by a fall of boulders and earth, weighing about half a ton.		
108	8th July, 2-30 p.m.	Sectalporo mine, Dishergarh P. O., Bengal.	Bengal Coal Co., Ltd	Sunia Mejhian, (f.), 14, Coal-carrier.	Coal .	Deceased was loading coal which had been robbed from the corner of a pillar, when a mass of overhanging coal, weighing about 2 tons, broke away from the side of the pillar and fell on to her, killing her instantly. Inspection and inquiry made.		
109	lith July, Z F.M.	Kendwadih mine, Kusunda P. O., Bihar & Orisse.	East Indian Coal Co., Ltd.	Taju Bhuia, (m.), 30, Coal-cutter.	Coal	Deceased, with two other miners, was dressing overhanging coal on the side of a pillar. Directly against orders, he went under the overhang to throw out some of the fallon coal. About 8 cwts, of coal fell upon him from s height of 15 feet. He was killed on the spot. Inspection and inquiry made.		
, 110_	12th July, 2 a.m.	Chanch mine. Chirkunda P. O., Bihar & Orissa.	Bengal Coal Co., Ltd.	Borka Manjhi, (m.), 45, Coal-autter.	Coal	Decensed broke down a fence and was robbing coal from the bottom of a pillar.  when a mass of side coal, about 2 tens in weight, broke away from a 'slip' and fell upon him. He sustained a fracture of the spine and died five hours later. Inspection and inquiry made.		

•
Č

. •	111	1st August, 2 a.m.	Dhadka mine, Asansol P. O., Bengal.	Dhadka Coal Co	Bhima Kol, (m.), 32, Coal-cutter.	Coal	Deceased, in spite of being warned not to do no, undercut the coal at the base of a pillar. A piece of coal, measuring 3'0"×2'6"×1'0", fell over from a concealed 'slip' and struck him on the head. He died half an hour later.  Inspection and inquiry made.	
	112	3rd Augnet, 3 p.m.	Thingandon mine, Tavoy P. O., Burma.	The Tavoy Concessions, Ltd.	Maung U Kin, (m.), 30, Tributor.	Wolfram	Deceased was killed by a fall of side in an open out-	
	113	9th August, 4 s.w.	Dishergarh mine, Dishergarh P. O., Bengal.	Equitable Coal Co., Ltd	Matabhik, (m.), 42, Coal-cufter.	Coal .	Deceased broke down a fonce and went into a disused gallery to rob coal. A piece of coal, measuring 5'0" × 6'0"×0"4", broke away from the side and struck him. He sustained a fracture of the spine and died 20 hours later. Inspection and inquiry made.	
	114	24th August, 4 a.m.	Jharia Khas mine, Jharis P. O., Bihar & Orissa.	Standard Coal Co., Ltd.	Dubraj Singh, (m.), 32 Coal-cutter.	Coal	Deceased was sleeping at the entrance to his working place whilst a coal cutter, with whom he worked, was sitting near him. A piece of coal, weighing about 2 cwts., fell off the side of the gallery, from a height of about 10 feet injuring deceased so severely that he died 3 or 4 hours later. Inspection and inquiry made.	
	116	16th September, 11-30 a.m.	Sutikdih miae, Bhojudih P. O., Bihar and Orissa.	Sutikdih Coal Co., Ltd.	Lakhiram Kahal, (m.), 21, Coal-cutter.	Coal	Doceased undercut the corner of a pillar 9 feet from the face of the gallery in which he worked. A mass of coal, about 1 ton in weight, fell upon him and killed him instantly. The gallery was 10 feet high. Inspection and inquiry made.	
	116	20th September, 4-15 P.M.	Chapui mine, Kalipahari P. O., Bengal,	Maharaja M. C. Naudi	Lalu Mahato, (m.), 37, Stone-outtors' Sisdar.	Coal	Deceased was standing at the bottom of a sinking shaft, 143 feet in depth, when a piece of stoue, measuring 0' 10"×0' 5"×0' 5", fell from the side of the shaft and struck him on the head. He died fifteen minutes later. Inspection and inquiry made.	ÇT CO
	117	28th Soptember, 6-15 P.M.	Chanch mine, Barakar P. O., Bihar and Orisea.	Bengal Coal Co., Ltd.	Bhaugot Manjhi, (m.), 25; Suku Manjhi, (m.). 33, Coal-cutters.	Coni .	The deceased, in the absence of the sirdar, broke down a fence and were robbing coal from the side of a pillar, when a triangular shaped mass of coal, measuring 7' 0' × 2' 0" × 1' 6", fell over upon them killing them instantly. Inspection and inquiry made.	_
	118	30th Septembor, 7-30 P.M.	Jamadoba mine, (No. 1 Division), Jamadoba P. O. Bihar and Orissa.	Tatu Iron & Steel Co., Ltd.	Sukhada Kora, (f.), 30; Dhani Kora, (f.), 14; Sori Kora, (f.), 20, Coal-carriers.	Coal	The three deceased women were employed in carrying coal in a pillaring district in a coal scam 7 feet thick. They went through a fence and whilst loading loose coal, a mass of overhanging side coal, 10°0″ × 3°0″ × 2°0″, fell upon them and killed them instantly. Inspection and inquiry made.	
•	119	2nd October, 3 a.m.	Jealgora mine, Jamadoba P. O., Bihar and Orissa.	East Indian Coal Co., Ltd.	Chatoo Manjhi, (m.), 30, Cogl-cutter.	Coal .	Deceased left his working place and began to rob coal from the side of a gallery A slab of iron stone band, weighing about 3 cwts., fell upon him, from a height of 4 feet, killing him instantly. Inspection and inquiry made.	
. 10	120	7th October, 11 A.M.	Bhelatand mine, Sijua P. O., Bihar and Orissa.	Tata Iron & Steel Co., Ltd.	Bistu Towari, (m.), 36, Sinker.	Coal .	Deceased was working in a pit bottom with 16 other sinkers and a chargeman, when a piece of stone, weighing about 8 lbs., fell from a 'slip' in the side of the shaft, about 120 feet from the bottom. He was struck on the head and killed instantly. Inspection and inquiry made.	

Serial umber,	Date and hour of accident,	Name and situation of mine.	Name of owner.	Name, ecr., age and occupation of person killed.	Name of mineral wrought.	Cause of accident and remarks.
				ROOFS AND SIDE—	concid.	
121	IIth October, 2 P.M.	Pathariachuck mine, Nowagarh P. O., Bihar and Orissa.	Sheo Persan Tewary	Bhiku Rajwar, (m.), 40, Coal-cutter.	Coal	Deceased left his working place in a quarry and undercut the side in a disused part of the quarry. A mass of coal, weighing about 1½ cwts., fell upon him from a height of 5 feet. He sustained injuries to which he succumbed a few hours later. Inspection and inquiry made.
122	18th October, 11 P.M.	Bhulanbararee mine, Jharia P. O., Bihar and Orissa.	Bhulanbararee Coal Co., Ltd.	Sufal Manjhi, (m.), 42, Coal-cutter; Mangli Manjhian, (f.), 16, Coal-carrier.	Coal	The two deceased left their proper working place and, crossing a fence, entered a disused gallery, from the side of which they commenced to undercut some coal. About 2 tons of coal foll suddenly from the side, at a height of 12 feet, near the roof and killed them both on the sput. Inspection and inquiry made.
.123	19th October, 1 P.M.	Rakha Hills mine. Rakha Mines P. O., Chota-Nagpar.	Cape Copper Co., Ltd.	Moonusawmy Naidu, (m.), 40, Underground Timber mistry.	Copper .	Deceased, who was an experienced timberman, was ordered to take down unsound rook from the hanging wall of a lovel. Instead of standing in a place of safety he stood underneath the stone. A slab, measuring 4'0"×5'0"×1;" to 6", fell upon him from the side at a height of 4 feet. He sustained injuries which resulted in death four days later. Inspection and inquiry made.
124	28th October, 10 A.M.	Taungpila mine, Tavoy P. O., Burma.	Quah Cheng Guan .	Wong San, (m.), 38, Miner.	Wolfram .	Deceased was killed by a fall of earth in an adit in which he was working.
125	22ad November, 5 A.M.	Khas Joyrampur P. O., Jharia P. O., Bihar and Orissa.	Jainarain Ramjash Agarwalla.	Gamari Pankar, (m.), 35, Coal-cutter.	Coal .	Deceased passed through a fence into an area of disused workings and began to rob coal from the corner of a pillar, 25 feet high. A mass of coal, weighing about 7 tons, fell from the side at the top of the pillar. He was struck by some of the falling coal and killed instantly. Inspection and inquiry made.
126	30th November, 6-30 A.M.	Dherao Main mine, Sitarampur P. O., Bengal.	Dhemo Main Collieries, Ld.	Damrnj Koiri, (m.), 19, Stone-cutter.	Coal	Deceased was working in the sump of a sinking shaft, 1,159 feet in depth, when a small piece of stone struck him on the head, causing serious injuries to which he succumbed a few minutes later. Inspection and inquiry unde.

127	Oth December, 9 R.M.	Duis mine, Manharpur P. O., Bihar and Orises.	Bongal Iron & Stael Co., Ltd.	Maki Kolin, (f.), 30; Jingi Kolin (f.), 23;	Iron ore .	Whilst a gang of 45 persons were engaged in loading ore from a dump, a mass of some 10 tons of ore dust slipped down suddenly and buried the two deceased. Death was due to sufficiation. Inspection and inquiry made. (See Report, page 9.)	
128	80th December, 2 P.M.	Duia mine, Manharpur P. O., Bihar and Orissa.	Bengal Iron and Steel Co., Ltd.	Roibari Tanti, (f.), 22, Loaders.	Iron ore	Deceased was one of a gang of 27 women, employed in loading iron ore from a dump. She fell down and was found to have sustained a fracture of the skull which caused death within a few minutes. It was presumed that a lump of ore rolled down the dump and struck her, but no one saw this happen. Inspection and inquiry made.	
129	Slat 1)ecember,	New Kondah mine, Jamuria P. O., Bengal.	New Kendah Coal Co., Ltd.	Ram Saran Gope, (m.), 32, Cool-cutter.	Coal .	Deceased was robbing coal from the side of a pillar when a mass of coal, weighing about 6 cwts., fell over on to him, killing him instantly. Inspection and inquiry made.	
	•	•	in shafts, ropi	ES AND CHAINS BRE —(14 deaths).	AKING		
130	24th Novomber, 8 A.M.	Kustore South mine, Kusunda P. O., Bihar and Orisea.	Raniganj Coal Association, Ltd.	(m.), 30; 2. Nanoo Dhikai, (m.), 30; 3. Basan Pankha, (m.), 28; 4. Jungloo Gara, (m.), 25; 5. Bultoo Gara,	Conl .	Whilst nine persons were being lowered and twelve persons were being raised in the cages at a shaft, 525 feet deep, the main shackle broke. The cage near the top of the shaft fell to the bottom and struck the other cage. All those in the top cage and four of these in the other cage were killed instantly. Another man succumbed to his injuries on the next day. Two men were slightly injured and five others escaped without injury. Inspection and inquiry made. (See Report, page 9.)	. 61
				(m.), 30; 6. Lochan Gara, (m.), 20; Coal-outlors, 7. Majid (m.), 30; Line Kholassie. 8. Ram Varas Goala, (m.), 40; 0 Budan Bauri, (m.), 40;			
		,		Pump Khalassies.  10. Sarali Monh, (m.), 28; Overman.  11. Sukar Manjhi, (m.), 12; Underground Gale Boy.  12. Labh Singh, (m.), 25; Tindal.  13. Faguni Moosa, (m.), 82; Trolleyman.  14. Foolkunari, (f.) 20; Coal-carries.			

<del></del>	Para Accidents, 1310—conta							
Serial number,	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, sex, age and eccupation of person killed,	Name of mineral wrought.	Cause of accident and remarks.		
1	•		IN SHAFTS-WHIL	E ASCENDING OR I ACHINERY—(8 deaths	ESCEND-			
131	10th January, 7-30 г.н.	Dishergarh mine, Diehergarh P.O., Bengal.	Equitable Coal Co., Ltd.	Budhu Manjhi, (m.), 24, Coal-cutter.	Coal .	Deceased, with five other persons, was in a cage descending a shaft, 1,100 feet deep, when the engineman caused the cage to shake violently. Deceased foll out of the cage to the shaft bottom, and was killed instantly. Inspection and inquiry made. (See Report, page 11.)		
132	24th February, 9-30 A.M.	Nigavalley mine, Kalipahari P. O., Bengal.	The Nigavalley Collieries, Ltd.	Gobinda Bauri, (m), 24, Khalassie.	Coal	Deceased was descending a shaft in a bucket, and, fearing the ascending bucket was going to collide with it, he attempted to push it away. In doing so he fell to the bottom of the shaft 40 feet below. He was injured internally and died about 6 hours afterwards. Inspection and inquiry made.		
133	2nd March; 1'P.M.	South Bulliaree mine, Kusunda P. G., Bihar and Orissa.	East Indian Coal Co., Ltd.	Dayem Menh, (m.), 28, Pump Khalassie.	Coal	Whilst deceased and another man were being lowered in a bucket at a sinking shaft, 500 feet deep, the winding engineman lost control of the engine. The bucket was dashed violently into water at the shaft bottom. Deceased was struck on the head by the rope capping, and was killed instantly. The other man was slightly injured. Inspection and inquiry made.		
134	19th March, 5 a.m.,	Kalithan Suratand mine, Jharia P. O., Bihar and Orissa.	Kunjo Behari Scal	Rupan Turi, (m.), 35, Sirdar.	Coal .	A goaf, 135 feet square, 21 feet high and 150 feet below the surface, collapsed suddenly to surface. The rush of air caused by the collapse blow the cages up in a winding shaft, 100 feet distant from the goaf. When the cage fell back it broke the winding rope, and the cage fell to the shaft bottom. Deceased, who was being raised in the cage at the time, was killed on the spot. (See Report, page 11.)		
135	let August, 8-30 r.u.	Choitedih mine, Katrasgarh P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ltd.	Sukram Manjhi, (m.), 35, Coal-cutter.	Coal .	Whilst being lowered in a cage in a winding shaft, 333 feet deep, deceased thinking the cage had reached the bottom, unhooked the safety chain and stepped out. He fell to the bottom 6 feet below and the cage came down upon him killing him instantly. A child who was with him in the cage also fell out and was slightly injured. Inspection and inquiry made.		
136	2nd August, 8-30 A.M.	Kirkend mine, Kusunda P. O., Bihar and Orissa.	R. B. Sircar and Sons	Mahi Mejhian, (f.), 40, Coul-carrier.	Coal .	Deceased, who was being lowered in a shaft, 276 feet deep, stepped out of the cage and fell to the bottom four or five feet below. The cage came down upon her and caused injures to which she succumbed on the following day. The cage was fitted with safety chains. Inspection and inquiry made.		
137	22nd Ootober, 11-30 p.m.	Lutchiporo mino, Sitarampur P. O., Bengal.	Lutchipore Conl Co., Ltd.	Pomi Mahata, (f.), 22, Coal-Carrier.	Conl	In the temporary absence of the winding engine man, an unautherised person attempted to lower a cage, containing five persons, down a shaft over SOO feet in depth. The engine got out of control and the descending enge was dushed violently to the shaft bettom. The deceased sustained injuries to which she succumbed two months later. Inspection and inquiry made.		

_

7,00	11th December, 10-45 A.M.	Bansjora mine, Bansjora P. O., Bihar and Orissa.	Bansjora Coal Co., Ltd.	Balak Manjhi, (m.), 34, Sinking Sirdar.	Coal	Deceased, whilst being lowered in a sinking shaft. 67 feet deep, lost hold of the rope and fell to the bottom of the shaft, 67 feet below. He was killed instantly. Inspection and inquiry made.
				LLING INTO TH IE SURFACE.—(9 d		
139	24th January, 10 P.M.	Borrea mine, Sitarampur P. O., Bengal.	New Beerbhum Coal Co., Ltd.	Kadir Khan, (m.), 35, Coolie.	Coal	Deceased was assisting a carpenter to nail down new floring planks on the top of a shaft. When in the act of stepping from the planks to terra firma, he missed his footing and fell a distance of 235 feet to the bottom of the shaft, and was killed instantly. Inspection and inquiry made.
140	4th February, About 11 a.m.	Burelia mine, Panuria P. O., Bengal.	Burelia Coal Co., Ltd.	Mohamad Ismail, (m.), 25, Chaprassi.	Coal	. The body of deceased was found in the sump of an uposst shaft, 290 feet deep.  It was presumed that he fell from the fan drift into the shaft.
· 141,	15th February, 5 A.M.	South Baraboni mine, Charanpur P. O., Bengal.	South Baraboni Coal Co.	Dhanu Bauri, (m.), 40, Line Mistry.	Coal	Deceased fell down a shaft, 126 feet in depth, and was killed instantly. The shaft was securely fenced. He was seen leaning over the fonce and probably over-balanced. Inspection and inquiry made.
142	26th March, 8 p.x.	Enet Jambad mine, Ranigunge P. O., Bengal.	East Jambad Coal Concern	Aku Bauri, (m.), 40, Banksman.	. Coal	Deceased, when in the act of landing a bucket of water on a platform at the top of a shaft containing 50 feet of water, over-balanced, fell into the shaft and was drowned. Inspection and inquiry made.
143	lat June, 2 P.M.	Jamgram mine, Panuria P. O., Bengal.	Burrakar Coal Co., Ltd.	Hari Pada Singh, (m.), 25, Depot peon.	Coal	The body of deceased was found in the water at the bottom of a discontinued shaft, 430 feet deep. The shaft was securely fenced. Inspection and inquiry made.
144	23rd June, 2-80 p.m.	Central Kenda mine, Toposi P. O., Bengel	Baijnath Rom Kumar Marwari.	Khukhi Baurin, (f.), 23, Coal-carrier.	Coal	Deceased fell from the top to the bottom of a shaft, 80 feet deep, and was killed instantly. The shaft was fonced. Inspection and inquiry made.
145	30th July, 12-30 p.m.	Pandaveswar Mine, Pandaveswar P. O., Bengal.	Jainty West Coal Co., Ltd.	Posu Bauri, (m.), 35, Stone-cutter.	Coal .	Deceased was standing at the top of a sinking shaft, 90 feet in depth, waiting to descend. The trolley was drawn back from the shaft but the temporary feace appears to have been fixed. Deceased went within the temporary fence in order to converse with some one on the opposite side of the pit, lost his footing and fell to the bottom of the shaft. He sustained serious injuries and died half an hour later. Inspection and inquiry made.
146	26th August, 8-30 P.M.	Bhowra Mine, Jamadoba P. O., Bihar and Orissa.	Eastern Coal Co., Ltd.	Sabrou Mahato, (m.), 22, Banksman.	Coal .	Deceased left open the gate at the top of a shaft and on bringing forward another empty tub pushed the tub into the shaft and fell with it to the bottom, 356 feet below. He was killed instantly. It was presumed that he either pushed it further than he intended or was under the impression that the cage had come up again. Inspection and inquiry made.
147	27th October, 7 P.M.	Barareo Mino, Jamadoba P. O., Bibar and Orissa.	East Indian Coal Co., Ltd.	Kabal Kumar, (m.), 18, Sinker.	Coal	Deceased was raised in the bucket in a sinking shaft and, whilst the banksmen were pushing the trolley over the month of the shaft, he attempted to jump from the bucket to the trolley. He slipped and fell to the bottom of the shaft 80 feet below. He was killed instantly. He fell upon one of a gang of twelve men who were working in the shaft bottom. This man was injured but recovered. Inspection and inquiry made.

Serial namber,	Date and hour of accident.	Name and situation of mine,	Name of owner.	Name, sex. age, and occupation of person killed.	Name of mineral wrought,	Cause of accidents and remarks,
			IN SHAFTS-FALLI OF THE W	NG INTO SHAFT FE AY DOWN—(5 deaths).	OM PART	
148	3rd February, 9 a.m.	Bhelatand mine, Sijua P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ltd.	Basu Manjhi, (m.), 25, Sinker	Coal .	Deceased with three other sinkers and a European assistant were lowered in a bucket in a sinking shaft to a depth of 360 feet, where there was a suspended scaffold from which they intended to work. One of the sinkers got out of the bucket and on to the scaffold, and deceased, in attempting to do so, slipped between the bucket and the scaffold and fell to the shaft bottom 95 feet below. He was instantly killed. Inspection and inquiry made.
149	7th Fobruary, 9-80 A.M.	Malkera mine, Katrusgarh P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ltd.	Ugni Turiu, (f.), 32, Coal-carrier.	Coal	Six persons entered a cage and were lowered in a shaft, 530 feet deep. The cage was stopped at a pump station about half way down where a fitter got out. Deceased, presumably thinking that the cage had reached the bottom of the shaft, stepped out, fell to the bottom of the shaft, and was killed instantly. Inspection and inquiry made.
150	3rd March, 4-30 A.M.	Hatgarooie mine, Sitarampur P. O., Bengal.	Lutchipore Coal Co., Ld.	Hiron Kole, (m.), 28, Coal-cutter.	Coal	Deceased fell out of a cage while descending a shaft at night. It is not known why he fell out, but the evidence points to the fact that he had been asleep and was probably half asleep when he fell. Inspection and
151	22nd Norch, 8-20 A.M.	Jamodaba mine, Jamadoba P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ld.	Sonar Ram Mahato, (m.), 20, Surveyor's Khalassie.	1	inquiry made.  Deceased, whilst attempting to enter the cage at a mid inset in a shaft, 306 feet deep, slipped between the cage and the platform, and, falling to the bottom of the shaft, was killed instantly. Inspection and inquiry made.
152	26th July, 9 P.M.	Bhalgors mine, Jharia P. O., Bibar and Orissa.	Bhalgora Conl Co., Ld.	Jungli Bhuian, (m.), 40, Miner's Sirdar.	Coal	Deceased, whilst being lowered in a shaft, 165 feet deep, fell from the cage to the shaft bettom and sustained injuries to which he succumbed three hours later. By mistake a loaded tub had been placed in the ascending cage but as the catch had not been placed in position the tub fell from the cage, the resulting jerk caused deceased to fall from the descending cage. Inspection and inquiry made.
		, 	IN SHAFTS-THIN SURFACE	GS FALLING FROM —(2 deaths).	THE	
163	24th February, 11-0 a.m.	Kustore (North) mine, Kusunda P. O., Bihar and Orissa.	Raniganj Coal Association, Ltd.	Raju Bauri, (m.), 36, Sinker.	Coal	A blasting sirder, whilst preparing fuses at the top of a sinking pit, allowed his knife to slip through a crevice, 4" wide, in the planking covering the top of the shaft Seventeen men were at work in the shaft bettom. 290 for below. Deceased, who was one of these men, was pierced to be heart by the

1 -

154	20th December, 5 P.M.	West Dobalia mine, Kalipahari P. U., Bengai.	West Dobalia Coal Co	Gonesh Manjhi, (m.). 34, • Coal-cutter.	Coal .	A bucket of coal was being raised from a shaft, 97 feet in depth. Deceased, in spite of being warned not to do so, attempted to put some coal into the empty bucket on the other rope, before the trolley was pushed ever the shaft. A piece of coal, weighing about 2 lbs., fell from the leaded bucket and struck him on the head killing him instantly. Inspection and inquiry made.
				•	ļ	<b>)</b>
				GS FALLING FROM Y DOWN—(3 deaths).		
155	15th January, 11 P.M.	Bokaro-Jharia mine, Nawagarh P. O., Bihar and Orissa.	Boknro-Jharia Coalfields, Ld.	Mangal Micah, (m.), 25, Shaft-sinker.	Coal .	Deceased was at work at the bottom of a sinking shaft, 53 feet in depth. Whilst a basket of debris was being raised to the surface, a piece of stone fell from it and struck him on the head. He was killed instantly. Inspection and inquiry made.
156	11th March, 5 a.M.	Lutchipere mino, Situran pore P. O., Bengal.	Lutchipere Coal Co., Ld.	Radhoo Kumar, (m.', 35, Sinker.	Coal	Deceased was killed by a piece of stone falling from a bucket in a sinking pit.  The bucket was probably overloaded. Inspection and inquiry made.
157	15th April, 10 P.M.	Amlabad mine, Jamadoba P. O., Bihar and Orissa.	Eastern Coal Co., Ld	Bhin Roy, (m.), 31, Hookman.	Coal	Deceased was a hookman at the bottom of a sinking shaft, 47 feet deep. In sending up a basketful of shale, he slung it slightly crooked and a small piece of shale fell from the basket, struck him on the head and killed him instantly. Inspection and inquiry made.
				•		1 1
	`					
			IN SHAFTS—MISCE	ELLANEOUS—(6 deaths)	) <b>.</b> .	
158	21st March, 3-30 r.m.	Bhaidih mine, Mahuda P. O., Bihar and Orissa.	Bengal Bhatdih Coul Co., Ld.	Madhu Teli, (m.), 30, Coul-cutter.	Coal	Deceased, whilst walking across a pit bottom, was orushed by the descending cage. He sustained injuries to which he succumbed a month later. A proper pass-bys was provided. Inspection and inquiry made.
159	31st March, 6-0 a.u.	Bhelatand mino, Sijua P. O., Bihar and Orissa.	Tata Iron & Steel Co., Ld.	Usman Khan, (m.), 25, Pump khalassic.	Coal	Deceased attended to a steam pump in a sinking shaft, at a depth of 540 feet.  He was found lying unconscious in the bottom of the bucket and he died two hours later. The cause of death was obscure. Inspection and inquiry made.
160	15th April, 12 noon.	Lutchipore mine, Sitarampur P. O., Bengal.	Damuda Coal Co., Ld	Sukaram Gopo, (m.), 30, Coolic.	Coal	Deceased was found under the cage at the bottom of a shaft, 379 feet deep. It was presumed that he walked under the cage as it was being lowered to the bottom. Inspection and inquiry made.
161	11th July, 11 a.u.	Victoria mine, Kulti P. O., Bengal.	New Beerblum Coal Co., Ld.	Mohan Meab, (m.), 30, Onsetter.	Coal	Deceased walked under the descending cage in a shaft. The cage came down upon him and killed him instantly. A proper travelling road was provided around the shaft. Inspection and inquiry made.
162	19th July, 1-30 p.m.	Chapui mino, Kalipahari P. O., Bengal.	Maharaja H. C. Nundi .	Baboo Lal Muchi, (m.), 42, Stone-cutter.	Coal	A bucket was being lowered down a sinking shaft. Deceased, who was working at the shaft bottom, was warned to get out of the way. He delayed doing so and the bucket struck a crow bar in his hand and swung against him. He sustained serious injuries to which he succumbed fourteen hours later. Inspection and inquiry made.
			•			

M

C

Serial number,	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, sex, age and occupation of person killed.	Name of mineral wrought,	Cause of accident and remarks,
		!		1		, <sup>†</sup> 1
•	. •		IN SHAFTS—I	MISCELLANEOUS-	oncid.	[i
163	15th August, 12 noon.	Purusathampur, Pandaveswar P. O., Bengal.	Tata Iron & Steel Co., Ld.	Bishuu Manjhi, (m.), 34. Stone-cutter.	Coal	The walling scaffold in a sinking shaft was raised and placed on the top of the last length of walling so as to enable another length to be built up. The ends of the main timbers of the scaffold were evidently placed too near the
•						apertures through which they were raised before being placed on the top of the walling and they therefore broke down the newly constructed brickwork, and the scaffold, upon which fifteen men were at work, fell a distance of 30 feet to the bottom of the shaft. All the men on the scaffold escaped injuries excepting deceased who was killed instantly. Inspection and inquiry made. (See Report, page 12).
			BY EX	LOSIVES—(7 deaths).		•
164	27th January, 1 P.M.	Serampur mine, Giridih P. O., Bibar and Orissa.	East Indian Railway Company.	Tribhuban Teli, (m.), 20, Stone-cutter.	Coal	Deceased was drilling a shot hole near another hole in which a shot had mis- fired. The misfired charge exploded causing serious injuries from which he died six weeks later.
165	10th February, 3-30 P.M.	Tellabadu mine, Sydapuram, P. O., Madras.	W. A. Beardsell & Co., Ltd.	C. Penchitgadu, (m.), 35, Cool ie.	Mica	Deceased, with two other men, was ordered to drill a hole near a missire. He disobeyed orders and attempted to extract the missired charge which exploded causing injuries which resulted in death nine days later. The other two men received minor injuries.
166	29th May, 1 a.u.	Sor-Range mine, Quetta P. O., Baluchistan.	North-Western Railway .	Ismail, (m.), 40, Coal-culler,	Coal .	Deceased without waiting for the prescribed period of time, returned to a working in which a missire had occurred. The charge exploded and he sustained injuries which caused death eleven days later.
167	9th June, 4 A.M.	Bangabari mine, Hazaribagh P. O., Bihar and Orissa.	Rup Narain Ram	Salai Manjhi, (m.), 30, Coolie.	Mics	Deceased was drilling a shot hole near an unexploded charge. The missired charge exploded causing serious bodily injuries to which he succumbed soon after.
168	2nd July, 11-30 A.M.	Borrea mine, Kulti P. O., Bengal.	New Reerbhum Coal Co., Ltd.	Mohomed, (m.), 30, Stone-cutter.	Coal	Four shot holes were charged, primed and lit by a shot-firer. Three of them exploded, but the fourth hung fire. The shot-firer went away to drink water, and in his absence, deceased, who had previously been warned not to do so, went to examine the shot which had not exploded. The charge went off as he was examining it and killed him instantly. Inspection and inquiry made.
169	Sth October, 9 A.M.	Jamadoba mine, Jamadoba P. O., Bihar and Orissa.	Tata Iron & Steel Co., Ld	Sib Charan Passi, (m.), 47, Coal-culler.	Conl	Deceased was blasting coal with gunpowder and, after lighting two shots, retired to the next gallery to await the explosions. He heard only one explosion but thought that both charges had exploded together and, after writing about an half hour, he returned to the place. The accordance explosed harling about 6 cwt. of coal against him and killing him on the spot. Inspection

_	_
_	۰
	•

•

170	25th December, 3 r.M.	Rakha Hille mine, Rakha Mines P. O., Bihar and Orissa.	Cape Copper Co., Ld.	Piruni Nair, (m.), 33, Blaster.	Copper	Deceased, who was an experienced blaster, was engaged in charging shot holes with gelignite in an underground stope. After placing gelignite in six of the nine holes, he was ramming the first two cartridges into the seventh hole by means of a wooden tamping rod, when an explosion occurred. The deceased was killed on the spot. A driller and his labourer were severely injured, and another labourer was slightly hurt. Deceased was using too much force, and the gelignite was probably defective. Inspection and inquiry made. (See Report, page 13).
		·		ATER OR FALLING FER—(1 death).		•
171	10th November, 10-30 a.m.	Kalichedu mine, Nellore P. O. Madras.	F. F. Chrestien & Co., Ld.	Natakarani China Abbi- Gadu, (m.). 40, Coolie.	Mica	Deceased whilst engaged in cleaning ithe suction pipe of an underground pump, fell into the water and was drowned.
			HAULAG	E—(41 deaths).		
172	8th January, 9-46 A.M.	Bagdiggi mine, Jharia P. O., Bihar and Orissa,	C. J. Smith	Chota Shambu Goris, (m.), 20, Tub-pushor.	Coal .	Deceased was employed in pushing tubs on a tramming sevel. Whilst a loaded tub was running down a slight grade he rode on its frame. Derailment occurred, and he was thrown off. His head struck the side of a pillar, and his skull was fractured. Death was instantaneous. Riding on tubs is forbidden at the colliery. Inspection and inquiry made.
. 178	10th January, 9-30 a.m.	Bhagaband mine, Jlaria P. O Bihar and Orissa.	Borren Coal Co., Ld.	Bhutni Mojhian, (f.), 18, Coal-carrier,	Coal ,	Whilst a train of ten empty tubs was being lowered on a haulage slope, the front tub became uncoupled and ran wild as far as the landing station. Deceased, who was walking along the landing at the time, was struck by the tub and sustained injuries to the head which caused her death twelve hours later. Inspection and inquiry made.
174	ith February, 1 a.u.	Lodna mine. Jlarin P. O., Bihar and Orissa.	Lodna Colliery Co., Ld.	Maki Mejhian, (f.), 20, Coal-carrier,	Coal .	Whilst a train of seven tubs was descending a haulage slope a coupling link fell off and the leading tub ran wild. Deceased was lying asleep at the corner of a landing 130 feet further down the slope. A coal-cutter named Mahanando ran across the road, and whilst trying to awaken the deceased, the tub ran into them. Deceased was killed outright, and the coal cutter sustained a fracture of the thigh. Inspection and inquiry made.
175	oth March, I r.m.	Koradih (East) mine, Samdi P. O., Bihar and Orissa.	Koradih Colliory, Ld	Bhukhi Deswali, (f.), 14, Coal-carrier,	Coal	Four empty tubs were hauled out of a level and lowered down a main haulage road dipping at 1 in 4. A coupling fell off, and three of the tubs rau wild. Deceased, who was loading a tub at a buffer, about 60 feet below, was struck by the tuba and killed on the spot. Inspection and inquiry made.
176	10th March, 7-15 A.M.	Ledo Valloy mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ld.	Robi Paharis, (m.), 80, Tub-filler.	Coal .	Deceased attempted to jump on to a train of moving tubs on a haulage read.  He fell and was crushed between the tubs and sides of the incline. He sustained injuries to which he succumbed a few hours later. Inspection and inquiry made.
177	12th March, 0-15 a.m.	South East Baraboni Khas mine, Baraboni P. O., Bengal,	Maharaja M. C. Nandi .	Lokhi Mejhian, (f.), 14. Coal-carrien.	Coal .	Deceased crossed the line in front of a set of tubs which was being lowered into a branch road. Two of the tubs became derailed and struck deceased inflicting serious internal injuries to which she succumbed two hours later. Inspection and inquiry made.

	<u> </u>	· · · · · · · · · · · · · · · · · · ·		Vores are a	<del></del>	
Serial Bumber.	Date and hour of accident.	Name and situation of mine.	Name o owner,	Name, sex, age and overpation of person killed.	Name of mineral wrought,	Cause of accidents and remarks.
•	1		HAU	LAGEcontd.		
178	13th March, 3-30 a.u.	Barkui mina. Pench P. O., Central Provinces.	Pench Valley Coal Co.,	Pachia Gondui, (f.) 20, Coal-filler.	Coal	Three full tubs, which had not been properly spragged, began to more on a loading level underground. Deceased got frightened and crossed in front of them. She was knocked down and killed.
179	13th March, 8-30 P.M.	Choitodih mino, Sijua P. O., Bihar and Orissa,	Lutchipur Coal Co., Ld	Sarup Dosadh, (m.), 32, Fireman.	Coal .	Deceased, during the temporary absence of the hauling engine-driver, attempted to lower a train of empty tubs on a dip haulage road, but lest control of the engine. The tubs devailed at the cut-rail, and the rope and became detached from the tub. He then reversed the engine, and the rope was wound up rapidly. The capping of the rope struck him on the head, and fractured his skull. He died within a few minutes. Inspection and inquiry made.
'180	lith April, 1 P.M.	Namdong mine, Margherita P. O., Assam.	Assum Railways and Trading Co., Ld.	Dhanjoo Teli, (m.j, 26, Tub-pusher	Coal .	Deceased was sitting at the foot of an incline. He was struck by a full tub which had run wild because the empty tub had not been properly coupled.  He died shortly after. Inspection and inquiry made.
181	17th April, 2 A.M.	Serampur mine, Giridih P. O., Bihar and Orissa.	East Indian Railway Company.	Bodni Jollin, (f.), 14, Coal-carrier.	Coal 7	Deceased was pushing a tub on an underground tram line when she slipped and was run over by a following tub which was being pushed by other transmers. She sustained a compound fracture of the right leg and died in hospital two days later. Death was said to have been due to influenza and not to the accident.
182	1st May, 9 P.M.	Khost mine, Khost P. O., Baluchistan.	North-Western Railway	(1) Hussain, (m.), 32, Assistant Banksman. (2) Dhaniram, (m.), 30, Carpenter.	Coal 5	Deceased and another man after rerailing a train of two trams on a handage plane, dipping at 45°, were following up the train when it suddenly ran back and into thom. Hussain was killed instantly and Dhaniram sustained injuries to which he succumbed a month later.
183	16th May, 3-30 a.u.	Mohpani mine, Mohpani P. O., Central Provinces.	Great Indian Peninsula Railway Co.	Sandaria Badhain, (f.), 33, Coal-carrier.	Coal .	Deceased, in spite of being warned, went into the landing of a haulage plane and was caught by an incoming train of tubs. She received injuries from which she died a few hours later.
, 184	26th May, 10 p.m.	Ballarpur mine, Ballarpur P. O., Central Provinces.	Sir Kasturchand Daga and M. B. Dadabhoi.	Sadhoo. (m.), 35, Trammer.	Coal	Deceased was struck by coal which fell from loaded tubs in collision with a run- away tub. He received injuries to which he succumbed five days later.
185	17th June, 12 noon.	Chowrassie wine, Dishergarb P. O., Bihar and Orissa.	Equitable Coal Co., Ld	Obilass Bauri, (m.), 26, Hookman.	Coal	A set of loaded tubs was being raised up an incline when the two leading tubs became detailed. Deceased, who was evidently riding on the front coupling, was thrown off and dragged some distance before the engine could be stopped. He sustained serious injuries and died twonty-six hours later. Inspection

,	-	٠
٠.	•	4
^	•	•

186	18th June, 0-15 A.M.	Bhutgoria mine, Januadoba P. O., Bihar and Orissa.	Aldih Coal Co., Ltd.	Meghna Gope, (m.), 24, Looseman at curve.	Coal .	Deceased was standing at a curve and guiding the first tub of a train of tule. His foot slipped under the wheel and he sustained an injury which necessitated amputation of the foot. He died in hospital eight days later. (napection and inquiry made. (See Report, page 13).
187	22nd June,	Jamadoha mine, Jamadoha P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ld.	Dakoo, (m.), 35, Trolleyman.	Coal .	Deceased was standing at a curve to receive a set of empty tubs coming down an incline, when the first three tubs became uncoupled and were thrown off the line at the curve. Deceased was pinned against the side of the gallery and died the same day as a result of the injuries received. Inspection and inquiry made.
168	5th July, 5 s.m.	Ekra Khas mine, Bansjora P. O., Bihar and Orissa.	Maharaja M. C. Nandi .	Punia Mahato, (m.), 22, Trolleyman.	Coal .	Deceased was standing at a curve in readiness to guide a train of nine tubs round the curve. A coupling chain felt off and seven tubs ran wild. Deceased was run over and killed instantly. Inspection and inquiry made. (See Report, page 13).
189	13th July, 3 a.m.	South-East Baraboni or Vanora Khas mine, Charanpur P. O., Bengal.	Maharaja M. C. Nandi.	Gondoria Ghatwal, (m., 25, Trummer.	Coal .	A hookman unhooked the rope of an empty tub on a main incline, having previously put one sprag in the wheel. This failed to hold the tub, which ran wild, killing deceased at the bottom of the haulage plane. Inspection and inquiry made.
90	7th August, 2 p.m.	Ledo Valley mine, Margherita P. O., Assam.	Assam Railways and Trad- ing Co., Ld.	Narathom Mokrani, (m.), 35, Tub-pusher.	Coal .	After beloing to release a tub which had jammed in a narrow gallery, deceased stepped aside to let it pass. He apparently miscalculated the clearance between the side of the road and the tub. His head was crushed between the tub and the side of the road and he was killed instantly. Inspection and inquiry made.
1	7th August, 5 P.M.	Bhulanbar ree mine, Jharia P. O., Bihar and Orissa.	Bhulanbararee Coal Co., Ld.	Babu Lall Bania, (m.1, 32, Trolleyman.	Coal .	Deceased, whilst crossing an underground hadage slope, was struck by a run-away tub. He succumbed to his injuries three hours later. Inspection and inquiry made.
02	21st August, 6 a.m.	Baraboni mine, Asansol P. O., Bengal.	New Beerbhum Coal Co., Ld.	Lokhu Mejhian, (f.), 20, Slack-carrier.	Coal .	Decoased was sleeping on the side of a main haulage read. A set of loaded tubs, being raised from a lower level, came into contact with an empty tub which was lying on its side on the curve of an upper level. The two front tubs were derailed and deceased was pinned under one of them. She sustained serious internal injuries and died eight days later. Inspection and inquiry made.
93	21st August, 6-30 a.m.	Bagdigi mine, Jharia P. O., Bihar and Orissa-	C. J. Smith	Ghendi Bhumij, (f.), 49, Coal-carrier.	Coal .	Deceased was walking up a haulage incline whilst the rope was in motion.  She was atruck by it and thrown against the side of the gallery, sustaining injuries to which she succumbed a fortnight later. Inspection and inquiry made.
94	23rd August, 3 A.M.	Khost mine, Khost P. O., Baluchistan.	North-Western Railway .	Shadman, (m.l, 20, Bellman.	Coal .	Whilst deceased was taking a full tub to attach it to a train, he was caught by a following tub, his head being crushed against roof timber. He died on the next day.
195	24th August, 5 a.m.	Mohpani mine, Mohpani P. O., Central Provinces.	Great Indian Peninsula Railway Co.	Munshi Musalman, (m.), 22, Banksman.	Coal .	Deceased signalled from the in-bye end of an engine plane for a set of tubs to be sent into the mine. He then appears to have sat down on the rails and fallen asleep. He was run over by the set when it arrived and killed.
196	24th September, 6 P.M.	Khas Joyrampur mine, Jharia P. O., Bihar and Orissa.	Khengorji Triku and Co.	Hanuman Show, (m.), 35, Hookman.	Coal	Owing to a fracture of the pinion of a hauling engine, five leaded tubs ran wild on a haulage slope. Deceased was run over and killed instantly.  Inspection and inquiry made.

Serial number.	Date and hour of accident.	Name and situation of mine.	Name of owner.	Name, sex, age and occupation of person killed.	Name of mineral prought.	Cause of accidents and remarks.
		·	•	HAULAGE-concld.	·	
107	26th September, 6 F.M.	Jharia Khas mine, • Jharia P. O., Bihar and Orissa.	Standard Coal Co., Ld.	Arjoon Chamar, (m.), 55, Sirdar.	Coal .	Deceased, whilst walking up a haulage incline upon which travelling was no allowed, was struck by run-away tubs and sustained injuries which resulted in death four hours later. Inspection and inquiry made.
108	30th September, 5 A.M.	Sodepur mine, Sitarampur P. O., Bengal.	Bengal Coal Co., Ld.	Bimala Mahalin, (f.), 24, Coal-carrier.	Coal	The tubs on a self-acting haulage plane were being balanced so as to work the load from an intermediate level. In order to make the rope move the brake was released and men were jerking the rope up and down. The rope moved suddenly and the brakesman lost control, consequently at empty tub was carried towards the wheel at the top of the incline. Deceased who was sitting down on the top level, was struck by the empty tub and flung against the side of a pillar. She sustained serious injuries and died twelve hours later. Inspection and inquiry made.
199	10th October, 8 A.M.	Jamadoba mine. Jamadoba P. O., Bibar and Orissa.	Tata Iron and Steel Co., Ld.	(m.), 80, Trolleyman.	Coal	Deceased was walking up a handage incline where travelling was prohibited A train of tubs, which was being lowered, became derailed and struck the side of the road causing a mass of coal, weighing about one tou, to full The coal fell upon deceased killing him instantly. Inspection and inquiry
200	15th October, 11-30 P.M.	Charanpur mine, Charanpur P. O., Bengal.	Apear Collieries, Limited	Srimati Mejhian, (f.), 50, Dust-carrier.	Coal .	made.  Deceased failed to get out of the way of a tub of slack which was being traumed down a gradient of 1 in 22 into a siding. Her right arm was pinned between a tub which she was pushing and the second tub. She died in hospits ten hours later. Inspection and inquiry made.
201	18th October, 2 A.M.	Bhagaband Mine, Jharia P, O., Bihar and Orissa,	Burea Coal Co., Ld.	Jhalka Manjhi, (m.), 35, Coal-cutter.	Coal	Deceased was sleeping near the curve of a naulage level and, upon being warned that the trams were coming, attempted to cross the tram line. He was run over by full trams which were being run down from the workings by gravity. He was killed on the spot. Inspection and inquiry made.
202	24th October, 8 a.u.	Rajhara mine, Rajhara P. O., Bihar and Orissa.	Bengal Coal Co., Ld.	Simarbasia Noonian, (f.), 12, Coal carrier	Coal	Deceased, whilst loading a tub on a level, was run over by empty tubs which were being shunted by miners contrary to orders. She sustained injuries which caused death four hours later. Inspection and inquiry made.
203	5th November, 9 a.u.	Ledo mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ltd.	(f.), 26, Tub-pusher.	Coal	Whilst deceased and others were working at an in-bye siding, the hadage rope slipped off a roller and caught both deceased and a fellow worker, indicting injuries to their legs. Deceased died from gaugrene twenty-two days later. Inspection and inquiry made.
204	6th November, 1-30 г.м.	(Nuvidih) Bhulanbararae mine, Jharia P. O., Bihar and Orissa.	Bhulanbararce Coal Co., Ld.	Doman Mahato, (m.), 18, .Piller markman.	Conl .	Whilst a train of empty tubs was being lowered over the brow of an incline the leading tub run wild and was derailed at the run-away switch. Deceased and another man, who were walking up the incline, whilst attempting to get into a manhole, were struck by the derailed tub. Deceased died on the way to hospital and the other man was seriously injured. Inspection and inquiry made.

	-
_	
_	~

<b>2</b> 05	8th November, 9-30 p.u.	Bhowra mine, Jamadola P. O., Bihar and Orissa.	Eastern Coal Co., Ld.	Ram Sumer Misser, (m.), 15, Coolic.	Coal	Owing to the fracture of a draw bar, three londed trams ran wild on a haulage slope. Deceased was run over and died a few hours after. Inspection and inquiry made.
216	11th November, 8-30 A.M.	Ledo Valley mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ld.	Mohamad Hossain, (m), 36. Contractor.	Coal	While ascending a self-acting incline, deceased was killed by a tub which had run wild owing to the trammer at the top not fixing the stop block properly.  Inspection and inquiry made.
2:)7	20th November, 2 a.m.	Chanch mine, Chirkunda P. O., Bihar and Orissa.	Bengal Coal Co., Ld.	Lakhi Bhuian, (f.), 60, Dust-carrier.	Coal	A set of five loaded tubs was being transmed along an underground level.  Deceased got confused and went in front of them. The wheels of the front tub passed over her thigh and fractured it. She died fourteen hours later, after the limb had been amputated. Inspection and inquiry made.
208	23rd December, 10-30 a.m.	Jainty Central mine, Karmstas P. O., Bihar and Orissa.	Jainty Central Collicry, Ld.	Mahabir Meah, (m.), 20, Trammer.	Coal	Deceased was evidently riding on the front of an empty tub which was being hauled out of an incline. The tub became derailed at the entrance to the mine and he fell off and was run over, being killed instantly. Inspection and inquiry made.
209	24th December, 2 A.M.	Tikak mine, Margherita P. O., Assam.	Assam Railways and Trading Co., Ld.	Monbharan Rai, (m.), 34, Hooker on.	Coal	Deceased, who was working at the bottom of a bruke, omitted to attach the empty tub to the rope. In consequence the full tub ran wild and caught deceased. He died from his injuries two weeks later. Inspection and inquiry made.
210	24th December, 11 A.M.	Dishergarh mine, Dishergarh P. O., Bengal.	Equitable Coal Co., Ld	Chand Manjhi, (m.), 38, Coal-cutter.	Coal .	A train of six londed and four empty tubs was being raised up an underground haulage road. The rope broke and the tubs ran back. Deceased, who was sitting on the side of the haulage road, ran down to the dip and was overtaken by the run-away tubs. He died from his injuries five days later. Inspection and inquiry made.
211-	27th December, 3 A.M.	Ghusick mine, Kalipahari P. O., Bengal.	Ghusick and Musila, Collieries, Ld.	Bisco Kol, (m.), 20, Coal-cutter.	Coal	Four loaded tube were being moved by gravity out of the face of a level. The centre coupling was not fastened and the two front tube ran ahead and came to a standatill. Deceased walked on to the line and was caught by the rear tube and crushed between them and the stationary tube. He was killed instantly. Inspection and inquiry made.
	•	1	BY UNDERGRO	UND MACHINERY	-(1 death).	
212	14th May, 12 midnight.	Murwara mine No. 1162, Katni P. O., Central Provinces.	D. A. David Bros.	Bhura. (m.), 45, Coolie.	Limestone .	A wooden trestle, supporting a suction pipe, suddenly collapsed. The pipe, in falling, struck deceased and killed him.
			SUNDRIES UNI	DERGROUND. ( 11 des	ths).	
213	15th February, 5 A.M.	Loyabad mine, Bansjora P. O., Bihar and Orissa.	Barakar Coal Co., Ld.	Budhan Manli, (m.), 45, Coal-cutter.	Conl .	Deceased was employed in a pillar cutting area. Whilst he and other miners were extracting a pillar, a loud noise was heard in the goaf. Every one ran out of the place. Deceased, whilst running, fell down and expired within half an hour. In the absence of injuries of any kind, death was attributed to heart failure. Inspection and inquiry made.
214	19th February, 9-30 p.m.	Sorampur mine, Giridih P. O., Hazaribagh.	East Indian Railway Co	Uban Mallah, (m.), 33, -Coal-cutter,	Coal	Deceased was killed by the fall of a prop which was displaced by a piece of coal rolling against it.

			<del></del>			· · · · · · · · · · · · · · · · · · ·
Serial pumber.	Date and hour of accident,	Name and situation of mine.	Name of owner,	Name, sex, age and scoupation of person killed.	Name of mineral wrought.	Cause of accident and remarks.
			SUNDRIES UNDE	RGROUND—contd.	•	
216	29th May, 2 p.m.	Tikak mine, Margherita P. O., Assaun.	Assam Railways and Trad- ing Co., Ld.	Sreepeti Lama, (m.), 25, Tub-filler.	Coal .	Whilst walking towards a tub, deceased fell and sustained slight injuries to his leg. He died from blood poisoning three and a half months later. Inspection and inquiry made.
216	22nd June, 10 A.M.	Muktia mine (Sq. No. D35), Hazaribagh P. O., Bihar and Orissa.	Hoare Miller & Co.	<ol> <li>(1) Raj Bullav Singh,         <ul> <li>(m.), 32,</li> <li>Fitter;</li> <li>(2) Sukar Muscher,</li> <li>(m.), 20,</li> </ul> </li> <li>(3) Pancha Chamar,</li> <li>(m.), 25,</li> <li>Coolies.</li> </ol>	Mica .	The deceased fitter, accompanied by two coolies, went underground to start a petrol pump and took with him a naked light instead of the electric lamp supplied for the purpose. The feed cock from the petrol tank had been left open and the vapour ignited. They were burnt so severely that all died within two days. Inspection and inquiry made. (See Report, page 13).
217	eth July, 2-45 a.m.	Namdang mine, Margherita P. O., Assaw.	Assam Railways and Trading Co., Ld.	Dalsing Lama, (m.), 30, Air-way man (Road-cleaner.)	Coal .	Whilst carrying shovels down an incline, deceased fell and injured his knee- joint. He contracted pneumonia and died 16 days after the accident. Inspection and inquiry made.
218	lst August, 6-30 P.M.	Ranadanga mine, Charanpur P. O., Bengal.	Economic Coal Co., Ltd.	Kousla Kol, (f.) 13, Coul-carrier.	Coal .	A derailed side-tipping tub was being lifted on to the tram line when, owing to the stop catch being open, the upper portion tilted and swung over. I becased, who was standing on the lower side of the tub, was struck on the head and body by the tipping portion of the tub and sustained serious injuries to which she succumbed three and a half hours later. Inspection and inquiry made.
219	10th August, 4 A.M.	Chesnela mine, Bhujudih P. O., Bihar and Orissu.	Lodna Colliery Co., Ltd.	Basco Manjhi, (m.), 35, Coul-cutter.	Coal .	Deceased, having cut a quantity of coal in a lovel, pushed most of it over a ledge to the next level and then went down to that level to load it up. He had left some of the coal close to the edge of the 'drop' on the upper level and a portion of it fell, about 15 to 20 feet, on to his head, killing him on the spot. Inspection and inquiry made.
229	20th November, 12 midnight.	Kutchidbana mine, Rankona P. O., Central Provinces.	The Indian Manganese Co., Ld.	Baloo, (m.), 18, Coulie,	Manganeso .	Deceased was removing overburden in a quarry. He slipped and fell a distance of 10 feet sustaining internal injuries which caused death two days later.
221	27th December, 8-30 P.M.	Loyabad mine, Bunsjora P. O., Bihur and Orissa.	Burrakar Coul Co., Ld.	Jhari Hajjum, (m.), 10, Coolie.	Coal .	Deceased was employed as companion to a pump minder. Whilst lying askeep near a pump, his clothes caught fire from an open hamp and he was severely hurned. He died in hospital two months later. Inspection and inquiry made.

•	
•	

			[			
222	9th Fobruary, 6 a.m.	Rakha Hilla mine, Rukha Mines P. O., Bihar and Orissa.	Cape Copper Co., I.d.	Nabi Bux, (m.), 20, Electric Hoist Driver,	Соррет .	Deceased, contrary to orders, was riding in an electric hoist. He lost control and an overwind occurred, causing the wire ropes to break. The cage fell a distance of 60 feet. He was killed instantly. Inspection and inquiry made.
233	30th May, 10 a.m.	Ghugus mine, Bailaspur P. O., Contral Provinces.	Sir Kusturchand Daga and M. B. Dadabhoy.	Vistari Zitroo Kunbi, (m.), 6(), Coolio.	Coal .	A fan was being crocted, and the fan shaft was lifted off the journals. The shaft swung round and pinned deceased against snother part of the machinery, causing wounds from which he died three hours afterwards.
221	30th June, 12-30 p.m.	Central Dharmaband mine, Katrasyarh P. O., Bihar and Orissa.	Central Dharmaband Coal Co., Ld.	Tagoo Mahato, (m.), 22, Engine driver.	Conl .	Deceased was driving a small hauling winch and it is supposed that, for some reason, he put his hund on the incoming rope. He was dragged under the rope and carried round on the drum, being killed instantly. Inspection and inquiry made.
225	lat December, 1-30 r.m.	Bhernghat mine, Katni P. O., Central Provinces.	Katni Cement and Indus- trial Co., Ld.	Hussaini, (m.), 36, Fitter.	Steatito .	Whilst a vertical boiler was being placed in position by means of a dérrick, one of the legs of the derrick slipped. The boiler fell upon deceased causing injuries to which he succumbed on the same day. Inspection and inquiry made.
,		,		ILWAYS AND TRAN TO THE MINE—(4 de		
236	llih May, 6 a.m.	Kendwadih (Kurkend), Kusunda P. O., Bihar and Orissa.	East Indian Coal Co., Ld.	Dhuba Roy, (m.), 20, Trolloyman.	Conl .	Deceased, with two other men, was pushing a side-tipping tub on a surface tram- line. The tub became derailed and tipped over on to deceased. He died almost immediately. Inspection and inquiry made.
227	23rd May, 8 a.m.	Simlabahal mine, Jharia P. O., Bihar and Oriesa.	Bhalgora Coal Co., Inl.	Brihaspat Dosadh, (m.), 45, Trolleyman.	Coal	Decoased was pushing an empty coal tub up a slight grade on a stock heap when, owing to carelessness of fellow-workmen, a full tub ran down the grade, and collided with the empty tub. He sustained injuries which caused death ten days later. Inspection and inquiry made.
228	8th July, Gr.m.	Namdang mino, Marghorita P. O., Assam.	Assam Railways and Trad- ing Co., Ld.	Pashupati Upadhaya, (m.), 35, Tub-fillor,	Conl .	Decembed was walking up a solf-acting incline on surface. He was knocked down and killed by a loaded train. Imspection and inquiry made.
220	Oth August, & c.m.	Balaghat mine, Balaghat P. O., Coutral Provinces.	Control Provinces Pros- pecting Syndicate, Ld.	Haglia, (m.), 25, Mato.	Manganeso .	Decensed slipped off the frame of a moving tub. In doing so he fell against the tub and received internal injuries, which resulted in death on the following day.
			Miscellaneou	JS ON SURFACE(23	deaths).	,
230	29th Jabuary, 9-354 a.u.	Loyabac mine, Sijua P. O., Bihar and Orissa.	Burrakar Coal Co., Ld.	Sakhawat Mistri, (m.), 311, Muson.	Coal .	Decoased was employed in plastering the wall of an electric winding engine house. The platform on which he worked was about 8 feet from the transmission wires carrying electricity at 550 volts. He left the platform and climbed along the scaffolding poles over the top of the wires. In doing so, he touched the wires, felt upon them and was electrocuted. Inspection and inquiry made.
231	11th February, 9-30 A.M.	Taungpilla mine,   Tavoy P. O., Burma.	Tavoy Wolfram, Ld	Nga Pu, (m.), 30, Coolie,	Wolfr¤m. ↓	Whilst a tree was being felled, deconsed was struck on the head by a falling-branch. He sustained concussion of the brain and expired a few hours later. Inspection and inquiry made.
232	22nd February, G A.M.	Dishergarh mine, Dishergarh P. O., Bougal,	Equitable Conl Co., Ld	Poorni Chamar, (m.), 36, C. olio.	Coul .	Deceased was found drowned in a large boiler tank which was properly fenced all round. Inspection and inquiry made.

# Fatal Accidents, 1919—contd.

				<del></del>	<del> </del>	
erial imber.	Date and hour of accident.	Name and situation of mine,	Name of `owner.	Name, sex, age and occupation of person killed,	Name of mineral wrought.	Cause of accidents and remarks.
	. :		MISCELLANE	OUS ON SURFACE-	oncld.	
233	20th March, 11 A.M.	Hpaungdaw, mine, Tavoy P. O., Burma.	High Speed Steel Alloys Mining Co., Ld.	Harr Dutt, (m), 80, Coolie.	Wolfranz .	Deceased and another man were sawing a log on the slope of a hill. Another log slid end-on down the hill-side and struck the log being sawn. The impact moved the log. Deceased was crushed between the log being sawn and a third log. He died in hospital an hour afterwards. Inquiry held.
234	28th March, 6 P.M.	Widnes mine, Tavoy P. O., Burma.	'The High Speed Steel Alloys Mining Co., Ld.	Maung Tak, (m.), 58, Sawyer.	Welfram .	Whilst employed in moving logs, deceased fell and fractured his ribs. He succumbed to his injuries later.
235	25th April	Kurhurbarce mine, Gıridih P. O., Bihar and Orissa.	East Indian Railway Com- pany.	Bhatni Kolin, (f.) 13, Coal-carrier.	Coal , .	Deceased was found drowned in a fonced boiler tank.
236	28th May, 3 p.m.	Central Jharia mino, Jharia P. O., Bihar and Orissa,	Jairam Shivice & Co.	Rajoni Bauri, (m.), 20, Coolie.	Coal .	Whilst a boiler shed was being erected the ridge pole fell accidentally from a height of 11 feet. Deceased was struck on the head and killed instantly. Inspection and inquiry made.
237	20th June, 3 a.m.	Phalaritand mine, Katrasyarh P. O., Bihar and Orissa.	Phularitand Coal Co., Ld.	Akloo Kahar, (m.), 30, Pump Khalasie.	Coal .	Owing to heavy rain a shelter shed on surface collapsed. Deceased, who was sleeping in the shed, was crushed by the falling timbers and killed instantly.  Inspection and inquiry made.
238	23rd June, 10-55 A.M.	Sodepur mine, Dishergarh P. O., Bougal.	Bengal Coul Co., Ld.	Futich Mohammad, (m.), 35, Coolie.	Coal .	Deceased, who was helping to erect the head-gear at a shaft, lost his footing and fell to the ground from a height of 50 feet. He sustained a fractured skull and died soon afterwards. I uspection and inquiry made.
239	I0th July, 8-0 a.m.	Tikuri mine, Katni P. O., Central Provinces.	Katni Cement and Indus- trial Co., Ld.	Hansi Korin, (f.), 22, Coolie.	Limestone .	Some person unknown removed a length of 300 feet of wire from an acrial transmission line. Subsequently the current was switched on. Deceased came in contact with the trailing wire and was killed. Inspection and inquiry made by the Electric Inspector.
240	14th July, 9 a.u.	Rakha Hills mine, Rakha Mines P. O., Bihar and Orissa.	Capo Copper Co., Ld.	Nursing Bhomij, (m.), 30, Fireman.	Copper .	Deceased was carrying an iron rake, 10 feet long, which came in contact with overhead electric transmission wires. The electric current passed through his body, killing him instantly. Inspection and inquiry made by Electric Inspector.
241	30th July, 4 P.M.	Kustore South mine, Kusunda P. O., Bihar and Orissa.	Raniganj Coal Association,	Mushau Dary, (m.), 32, Trolleyman.	Coal	An empty tub had been over turned on a covered opining in the floor of a heapstead. The cover consisted of an iron sheet and planks. While deceased and another man were turning the tub upright, the cover gave way and the two men with the tub fell to the ground, 18 feet below. Deceased was killed instantly and the other man was slightly hart. Inspection and inquiry made.

- 1	
O.	

			•				
212	24th August, 1 P.M.	Khas Joyrampur mine, Jharia P. O., Bihar and Orissa.	Jainarain Ramjash Agar- wala.	Jhnrar: Bauri, (m.), 13, Coolie,	Coal	Deceased was drowned in a boiler feed tank which was properly walled round.  Washing in the tank was not allowed, but deceased disregarded the pro- hibition. Inspection and inquiry made.	
<b>2</b> 43	26th August, 3 P.M.	Jamadoba mine, Jamadoba P. O, Bihar and Orissa.	Tata Iron and Steel Co.,	Dinoo Roy, (m.), 40, Coal-cutter.	Coal	Deceased passed through a fonce, and, whilst trying to dig coal for his own purposes from a subsided coal working, was killed instantly by the fall of overburden weighing about one ton. Inspection and enquiry made.	,
211	6th Septembor, 3 r.m.	Shivrajpur mine, Shivrajpur P. O., Bombay.	Shivrajpur Syndicate, Limited.	I. Sundha Mangla, (m.), 3-h. 2. Chhotu Gulla, (m.), 21, Coolies.	Manganese .	The two deceased whilst bathing in a water-logged quarry, were drowned.	
215	10th June, 10-15 A.M.	Phuletto mine, Tavoy P. O., Burma.	Phuletto Mining Syndicate.	Leong Chiao, (m.), 25, Tributor.	Wolfram .	Whilst engaged in ground sluicing, deceased was struck by a tree blown down by high wind. He was killed instantly.	
246	Ott. September,	South Barora mine, Nowagash P. O., Bihar and Orissa.	Mosers. Chunder and Dass.	Haricharan Beldar, (m.), 30, Earth-cutter.	Coal	Decoased and other coolies were engaged in throwing up an embankment, 18 feet high. Owing to the weight of the embankment, the surface overlying an old mine broke down. Deceased fell into the subsidence and was buried by the earth. When his body was recovered about an hour attaywards, life was found to be extinct.	•
217	27th September, 1 r. u.	Taungoilly mine, Tavoy P. O., Borma.	Tavoy Wolfram, Limited	Mg Tha Nyni, (m.), 18, Tributor.	Wolfram .	Deceased and another man, whilst working against orders in an abandoned open-cut, brought about a full of overburden. Deceased was killed instantly and the other man slightly injured.	_ "
218	13th October, 5 A M.	Sijua mine, Sijua P. O., Bihar and Orissa.	Tata Iron & Steel Co., Ld.	Gonga Singh, (m.), 30, Coolie.	Conl .	Whilst a guide rope was being fixed in a shaft, the chain, by which it was suspended, broke and the rope fell down the shaft. The loose end struck deceased on the head inflicting injuries from which he died on the next day. Inspection and inquiry made.	C Z
210	18th October, 9 A.M.	Lakurka mine, Kutrasgarh P. O., Bihar and Orissa.	Lakurka Coal Co., Ld.	Ramdin Gowala, (m.), 60, Coolis.	Coal .	Deceased and another coolie were carrying a prop. 13 feet long. Deceased failed to let the prop fall at the same time as the other man. The weight of the prop came upon him and fractured his collar bone. He died three days later. Inspection and inquiry made.	
250	6th November, (unknown.)	Purusathampur mino, Pandaveswar P. O., Bongal.	Tata Iron & Steel Co., Ld.	Rampadarat Singh, (m.), 60, Store Peon.	Conl .	Deceased went to sleep in an unventilated room, connected with a colliery store godown, in which a coal fire was burning and in consequence died of sufferation. Inspection and inquiry made.	
251	24th November, 11 A.M.	Ukwa mine, Bulaghat P. O., Central Provinces.	Carnogie Steel Co.	Talsi, (m.), 45, Coolis.	Manganeso	Deceased whilst working with a crowbar on the edge of an excavation, over- balanced and fell a distance of 7 feet. He sustained internal injuries and ex- pired tive hours later.	
252	23rd December, 12-5 a.m.	Kargali mine, Bokare P. O., Bihar and Orissa.	Great Indian Poninsular Railway Co.	(1) Badal Khan, (m.), 25, Pump Khalasi. (2) Thanu Meah,	Conl .	The two deceased attempted to steal oil from a pressure fed oil lampused for illuminating a coal quarry. The impedant fire and they were severely burnt. Badal Khan succumbed on the following day and Thanu Meah a mouth later. Inspection and inquiry made.	
				(m.), 40, Boiler Fireman,			

	, , , , , , , , , , , , , , , , , , , ,			<u> </u>	 I	<u> </u>	
Serial aumbęr.	Date and hour of ace.dent,	Name and situation of mine.	Name of owner.	Name, sex, age and occupation of person killed,	Name of mineral wrought.	Reason for exclusion.	Cause of accident and remarks.
		DEATHS	S NOT INCLUDED IF	THE STATISTIC	CS-(46 death	s).	
i	4th January, 5 A.M.	Kalikapur mine, Mejia P. O., Bengal.	Regbunath Banerjee & others.	Sabitri Goalini, (f.), 80.	Coal .	Not employed.	Owing to the collapse of mine workings, a subsidence of the surface took place. Deceased, who was sleeping in a but on the surface, was engulfed before she could escape. Inspection and inquiry made.
2 '	20th Jinuary, 21.M.	Joyrampur mine, Jharia P. O., Bihur and Orissa.	B. R. & Co.	Pattu Bhuiyan, (f.), 13, Coal loader.	Coal .	Not a mining accident.	Whilst bathing in an abandoned quarry deceased got out of her depth, and was drowned. Inspection and inquiry made.
3	12th February, 8 a.m.	South Kujama mine, Jharia P. O., Bihar and Oriesa.	Bagdiggi Kujama Collieries, Ld.	   Digam Deswali,   (m.), 10.	Coal .	Not employed	Deceased climbed on to the top of a wall, 4 feet high, fencing a reservoir, and fell into water 7' 0" deep. He was drowned. Inspection and inquiry made.
4	12th February, 10 a.m.	Jogta mine, Sijua P. O., Bihar and Orissa.	Agabeg Brothers	Delchand Turi, (m.), 3,	Coal .	Not employed	Deceased tell into a surface reservoir and was drowned. Inspection and inquiry made.
5	28th February, 2 30 P.M.	South Govindpur mine, Kutrasgarh P. O., Bihar and Orissa.	South Gobindpur Colliery, Ld. ,	Bundia Gowalin, (f.), 7.	Cool .	Not employed	Deceased, who was deaf and dumb and partly blind, was run over by a tub on a surface tram line. She was so severely injured that she died in hospital ten days later. Inspection and inquiry made.
6	9th April, between 6 and 7 A.M.	Kusunda and Nyadeo mine, Kusunda P. O., Bihar and Orissa.	Kusunda and Nayada Collierics, Limited.	Name not known, (m.), about 30 to 35.	Conl .	Not employed .	Deceased, jumped into a wall and was drowned. The well was surrounded by a wall 6 feet high. Inspection and inquiry made.
	loth April, about 6 A.M.	Khas Jharia mine, / Jbaria P. O., Bihar and Orissa.	Jagarnath Ramjash Agarwalla.	Names not known, (1) (m.), 26; (2) (m.), 28.	Coal	Not emploped .	The two deceased were unknown in the district. They appear to have jumped at night, ever a wall surrounding the cutting of an incline, thinking they were jumping on the solid ground on the other side. In the morning they were found at the bettom of the cutting, one was dead and the other died about 15 minutes later without making any statement. They fell about 70 feet. Inspection and inquiry made.
8	20th April, 3-15 P.M.	Tectulmuri mine, Sijua P.O., Bihar and Orissa.	Teetulmuri Collieries, Limi- ted.	Footia Bhuia, (m.), 13, Shal-picker.	Coal .	Not a mining accident.	Deceased was struck by lightning and killed.

	•
	٠,

	9	23rd April, 3 p.m.	Mohrani mine, Mohrani P. O., Central Provinces.	Great Indian Peninsular Railway Co.	Binia Darzan, (f.), 8, Water-carrier.	Coal .	Not a mining accident.	Deceased, with several other women, took shelter under a railway wagon during a sterm. The high wind set another wagon in motion and when they saw it approaching they attempted to run out from under the wagon. Deceased was run over and killed; one of the other women was severely injured.
	10	26th April. 12 midnight.	Gopalichuck mine, Bansjora P. O., Bihar and Orissa.	Gopalichuck Coal Co., Ltd.	Nishi Baurin, (f), 30.	Coal .	Not employed .	The body of deceased was found in the sump at the bottom of the shaft, 288 feet deep. The shaft was fenced and it was presumed that she had jumped into the shaft. Inspection and inquiry made.
	11	29th April, 8 p.m.	Madhobpur mine, Ranigunge P. O., Bengal.	Imperial Coal Co., Ltd.	Khudi Bagdi, (f.), 30, Coolie.	Coal .	Not a mining accident.	Deceased, whilst cooking food on the verandah of a hut, set tho roof on are. She was severely burnt and died a week later. Inspection and inquiry made.
	13	ist May, 3 p.m.	Bansdeopur mine, Kusunda P. O. Bihar and Orissa.	Bansdeopur Coal Co., Ltd.	Ajinashia (f.), 50, Loading Coolie.	Coal .	Not a mining accident.	Whilst sheltering behind a railway wagon, which moved under the impulse of the wind, deceased attempted to run out but was run over and injured so severely that she died 16 days later. 'Inspection and inquiry made.
•	13	let May, 3-15 p.m.	Gepalichuck West mine, Kusunda P. O., Bihar and Orissa.	Gopalichuek Coal Co Ltd.	Sohagi Dosadhin, (f), 28, Wagon loader.	Coal .	Not a mining accident.	During a storm, deceased took shelter behind railway wagons.  The wind moved the wagons and she was crushed between the buffers, being killed instantly. Inspection and inquiry made.
1.7	14	19th May, 11-30 P.M.	Badjoa mine, Mugma P. O., Bibar und Orissa.	Western Coal Co., Ltd	Mahadeb Keot, (m.), 35.	Coal	Not employed	Deceased threw himself down a shaft, 264 feet doop, and was killed instantly. The shaft was adequately fenced. Inspection and inquiry made.
	15	17th May, 9 a.m.	Shivrajpur mine, Shivrajpur P. O., Bombay.	Shivrajpur Syndidate, Ltd.	Ruti Dewa, (f.), 2.	Manganese .	Not employed	Deceased was run over by a loaded tub, at a bond, and succumbed thirteen days later.
	16	22nd May, 6 F.M.	Jharia Khas (Angrapathra) mine, Sijua P. O., Bihar and Orissa.	Trigunait Brothers	Tribenia Bhuis, (m.), 21.	Conl .	Not employed .	Deceased was found drowned in a bathing tank. The tank was properly feaced. Inspection and inquiry made.
•	. <b>17</b>	3rd June, \\1 P.M.	Khudia mine, Mugma P. O., Bihar and Orissa.	Khudia Coal Co., Ltd	Rajani Roy, (m.), 5.	Coal .	Not employed	Deceased fell into a boiler tank and was drewned. There was a wire fence around the tank. Inspection and inquiry made.
	18	16th June, about 7-30 A.M.	(Widnes), Hpaungdaw mice, Tavoy P. O., Burma.	High Speed Steel Alloys Alining Co., Ltd.	(1) Kasi Ram, (m.), 18. (2) Tek Bahadur, (m.), 30. (3) Patima, (f.), 25.	Wolfram .	Not a mining accident.	During a severe storm, a tree was blown over and fell on the hut occupied by the four deceased. They were killed on the spot.  Inquiry held.
•	•	,	,		(4) Tilla, (f.), 21. Tributors.			
	<b>1</b> 9	22nd July,	Nudkhurkee mine, * Nowagarh P. O., Bihar and Orissa.	Ganendra Nath Ghose .	Kunia Jolani, (f.), 10.	Coal .	Not employed	Whilst picking leaves inside the walling of a cutting for an incline, deceased slipped into water and was drowned.

rial mber.	Date and hour of accident.	Name and situation of mine,	Name of owner.	Name, sor, age and occupation of person killed.	Name of mineral wrought,	Reason for exclusion.	Cause of accident and remarks.
	1	· ·	DEATH NOT INCLU	DDED IN THE S	TATISTICS		
20	26th July, 11-30 A.M.	Jogta mine, Sijua P. O., Bihar and Orissa.	Agabeg Brothers	Rampal Bhuiya,	Coal	Not employed	Whilst at play near a soft coke, depot, deceased fell into a small water hole, 2 feet deep, and was drowned.
21	31st July, 5 P.M.	North Mudidih mino, Sijua P. O., Bibar and Orissa.	Reliance Coal Co., Ld.	Dewarka Gossai, (m.), 5.	Coal	Not employed	Deceased was found drowned in a hoiler feed tank. The tank was walled but there was a small opening at one corner of the walling. Inspection and inquiry made.
22	Ist Angust, 7 A.M.	Nimeha mine, Raniguni P. O., Bengal.	Baraboni Coal Concern, Ld.	Makhu Mejhian, (f.), 8.	Coal .	Not employed	Deceased fell into a boiler tank, 7 feet deep, and was drowned.  The tank was fenced. Inspection and inquiry made.
23	13th August, 11 a.m.	Bhalgera mine, Jharia P. O., Bihar and Orissa.	Bhalgora Coal Co., Ld.	Suran Sing, (m.), 33.	Coal	Not employed	Deceased jumped down a shaft, 165 feet deep, and was killed instantly.
24	26th August,	Madhabpur mine, Ranigunge P. O., Bengal,	Imperial Coal Co., Ld.	Koka Kera, (m.), 4.	Coal	Not employed	Deceased was found drowned in a brick-makers' excavation, containing 3 feet of water.
25	20th September,	Pootkee mine, Bansjora P. O., Bihar and Orissa.	Eastern Coal Co., Ld.	Muchiram Kora, (m.), 2.	Coal	Not employed	Deceased was found drowned in an excavation made by brick-makers.  The depth of water was only 1 inches. Inspection and inquiry made.
26	23rd September, between 2 and 6 P.M:	Gopalichuck West mine, Kusunda P. O., Bibar and Orissa.	Gopaliehuck Coal Co., I.d.	Alkee Dośnd, (f.), 9.	Coal	Not employed	Deceased was found drowned in a boiler feed tank which was pro- perly fenced. Inspection and inquiry made.
27	24th September, 1 P.M.	Basudev mine, Jharia P. O., Bihar and Oriesa.	Basudev Colliery Company	Daskhora, (m.), 4.	Coal .	Not employed	Deceased fell into a water-logged quarry and was drowned. A wall was being built round the quarry, but deceased, during the temporary absence of the masons, passed through a gap. Inspection and inquiry made.
28	8th October, 9 a.m.	Deshergarh mine, Deshergarh P. O., Bengal.	Equitable Coal Co., Ld.	Pebisaran Pasi, (m.), 8.	Coal	Not employed	Deceased attempted to ride on an empty tub on a surface handage driven by an endless trope. He slipped and fell in front of the moving tub, which passed over and fractured his leg. He died three days later. Inspection and inquiry made.

~7	
60	

•

•

.

29	10th October, 12-30 p.m.	Bhuggatdih mine, Jharia P. O., Bihar and Orissa.	Bengal-Nagpur Coal Co., Ld.	Nat! u Beldar, (m.), 4.	Coal 7	Not employed	A cutting had been made for a road in a new earth bank, 30 feet wide by 10 feet high. Deceased's mother, who had been carrying earth from a cutting, sat down at the side of the cutting, with the child, to eat food. About a cubic yard of earth fell upon them from the side of the cutting. The woman was unburt but the child was killed instantly. Inspection and inquiry made.
30	10th October, 1 F.M.	Lachipur mine, Sitarampur P. O., Bengal.	Jalota Lachipur Coal Co.	(1) Name not known, (f.), 5; (2) Name not known, (f.), 7.	Coal.	Not employed	The bodies of the deceased were found floating in an old shaft containing water. The water in the shaft was used for drinking purposes, and the shaft was adequately fenced. Inspection and inquiry made.
31	11th October, 4-30 P.M.	Bansjora mine, Bansjora P. O., Bihar and Oriesa.	Bansjora Coal Co., Ld	Mongar Pashi, (m.), 30, Trolleyman.	Conl .	Not a mining accident.	Deceased, with a number of other persons, took shelter in a surface engine house during a thunderstorm. The house was struck by lightning, and deceased was killed instantly and another man was slightly burnt. Inspection and inquiry made.
82	18th October	Nandi mine, Nandi P. O., Bengal.	Adjai Coal Co., Ltd.	Name not known, (m.), 60,	Coal .	. Not employed	The body of deceased was found in water at the bottom of a shaft, 100 feet in depth. The shaft was adequately fenced Inspection and inquiry made.
33	19th October, 8 P.m.	Widnes Hyaungadaw mine, Tavoy P. O., Burma.	High Speed Steel Alloys Mining Co., Ld.	Lee Quine, (m.), 25, Tributor.	Wolfram	Not a mining accident.	Deceased was cooking food in a coolie lines. Stolen explosives had been buried there. His fire caused them to explode. He was killed instantly.
<b>84</b>	22nd Cotober, 8 P.M.	Pootkee mine, Bansjora P. O., Bihar and Orissa.	Eastern Coal Co., Ltd.	Mahi Ali Saheikh, (m.), 65.	Coal .	Not employed	Deceased was crossing a surface tramway at night and was run ever by a train of loaded trams. He was killed instantly. Inspection and inquiry made.
85	18th November, 12 (noon).	Ghusick mine, Kalipahari P. O., Bengal.	Ghusick Coal Co	Sobu Bauri, (m.), 13.	Coal .	. Not employed	Deceased, a person of unsound mind, fell from the surface into a shaft, 112 feet in depth, and was killed instantly. The shaft was fenced. Inspection and inquiry made.
36	28th November, 1 P.M.	Deoli mine, Deshergarh P. O., Bihar and Orissa.	Deoli Coal Co., Ltd.	Bolas Bauri, (m.), 15.	Coal .	. Not employed	Deceased was riding on the front tub of a set of six leaded tubs on an endless haulage. The set rider warned him to get off. When doing so he slipped and fell in front of the moving tubs and was dragged along by them. He sustained serious injuries and died three hours later. Inspection and inquiry made.
37	28th November, 6-30 A.M.	Now Kessurgurah mine, Nowagarh P. O., Bihar and Orissa.	New Kessurgurah Coal Co., Ltd.	Ramdhani Mejhian, (f.), 13, Coul-carrier.	Coal .	. Not a mining accordent.	Whilst drawing water from a disused well, the deceased over-balanced and was drowned. Inspection and inquiry made.
38	4th November, 11 P.M.	Raghunathbati mine, Sitarampur P. O., Bengal.	Raghunathbati Coal Co., Ltd.	Tribhanga Bauri, (m.), 18, Coolie.	Coal -	Not a mining accident.	A basket of debris was being raised from a well, 50 feet in depth. A piece of stone, weighing about 2 lbs., fell out of the basket and struck deceased, who was at the bettern of the well. He sustained a fracture of the skull and died twenty-two days later. Inspection and inquiry made.
89	11th December, 9-30 p.u.	South Bulliari mine, Kusunda P. O., Bihar and Orissa.	East Indian Coal Co., Ltd.	Ratni Ghosain, (f.), 18, Mason's Coolis.	Cont .	Not a mining accident.	Deceased was burnt to death in a hut which caught fire.

#### APPENDIX II—concld.

Serial number,	Date and hour of accident.	Name and situation of mine.	Name of owner,	Name, sex, age and occupation of person killed.	Name of mineral wrought,	Reacon for exclusion,	Cause of accident and remarks.
		DEATES	NOT INCLUDED IN	· · · · ·	CS—concld.	,	
<b>40</b>	23rd December, 9-30 P.M.	Jamadoba mîne, Jumadoba P. O., Bihar and Orissa.	Tata Iron and Steel Co., Ltd.	Prasadi Rana, (m.), 24, Sinker,	Coul .	Not a mining accident.	Whilst sleeping near a fire in a hut, the clothes of deceased became ignited and he was burnt to death.
41	26th December, 9-30 A.M.	Duia mino, Mouharpur P. O., Bihar and Orissa.	Bengal Iron Co., Ltd.	Guru Charan Tunti; (m.), 35, Shop-keeper.	Iron .	Not a mining accident.	Deceased was not an employé of the Company. Whilst attempt ing to jump on a moving train of ore wagons, he slipped and fell under the wheels. His leg was almost avered and he died from the resulting hamorrhage, within a few hours. Inspection and inquiry made.
						Ì	·
	•	·				-	
	/··•	/.			,		
				·			
					1		

#### APPENDIX II-

Table No. 2.

Statement of fatal and serious accidents in and about mines regulated by the Indian Mines Act, 1901, during the year 1919.

_	<del>                                     </del>	7 25	P	ATAL A	CCIDE	¥ТВ.	87	Biors .	CCIDE	N78.	Dr	ATH-207	- PER
		daily.		] -	NCW PER MEANS		serious non-		NEWSER (18JUSE)	IOC#LT		(i) PER EMPLOY	KOWS.
Раочінся,	District and mineral field.	Total average runher of	Number of separate	Below ground.	Abore ground.	Total deaths.	mber of	Relow ground.	Alove ground.	Total tumber of persons in-	Below ground.	Above ground.	Defow and above ground.
·				AC	OAL.							-	]
ſ	Lakhimpur	. 2,738	13	1 12	1	13	90	85	G	91	6.26	1.10	1.75
Aman	Noga Hills	415						***					
ţ	Sibasgar	. 45		<b>-</b>		•••							]
į	TOTAL	3,193	13	12	1	13	90	85	6	91	5:33		4.07
	· · · · · · · · · · · · · · · · · · ·		<u> </u>			-					-	-	-
ر	Loralai	35	1	} •	ĺ	]	ļ				]		`
Baluchistan	Quetta-Pishin	139	" 1		***	<i>"</i> ",	] ":	1		l <sup></sup> ,		···	-
ì	Sibi-Khost	728	2	3		3	1	ļ	1	1	8.15	""	7:11
ĺ	Тотав	902	3			4	2	1	1		7:97		4·12
<u>-</u>	Bankura, Raniganj	94	! 		<u> </u>		<del> </del> -		<u> </u>	<b> </b>	-		
, , , , , , , , , , , , , , , , ,	Birbhum ,,	54						***	•••	''' ,	""	•••	•••
{}	Burdwan ,	48,494	63	69	3	92	59	45	17	62	2.28		1.40
	TOTAL .	48,642	63	69	3	72	59	45	17	62	2.27	16	1:48
ſ	(Bokaro-		 			<b></b>					<b></b>	<u> </u>	
[]	Ramgarh Giridih .	8,796	1 5	,	2	2 5	7	1	6	7		-66	-23
. []	Jharia .	10,951 1,729	2	4	1		13	13	1	14	-49	•85	46
	Manbhum, Jharia	94,384	97	2   113	 12	2 125	2	1	1	2	2.13	•	1.16
Bluar and Orima	Raniganj	10,762	14	22		22	98	72 3	28	100	1.98	-32	1.33
	Palamau, Daltonganj	770	2	2		2	•		2	5	8.70	•••	2.01
il	Sambalpur, Hingir-Rampur .	929	1	1		1	***	***	***	•	A:71		2·6Q
] [	Southal Parganas, Jainty	1,712	2	2		2		".	1	 2	1.78	***	1.08
ij	" Raniganj .	75	[		•••					ĺ	2.32	•••	1-17
	TOTAL .	129,808											
			124	146	15• ——	161	127	91	89	130	1.43	·a0	1::4
- 11	Chanda, Ballarpur	1,687	2	1	1	2	Б	8	3	6	1-10	1.29	1.19
26-22101 E 1011715(M ,4	Chhindwara, Peach Valley .  Narsinghpur, Mohpaui	3,044	4	5		5	5	7		7	2.20		1.64
11	Yeotmal	1,572	2	2		2	9	5	8	13	2.03		1.27
}	TOTAL	3	_ <del></del> -	<del></del> ,'.	_ <del></del>			<del></del>		<u></u> -	-:-		
North-West Frontier		6,306		<u>8</u>		9	19	15	11	26	1-92	47	1.13
I mvince.	linzara	5	<u></u>	İ		•••			***		164		
	Jholum	946	•••	]	***		1	2	***	3			
11	Minnwali	123	1	1	`	1	•••		•••		25 00	•••	
1	Shahpur	122	<u> </u>	<u></u> !		`	<u></u>		<u></u>			•••	S-13
	TOTAL .	1,191	-1	1	***	1	1	2		8	1.52		-54
	GRAND TOTAL (COAL) .	190,052	212	240	20	260	299	238	70	314	2.04		

Table No. 2—contd.

Statement of fatal and serious accidents in and about mines regulated by the Indian Mines

Act, 1901, during the year 1919—contd.

<del></del>		484	P	TAL A	CCIDEN	TB.	81	Rious	OUS ACCIDENTS.			DEATH-BATE	
		nber of laily.	ste	2	NUMBER	G#	- 100 a	721	NUMBER ERR BKO	OCELY	1	ATE-BAT AST (OO) EMPLOS	101
PROVINCE.	District and mineral field.	Total average number of per- sons employed daily.	Number of separate fatal accidents.	Below ground.	Abore ground.	Total deaths.	Number of serious fetal accidents.	Below groand.	Above ground.	Total number of persons in	Below ground,	Above ground.	
-				В.	-MI	CA.							Ī
ſ	Gaya :	1,728	•••		<b></b>		1	1		1			
	Manbhum	11		•••			•••						
Bibar and Orissa	Hazaribagh	15,417	4	8	•••	8	10	12		12	•78		
]	Monghyr	774	•••	***	•••		1	I	***	1	p=4		
	Sambalpur	140											_ -
	Total .	18,100	4	8		8	12	14		14	-67		
	Kistna	42	***			1**	470						
Madres	Nellore	3,837	2	2		1 2	•••	•••			71		
Į	Salom	180		ىود.			<u></u>						_
;	TOTAL .	4,059	2	3		2					.70	,,,	
	Ajmer-Merwara	492	.,,						***		,		
Rajputana	Nasirabad	. 11											
	. Total .	503					•••						
<del></del>	GRAND TOTAL (NICA) .	22,662	8	10		10	12	14		14	- <del></del>		
			- C.	-MA	NGA	NESE	<u> </u>						-
Bombay	Panch Mahals	1,280	1	111	2	2	2	1	1	2	***	7.04	
	Balaghat	6,007	4	7	2	9			<b></b>	•••	1.44	174	
Central Provinces	Bhaudara							<b></b>			•••		l
Leutral Provinces.	Chhindwara	772	1	1		1	180				1.94	***	1
(	Nagpur	3,427									•••	***	
,_	Toraz .	10,886	5	8	9	10		•••	,		.97	'76	
Madras	Vizagapatam	257	•••	***								***	
	GRAND TOTAL (MANGANESE)	12,423	6	8	4	12	2	1	1	2	•85	1:31	
	•	<del></del>		.—LI	MES1	ONE.				-			
Contral Provinces.	Bilaspur	126		۱	·•• [			***	***			0.04	١,
Ţ	Jabalpur-Katni	2,251	3	2	1	8		***			1.10	2.34	_
~	Тотас .	2,377	3	2	1	3		 	***		1.01	2 18	_
Panjab	Hoshiarpur	50					nă.				,	<u> </u> 	•
	GLAND TOTAL (LIMESTONE)	2,427	3	2	,1	3		***			1.03	2.08	1.2

Table No. 2—contd.

Statement of fatal and serious accidents in and about mines regulated by the Indian Mines Act, 1901, during the year 1919—contd.

<del></del>		į.	F/	ATAL AC	CIDENT	D8.	5ER	ious ac			Drith-rate cer 1,00 presons				
		Not of sily.	ar te to	N N	DEATES,	7	non.	72280	CMBER C BS SEE BS br>SEE BS SEE BS br>SEE BS SEE BS SEE S	CLLY		MAPOLEI	D.		
Растіяса.	District and mineral field.	Total average number sons employed daily.	Number of separate	Below ground.	Above ground.	Total deaths.	Number of serious fatal secidents.	Below ground.	Abore ground,	Total number of persons injured.	Below ground.	Above ground.	Below and above ground.		
				E	-SAL	т.						,			
(	Jhelum	873			•••		6	6	***	6	,	, 	"		
anjah	Mianwali	49		•••	•••		}	•••	•••		***	  -	"		
Ļ	Shabpur	81					··· 					••• 	<u>                                     </u>		
	GRAND TOTAL (SALT)	1,003					в	6	***	в	6				
			<b>F</b> .—	GEM	3.							·	ļ		
Sarion	Mogok (Rubies, etc.)	1,319	···		•••	····	1		1	1			<u>                                     </u>		
			<b>G</b> .—	SLAT	E.					'					
lihar and Orisaa	Monghyr	405	·••	***	····`]				<i>,,,</i>	,,,		 			
j	Gurdaspur . ,	6		•••		**			***		***				
nujab	Gurgnon	217			•••			•••	11,		47.		"		
. (	Kungra	160		•••		3	<b></b> ,						<u>                                     </u>		
	Total .	4 3	•••												
	GRAND TOTAL (SLATE) .	808				.,,									
<del></del>			H	-GOL	D.						i	<u>-</u>			
iller and Orison	Singhthum	228	···			***	1	***	1	1	•••	•••	ļ		
adras	Augutapur	554					2	8	1	4					
·	GRAND TOTAL (GOLD) .	782					8	8	2			470			
			-IRO	N OR	 E.						<u> </u>				
iliar and Oriesa	Singlibhum	986 <sub> </sub>		3	, ***	8		.,.	***	4	4.13	•••	8.0		
entral Provinces	Jabalpur	133	***	•••	•••		•••	***	141						
lajputana	Ajmer-Merwara	2				 	\  	•••				 	-		
	GRAND TOTAL (IBON ORE)	1,118	2	3	•••	3	 				3.67		2.6		
<del></del>	(·		r.— <b>W</b> (	) )T.TP Ř	A 1MT	<u></u>			<del></del>				-		
thar and Orism	Singhbhum	20		""		·.   ···	1	1	•••	1	•••		ļ		
ſ	Mergui	530	2	2		2	1			1	8-93		37		
arms [5	Tavoy	8,736	16	12	5	17	7	3	5	8	2-48	1-43	20		
	Thaton	828				}	]								
	TOTAL	9,694	18	14	5	19	8	3		9	2.53	1.20	1:		
<del></del>	GRAND TOTAL (WOL-	9,714	16	14	5	19	9	4							
	FRAM).		<u> </u>	^*	1	}	8	4	6	10	2.53	1.20	1.		

#### Table No. 2-contd.

Statement of fatal and serious accidents in and about mines regulated by the Indian Mines Act, 1901, during the year 1919—contd.

	Diffies Act, 18												
		f per-	FA'	TAL ACC	IDENTS	3 <b>.</b>	SER	lous ac	CIDEN	rs.	Deat	11-24 <b>72</b> p	181
Province.	District and inheral field.	sumber of a daily.	eparate	N:	MARRON	,	as bon-	<b>7228</b> 0.	UMBER O Berrio Raurre.	UBLY	1,11.	PERSON	•
P.EOVINGS.	erzetzete deut materende myse	Total average number sous employed dally.	Number of separate	Below ground.	Abore ground.	Total deaths.	Number of serious non- fatul accidents,	Below ground.	Above ground.	Total number of persons injured.	Below ground.	Above ground.	
, <u> </u>				GNES	<del></del>				_				
Madras	Salem	738	-ma	 	 	•	1	•••	1	1		***	
		'	—— <u>'</u> СН	ROM]	TE.								- 
É alt chistan	Zhob	279		···		•••	1		1	1			L
Bihar and Oriesa	Singhbhum	180											L
	GRAND TOTAL (CHROMITE)	465			•••		1	1	•••	1			 
-		M	-COP	PER	ORE.								
Bihar and Oriesa	Singhbhum	2,628	4	2	2 !	4	14	4	12	16	3-12	1.01	  -
Central Provinces	Balaghat	33						<u></u>	ļ			<del></del>	-
	GRAND TOTAL (Copper)	2,666	4	3	2	1	14	4	. 12	16	2.99	1.00	-
		7	7.—BA	UXI	Te.		1	j			l		
Central Provinces	Jabalpur	125	_	 		·   •	] ]	 	 				 
			00	CLAY	,			1					t
•	Bhagalpur	214		•••	•••	•••			***				
Biber and Oriesa	Manbhum	376		`	•••	•••		•••	•••				
	Palamau	159				•••	<i></i>						ŀ
	TOTAL .	779	•••	···   	 		 		- <del></del> -				I I
Central Provinces		1,073				, —	'''   				\		<u> </u> 
Dolhi	Delhi	20	 	<u> </u>	···		···			<del> </del>	i		
	GRAND TOTAL (CLAY) .	1,872					<u> </u>	••• •———					_  -
. Contral Provinces	Drng	1 30		LEN 	<b>A.</b>	l •••							
			1	_TIN.	<u> </u>	!	. <u>'</u>	-		<u> </u>	-		-
Bihar and Orissa	Hazaribagh	172	\	-TIN. 				***				 	<u> </u>
	Mergui (Maliwan)	56		100	·								
Burma	Tavoy	149											
	Thaton	35		•••		 	···		-	-			  -
· · · · · · · · · · · · · · · · · · ·	TOTAL .	240				ļ				\ <u></u>			  -
	GRAND TOTAL (TIN)	412					***					٠,,	_

Table No. 2-concld.

Statement of fatal and serious accidents in and about mines regulated by the Indian Mines Act, 1901, during the year 1919—concld.

		Ž.	P.	LTAL A	CCIDEN.	TS.	SE	dous d	CCIDE:	STS.	DEATH-RATE PER				
		mber of	Parate		CWNER ( Deaths,		n Bob.	PER	NCMBER One seri	OUSLX		uo prem Employe	D.		
Риотівия.	District and mineral field,	Total average number Bons employed daily,	Number of separate fatal accidents.	Below ground.	Abore gr and.	Total death.	Number of serious	Below ground,	Above ground.	Total number of persons injures.	Betow ground.	Above ground.	Below and above ground.		
		I	3.—ST	EAT.	TE.	·									
Cartral Provinces .	Jahalpur	179	1		- 1	1						14:49	5.59		
Mustras	. Kurnool ,	16			ļ										
•	GRAND TOTAL (STEATITE).	195	1		1	1		•••				13.33	5.13		
			8.—	осні	RE.							\			
Bibut and Orises .	Pori :	43			<b></b>										
			T.—G	RAPI	ILLE		]								
Rajputana	Ajmor-Merwara	22	ļ •••		•••										
		τ	J. – A I	AT1	Œ.		٠								
Biliar and Orises	Singhbhum	250	•••	•••		·	··· '								
		<b>v</b> .—i	MOLY	BDE	NITE	.			•						
Burma	Favoy	10	•••	<b></b>	***	***	•••	•••					***		
		V	7.~B	ARYI	es.										
ifactras	Kurnool	20		••• [	<b></b> [	•••	•••		<b></b>	   <b>,</b> .	•••	•••			
	GRAND TOTAL (ALL MIRRS)	249,156	262	279	38	312	350	272	100	872	1.78	•36	1.25		

## Table No. 3.

Statement of fatal accidents in mines regulated by the Indian Mines Act, 1901, during the year 1919, classified according to the age and sex of the workers.

			ents.			N	JMBER	OF DEA	THS.			TRD.
-			ıl aecid		Batow (	GRUUND.	•		Apoyx	GROUND		OH OH
Miberal.	PROVINC	M AND MINISTE FIELD.	Number of separate fatal accidents.	Adult males.	Adult fomales.	Children (under 12).	Total.	Adult males.	Adult females.	Children (under 12).	Total.	TOTAL BELOW AND ANOVE SHOUP.
-	Assam, I	Lakhimpur	13	11	1		12	1			1	13
r	Baluchis	t	1	1	<b></b>		1					1
		Sibi, Khost .	2	8			3				***	3
	То	TAL BALUCHISTAN	3	4			4	444			•••	4
,	Bengal, I	Raniganj	63	51	18	 	69	3		<b>::</b>	8	72
	-	Bokaro, Ram-	1	•••	400	***	•••	2	***	***	2	2
<u> </u>		garb.  Giridib	5	2	2	•••	4	104			1	5
		Jharis .	2	2			2	•••		***		2
-	Bibar	Manbhum, Jharia .	97	92	20	1	113	12	701	***	13	125
DOAE.	and orisss.	Manbhum, Raniganj .	14	16	6	•••	22	•••		***		22
_		Palamau, Daltonganj.	2	1	1	/	2	•••				3
•		Sonthal Parganas, Jainty.	. 2	2	•••	<b></b>	2	***				2
		Sambalpur Hingir Rampur,	1	 - <del></del>	1		1				 	1
	Тот	AL BIHAR AND ORISSA.	124.	115	30	1	146	14	1		15	161
		Chauda .	2	1		   	1	1			1	S
· ·		Provinces { Chhindwara .	4	4	1		5	•		<u></u>		5
		. Narsinghpur	2	1	1		2				••• •	2
	TOTAL	CENTRAL PROVINCES	8	6	2		8	1		***	1	9
	Punjab,	Mianwali	1	1			1					1
		TOTAL COAL ,	212	163	.51	1	240	19	1	•••	20	200

## Table No. 3-concld.

Statement of fatal accidents in mines regulated by the Indian Mines Act, 1901, during the year 1919, classified according to the age and sex of the workers—concld.

		en tx		-	ĸ	UMBEB	o <b>f</b> De.	ATHS.			A DO
	1	l aceid		Balow	BOUFD.			ABOTS	G K T O K D		0 110
Nianore	PROTURGE AND MUNICAL SIXLD.	Number of separate fatal accidents	Adult males.	Adult females.	Children (under 13).	Total.	Adult males.	Adult females.	Chlidren (under 12).	Torte.	TOTAL BECOW AND ABOVE GROUND
	Bihar and Orisen, Hazaribagh .	4	7	1		8	••		329		
110A • • •	Madras, Nollors	2	2			2	,	•••			
-	TOTAL MICA .	6	9	1		10	**			;••	
	Central Provinces Balaghat .	4	2	4	1	7	2		.,,	2	
	Chhiudwara TOTAL CENTRAL PROVINCES .	. 1 	3	4	ñ" 1	8	2	***		2	 
Anganus <b>u</b> -	Rombay, Panchmahals	1					. 2		,,,,	2	-
	TOTAL MANGANESE .	6	3	4	1	-8	4			4	
IMESTONE	Contral Provinces, Jabalpur .	3	2	***	***	2	•••	1		1	
STEATITE	Central Provinces, Jabalpur .	1	•••			•	1			1	
non Orm	. Bihar and Orissa, Singblum .	2	***	3		8			•••		
Wolfram , ,	Burma . Morgui	2 16	2 12			2 12	  6		···	 5	
•	- Total Wolfram	18	14			14	5		•••	. Б	<u></u>
COPPRE	. Bibar and Orises, Singhbhum	4	2			2	2			. 2	-
GRAN	D TOTAL (ALL MINERALS)	252	218	 59	2	279	31	<u> </u>		- 33	្ន

## APPENDIX II-concld.

Table No. 4.

Statement of fatal accidents in mines regulated by the Indian Mines Act, 1901, during the year 1919, classified according to cause of accident.

	)a(e.					(UMBER (	PERSON	S KILLE	D.	~			PEAT	I-RATE PE	n 1,000 ovad,
Mineral worked.	Number of separate fatal accidents.	Explosions of fire-damp.	Palls of roof.	Pails of side.	In shafts.	Suffication by gases.	By explosives,	Irruptions of water or fulling luke water.	Haulago,	Miscellaneous below ground.	Sarface.	Total deaths.	Below ground,	Above ground,	Below and above ground.
Coal	212	1	91	49	47	***	4		41	7	2)	260	204	-28	1:37
Copper .	4	•••• ••••	•••	1		•••	1	• ада		•••	. 2	4	2:99	1:00	1-50
Jron	2	•••	•••	3		\ \ \ \				••• !-		3	3.67		2:69
Limestone	3	<b></b>	•••	1	<b></b>					1	1	3	1.03	2:06	1.2
Manganese	c	• • • • • • • • • • • • • • • • • • •	<b></b>	7	•••			<b></b>	•••	1	4.	12	·85	1:31	-97
Mica	6		1	3			2	1		3	•••	10	•65 	•••	   4    
Steatite .	1	•••	***	<b></b>				***	***		1	1	·	13 33	<b>5</b> ·13
Wolfranu	18	<b></b>	3	13	•••		•••			•••	5	19	2.53	1:20	1:9€
Total 1919 .	252	1	95	75	47	·	7	1	41	12	33	312	1.78	-36	1.20
Total preceding	209	12	70	56	21		9	6	23	16	81	243	1.37	-12	1-05
Difference .	+48	-11	+25	+19	+26		_2	-5	+19	4	+2	+69	+.11	:06 :	+ :23

## APPENDIX III.

## PROSECUTIONS UNDER THE INDIAN MINES ACT, 1901.

Statement of prosecutions instituted under the Indian Mines Act, 1901, during the year 1919.

PROVINCE.	District.	Number of prosecutions.	Number of persons prose uted.	Number convicted.	Numbers of rules and sections of the Act contravened.	Benarce,
	Manblum	1	2	2	Section 20, Rule 12 of Notification No. 864-68-20, dated 10th March 1904.	
	1)0.	1	2	2	Section 20, Rules 3, 19 and 22 of Notification No. 864-68-20, dated 10th-March 1904.	
	Do	1	1	. 1	Section 20, Rule 8 of Notification No. 864-68—20, dated 10th March 1904.	  -
	Do	1	3	3	Section 20, Rule 19 of Notification No. 804-68-20, dated 10th March 1904.	
	Do	1	1	1	Section 20, Rules 1(b), 7 and 14 of Notification No. 864-68-20, dated 10th March 1904.	
	Do. '.	1	4 .	1	Section 20, Rule 19 of Notification No. 864-68-20, dated 10th March 1904.	
1	Do	1 1	1	4++	) 1002.	Acquitted.
į	Do	1	1	1	Section 20, Rule 12 of Notification No. 861-68-20, dated 10th March 1904.	
	Hazaribagh .	1	2	. 2	Section 20, Rule 19 of Notification No. 6436-152, dated 2nd September 1911.	
ihar and Orissa }	Do, .	1	1	1	Section 20, Rule 4 of Notification No. 11793—103, dated 80th December 1908 as amended by Notification No. 5072—118, dated 1st July 1916.	4
	Do	1	3	8	Section 20, Rule 3 of Notification No. 8436-152, dated 2nd September 1911.	
]	Manbhum .	1	- 1	1 j	· .	
	Do	1	1	1		
<b>!</b>	Do. ,	1	1	1	·	
	Do	1	1			Withdr a w
	Hazaribagh	1	2	2		Accused n traceable.
	ν₀. ,	1	1	ı		
	od	1.	1		<u>.                                    </u>	Withdra wn
}	Do	1	2	1	Section 20, Rule 1 of Notification No. 11708—103, dated 30th Decem- ber 1908, as amended by Notification	Accused n traceable.
	Do	1	1	***	No. 5072—113, dated 1st July 1916.	Withdrawn.
1	Do.	1	2	1		
	Do	1	1	1		
ļ	Do.	1	2	1		
. }	Do	1	2	2		
{	Do	1	1	•••		Acquitted :

## APPENDIX III—concld.

# PROSECUTIONS UNDER THE INDIAN MINES ACT, 1901-concld.

Statement of prosecutions instituted under the Indian Mines Act, 1901, during the year 1919—concld.

Paovince.	District.	Number of prosecutions.	Number of persons prosecuted,	Number convicted.	Numbers of rules and sections of the Act contravoued.	Benates,
	Burdwan	1	2	2	Section 20, Rules 3, 4 and 19 of Notification No. 864-68-20, dated 10th March 1904.	
	Do.	. 1	1	1	Section 13 (1), and Rule 19 of Notifica- tion No. 864-68-20, dated 10th March 1904.	
	Do.	. 1	1	1	Section 13 (1), and Rule 1(a) of Notification No. 864-68—20, dated 10th March 1904.	
Bengal . 4	Do.	. 1	2	2	Section 20, Rules 3, 7 and 19 of Notification No. 864-68-20, dated 10th March 1904.	
	Do.	. 1	2	2	Section 20, Rules 7, 13 and 19 of Notification No. 864-68—20, dated 10th March 1904.	
	Do.	. 1	1	1	Section 20, Rules 7 and 20 of Notification No. 864-68—23, dated 10th March 1904.	
	Do.	. 1	1	. 1		
•	Do.	. 1	2		Section 20, Rule 1 of Notification No. 11793-103, dated 30th Decomber 1908, as amended by Notification No. 5072-113, dated 1st	Withdraw
Central Provinces	Jabalpur	. 1	2	***	tion No. 5072-113, dated 1st July 1916.	Acquitted.
Madras .	. Nellore	. 1	3	8	<u> </u>	
-						
i .				;		
•						
		,				
					·	
			,			
					-	<b>}</b>
						-
. ,			,			

## APPENDIX IV.

### MISCELLANEOUS.

## Statement No. 1.

## List of Inspection Circles.

No. 1 Circle.	No. 2 Circle.
<ol> <li>All mines in Bihar and Orissa except mines in the district of the Santhal Parganas and such mines in the district of Manbhum as lie east of a line drawn from mile 175 on the Bongal Nagpur Railway to mile 169 on the Grand Trunk Road and continued in a straight line across the district.</li> <li>All mines in Baluchistan.</li> </ol>	<ol> <li>All mines in Bengal.</li> <li>Such mines in Bihar and Orissa as lie in the district of the Santhal Parganas and in the district of Manbhum east of a line drawn from mile 175 on the Bengal Nagpur Railway to mile 169 on the Grand Trunk Road and continued in a straight line across the district.</li> </ol>
3. All mines in the North-West Frontier Province.	3. All mines in Bombay.
4. All mines in the Panjab.	4. All mines in the Central Provinces.
5. All mines in Rajputana.	5. All mines in Madras.
G. All mines in Assam.	6. All mines in Burms, other than those in the Tavoy District.

#### No. 3. Circle. All mines in the district of Tavoy, Lower Burma.

### Statement No. 2.

List of holders of certificates as managers of coal mines in British India.

(a) Cortificates granted to holders of English Certificates of competency.

## FIRST CLASS.

Nawe.		No. of Indian certificate.	Date of Indian certificate.	No. of English certificate.	Date of English certificate.
Provan, Joseph Chapman .		212	22nd January 1919	2348	13th January 1904.
Curley, James		213	Ditto .	1522	16th June 1899.
Ford, Leo Dorey		214	Ditto .	. 16	30th January 1913.
Potter, Robort	•	215	17th February 1919	. 364	24th January 1917.
Robb, William David		216	7th July 1919 .	. 427	27th July 1917.
Weir, Walter		217	Ditto .	. 1732	19th June 1900.
Cox, John William		218	26th July 1919 .	. 163	26th January 1915.
Prentice, John Robertson .	•,	219	Ditto .	. 485	24th January 1918.
Brown, Hugh		220	Ditto .	401	27th July 1917.
Brady, Hugh	•	221	13th October 1919	4	30th January 1913.
Hanson, William Brooks .	•	222	Ditto .	411	27th July 1917.
Spray, William Alfred .		223	Ditto .	561	26th July 1918.
Bryan, Robert	•	224	Ditto :	. 373	27th July 1917.
Smillie, James	•	225	Ditto .	4070	10th June 1912.
Wilcox, William, H	•	226	Ditto .	. 3644	9th June 1910.
Semple, Francis Bernard		227	Ditto .	. 180	26th January 1915.
Cunningham, Andrew Mitchell	•	228	Ditto .	4033	10th June 1912.

## MISCELLANEOUS—contd.

## Statement No. 2-contd.

# List of holders of certificates as managers of coal mines in British India—contd.

### (b) Certificates of competency. FIRST CLASS.

					_			
Nam	۵.					No. of certificate.	Date of certificate.	Remarks.
Adamson, Bertie	•		•		_	111	7th July 1919.	
Mukberji, Indu Bhusan .		•	•	•		112	Ditto.	
Ward, Wesley Ashbury .	•	•	•	•	-	118	Ditto,	
					•	Second (	Class.	·
Gibson, Albert . 7	÷	;	•	÷	•	158	15th July 1919 • •	lst class candidates recommend
Allan, Herbert Durham .	•	٠	•		إ.	169	Ditto	ed for 2nd class certificates,
Connolly, William John ,		•	•	•	-	170 .	Ditto.	
Sheehan, Frederick George	•			•		171	Ditto.	
Banerji, Jotindra Nath .	•			•		172	Ditto.	
Caddy, Douglas George		. •		•		178	Ditto.	
Durham, Vivian Clyde .	•	•	. •	٠.		174	Ditto.	
Roy, Ram Gobinda .	•	•			,	175	Ditto.	
Simon, Cyril Paul	•	•	•	•		176	Ditto.	
Chatterji, Aroon Kinkar	•	•	•	•		177	Ditto.	
Mitra, Birendra Nath .	•		•			178	Ditto.	
Mukherji, Pataki Charan	•	•	•	•		179	Ditto.	
Mazumdar, Pravakar			•	. •		180	Ditto.	
Chatterji, Kshetra Mohan		•		•		181	Ditto.	
Samanta, Satya Kinkar	•		•		•	182	Ditto.	
Mahats, Jyotish Chandra					•	183	Ditto.	
, Chatterji, Hrishi Kæi	•		•	•		184	Ditto.	: \
Mukherji, Dhirendra Nath	•	•	•	-	•	185	Ditto.	
Varma, D. R.	•	•.	•	•		186	Ditto.	
Roy, Asita Bhusan	`•	•		•	•	187	Ditto.	
Bancrji, Aditya Chandra	•		•	•		188	Ditto,	
Chatterji, Nritya Gopal			, r.	,•		189	Ditto,	
Sama Bhola Nath		•				190	Ditto.	

## MISCELLANEOUS—contd.

## , Statement No. 2-concld.

# List of holders of certificates as managers of coal mines in British India—concld.

### (o) Certificates of service.

### FIRST CLASS.

N	'AMR,					No. of certificate.	Date of certificate.	Remarks,
Tyore, John Emanual .	•	•	•	•	٠	151	22ud January 1919.	
Hyde, Joseph	•	•	•	•		152	15th July 19 <b>19.</b>	•
Biddle, Leonard Alexander	•	•	•	7		158	Ditto.	
Mondol, Upendra Nath .	•	•		•		154	Ditte.	
Griffiths, James		•		•	,	155	Ditto.	
						,		•
								• •

#### (d) Certificates of service.

#### SECOND CLASS.

		Nam	z.	-				No. of certificate.	Date of certificate.	Remarks.
Parsons, Issachar	•	•	•	•	•	•	•	199	15th July 1919.	
York, Bonjamin	•	:	•		•	•	•	200	26th July 1919.	
Vhile, Bonjamin	•	•	•	•	•	•	•	201	Ditto.	~
Lhmad, Qurban	•	٠	•	•	•	•	•	202	Ditto.	
										•

## MISCELLANEOUS-contd.

## Statement No. 3.

List of Universities and Colleges approved by the Governor-General in Council for the purposes of Rules 32 and 33 under the Indian Mines Act, 1901.

Name of Institution and Degree or Diploma.	Date.
University of Birmingham in respect of its Degree of B.Sc. in Mining and Diploma in Mining.	11th June 1904.
University College of Bristol in respect of its Senior Diploma in Mining.	16th September 1904.
University of Cambridge in respect of its Diploma in Mining Engineering.	.6th June 1905.
University of Durham in respect of its Degree of B.Sc. in Mining. Durham College of Science in respect of its Diploma in Mining. University of Glasgow in respect of its Degree and Diploma in Mining.	21st December 1903. 29th June 1904. 28th September 1904.
Glasgow and West of Scotland Technical College in respect of its Diploma in Mining.	28th June 1904.
University of Leeds in respect of its Degree of B.Sc. in Mining and Diploma in Mining.	21st November 1904.
University of London in respect of lits B.Sc. Degree in Mining for Internal Students, subject to the Degree being endorsed by the University with a certificate of four months' practical experience in a mine.	9th June 1905.
University of London in respect of its B.Sc. Degree in Mining for External Students, subject to the Degree being endorsed by the University with a certificate of four months' practical experience in a mine.	7th August 1906.
Royal School of Mines in respect of its Associateship in Mining. University of Oxford in respect of its Diploma B. for Colliery Engineers (in Scientific Engineering and Mining subjects).	24th March 1904. 11th February 1905.
University College of Sheffield in respect of its Diploma in	15th July 1904.
Mining. University College of South Wales and Monmouthshire in respect	19th April 1904.
of its Diploma in Mining. Wigan Mining and Technical College in respect of its Diploma	26th August 1904.
in Mining.  Bengal Engineering College, Sibpur, in respect of its Diploma in	22nd February 1907.
Mining.  Merchant Venturers' Technical College, Bristol, in respect of its	5th October 1905.
Diploma in Mining Engineering. Victoria University of Manchester in respect of its Degree and	14th February 1906.
Certificate of Mining. University College of Nottingham in respect of its Diploma in	28th March 1906.
Mining Engineering. University of Sheffield in respect of its Degree of Bachelor of	30th June 1906.
Engineering (Mining).  Heriot-Watt College in respect of its Certificate in Mining	16th January 1903.
Engineering.  Calcutta University in respect of its Degree of Bachelor of	24th September 1910.
Engineering in the Branch of Mining Engineering.  Harvard University, Cambridge, Massachusetts, in respect of its	22nd February 1913.
Diploma in Mining Engineering.  Columbia University, New York, in respect of its Degree of	13th March 1915.
Engineer of Mines.  California University, United States of America, in respect of	19th February 1916.
its Degree of Mining Engineer. Pittsburg University, United States of America, in respect of its	19th February 1916.
Degree of Engineer of Mines.  Leland Stanford Junior University, California, in respect of its  Degree of Bachelor of Arts in Geology and Mining.	10th August 1918.

#### MISCELLANEOUS—contd.

#### Statement No. 4.

#### BENGAL ENGINEERING COLLEGE.

THE MINING CLASSES.

Admissions to the Diploma Course in Mining at the Civil Engineering College, Sibpur.

The Diploma Course covers two sessions, commencing yearly in April, and lasting till the examinations in the following March. (There is a vacation of about three months in August, September and October.) Six weeks of each session is spent at a camp of mine surveying in the collicry districts.

Two classes of students are admitted-

Regular-who need have no experience of Mining.

Special—who have had about two years' previous experience of coal-mining (under ground.)

#### Admissions are made as follows :--

Regular students.—Age may not exceed 20 on January 1st of the year of admission—

- A.—Through a special preparatory course of one year's duration at the Civil Engineering College. Admissions at the beginning of February.
- B.—Through the Sub-Overseer classes (a two years' course) at Dacca, Burdwan, Rajshahi and Pabna in Bengal; Bankipore and Ranchi in Bihar and Orissa.

#### Special students-

C.—Direct from the mines to the Mining classes without passing through either A or B. Admissions at the beginning of April. Applications must be made by 1st March accompanied by certificates from the colliery managers under whom the candidate has served, showing the period and nature of his employment underground.

## Admission qualifications to A, B and C-

The passing of the Matriculation Examination, the Junior Cambridge Examination, the Examination held at the end of the supplementary course for elementary European schools, or equivalent.

The number that can be admitted is limited. The selection of candidates rests with the Principal who, all other things being equal, will prefer the younger of two candidates.

## Scholarships awarded by the Bengal Government-

For Regular students-

Scholarships of the following number and value are available for Regular students admitted under A, these are awarded on the result of the examination held at the end of the preparatory course A:—

Two of Rs. 12 monthly.

Three " 6 "

Stipends awarded by the Bihar and Orissa Government-

Two Boarding stipends of Rs. 15 monthly tenable for three years by poor and capable students of that Province. These are available in either the Mining or Mechanical and Electrical Engineering classes.

### For special students.—Awarded by the Bengal Government—

Awarded on the result of the examination held at the end of the lectures given in the colliery districts by the Instructor in Mining—

One of Rs. 50 for Europeans. One or two of Rs. 25 for Indians.

These amounts should be sufficient to maintain a special student resident at the college. For further particulars apply for the Apprentice Department Circular.

B. HEATON,

Principal, Bengal Engineering College, o topur.

#### MISCELLANEOUS—contd.

#### Statement No. 5.

## MINING INSTRUCTION IN BENGAL AND BIHAR AND ORISSA.

[The Mining Education Advisory Board desire that Colliery Managers will kindly publish this information in their collieries. An appeal is also made to them to support the lectures by seeing that members of their colliery staff, who are suitable, take advantage of the lectures and attend them regularly.]

The full course comprises two parts, the lectures in which are delivered in alternate years as follows:—

The principles of Coal Mining 1920-21, 1922-28, etc.

The principles of Mcchanical Engineering of Coal Mines 1919-20, 1921-22, etc.

A fee of Rs. 5 (five rupees) payable to the Mining Instructor on the first registration of his name is charged to each student for each year's series of lectures. This fee is non-returnable.

#### Programme for Session 1919-20.

LECTURES on the Principles of Mechanical Engineering of Coal Mines will be delivered in English by Mr. H. C. Read, Mining Instructor, as follows:—

#### JHARIA COAL-PIELD.

Jharia ... Lecture-room near Club ... Mondays ... 5-30 p.m.
Sijua ... Lecture-room near Station ... Tuesdays ... 5-0 ,,

#### RANIGANJ COAL-FIELD.

Deshergarh ... Lecture-room near Club ... Wednesdays 5-30 p.m.
Raniganj ... Old Railway Institute ... Thursdays ... 5-0 ,,
Jamuria ... Chief Mining Engineer's office,
Sibpur Colliery ... Fridays ... 5-30 ,,

The course of instruction, consisting of not less than 80 lectures, will commence the first week in September and end in the following April. The examination will be held early in May. Candidates who pass the examination will receive a certificate recording their success. No candidate will, however, be permitted to sit for the examination unless he has attended 50 per cent. of the lectures and received 40 per cent. of the marks allotted for home work.

Rupees 100 monthly is offered in scholarships awarded by the Mining Education Advisory Board on the results of the examination, these will be tenable for two years at the Bengal Engineering College and are granted to enable the holders to attend the full course for the Diploma in the Principles of Mining. One scholarship of Rs. 50 is reserved for Europeans and two of Rs. 25 are awarded to Indians.

The following Local Committees have been appointed:-

#### RANIGANI COAL-FIRLD.

Jamuria Centre.

#### Deskergark Centre.

Mr. H. Lancaster, Chairman.

(Deshergarh).
,, Geo. Miller (Sitarampur).

" F. Owen (Deshergarh). Babu M. N. Roy (Begunia).

" P. C. Tarafdar (Mugma). " S. N. Ghosh (Barakar). Mr. H. Lancaster, Chairman, ,, P. S. Keelan (Charanpur).

"T. Samson (Charanpur).
"H. L. Wilkinson
(Sibpur).

" W. S. Elphinstone (Asansol). Babu Atul Shashi Mitra (Asansol).

### Raniganj Centre.

Mr. H. Lancaster, Chairman., P. S. Keelau

(Charanpur).

A. T. Creet

(Kalipahari). "W. J. Rees (Raniganj). Babu Promotho Nath Hazra

(Toposi).
, Kali Kumar Misra
(Scarsole Raj Estate).

S. Chaudhuri (Jamehari, Raniganj).

## MISCELLANEOUS—contd.

#### Statement No. 5-conld.

#### JHARIA COAL-PIELD.

#### Jharia Centre.

Mr. F. L. G. Simpson, Chairman. R. G. M. Bathgate (Jamadoba).

J. Kirk (Kustore).

J. B. Argy'e (Lodna).

R. Barrowman (Standard Coal Company, Jharia).

Babu Goburdhan Das Manishankar (Jharia).
"Narendra Nath Sarkar (South Kujama, Jharia).

### Sijua Centre.

Mr. F. L. G. Simpson, Chairman.

" A. A. Agabeg (Sijua).

", R. Heron (Ekra, Bansjora).
", H. M. Bull (Bansjora).

-,, G. C. Leach (Sijua P. O.)

Babu Trikumdas Doyal (Bansjora).

Basanta Kumar Roy (Kirkend).

#### B. HEATON,

Secretary, Mining Education Advisory Board, B. E. College, Sibpur Botanic Garden, P. O. Howrah.

#### SYLLABUS OF THE COURSE OF INSTRUCTION.

The lectures in the following courses are delivered in alternate years :-

### THE PRINCIPLES OF COAL MINING.

- 1. Geology.—General structure of the earth's crust: igneous and aqueous rocks; definitions of outcrop, dip, strike, fault, roll, wash-out and dyke, etc.; recording geological observations, reading a geological map; description of the Indian coal bearing rocks; composition and properties of coal. Commercial values of coal.
- 2. Exploration .- Prospecting, trial shafts and trenching; advantages of boring; methods of boring; driving through faults, uses of borcholes in mines, etc.
- 3. Breaking ground.—Common tools; storage and use of explosives; electric fuses; machine drills; coal-cutting machines.
- 4. Sinking.—Site of colliery; position of inclines and shafts, their excavation and shape, apparatus used in sinking; lining shafts; arrangements at top of sinking shaft; brief mention of special methods of sinking.
- 5. Methods of working.—Quarrying, advantages of bench work, disposal of soil; shaft pillars; pillar and gallery method, working thick seams in stages, extraction of pillars, panels; brief description of longwall and chambering methods.
- 6. Supporting.—Props and lids, bars, checks or cogs, square sets, special timbering of loose ground; arching; steel girders; packing; dry and hydraulic stowing.
- 7. Mine gases.—Their experimental preparation by chemicals, and illustration of their physical and physiological properties; their chemical composition; methods of detecting; explosions; spontaneous combustion of coal; dangers of coal dust.
- 8. Ventilation.—Ascensional currents, currents induced by the heat of steam or furnace; mine fans; friction of air in mines; theory of splitting the air; calculations of ventilating pressure, etc.; coursing the air; measurement of quantity of air; use of anemometer, watergauge, thermometer and barometer; reversing the air current.
- 9. Safety lamps.—Principle of the safety lamps; Sir Humphrey Davy's experiment; types of safety lamps; firedamp detectors.

## THE PRINCIPLES OF MECHANICAL ENGINEERING OF COAL MINES.

1. Applied Mechanics.—Mensuration; definitions of force, motion, friction, work and energy; the simple machines; mechanical and electrical units; hydrostatics; the siphon; pressure of gases; Boyles' law.

#### MISCELLANEOUS—coutd.

#### Statement No. 5-concld.

- 2. Steam, Electricity and Compressed air.—Theory of steam boilers and their fittings; the steam engine; the dynamo; the electric motor; the air compressor.
- 3. Winding.—Types of winding engines and description of parts; calculation of the dimensions of winding engines; strength of ropes and chains; detaching hooks; overwinding prevention devices; rope cappings; care and examination of ropes, buckets, cages, guide ropes.
- 4. Pumping.—The lift pump; the force pump; sinking pumps; pumps with positive valve motion; the pulsometer; turbine pumps; calculations of the dimensions of pumps; methods of supporting pumps and pipes; strength of pipes; pipe joints; dams to hold back water.
- 5. Hauling.—Tramways; tubs; hand tramming; horse haulage; self-acting inclines; locomotives; single rope haulage; main and tail rope haulage; endless rope or chain haulage; calculations of the dimensions of hauling engines, ropes, etc.; capping of haulage ropes; couplings; haulage clips, etc.; signalling.
- 6. Surface arrangements.—Headframes and pulleys; receiving frames; keps; arrangements of roads on pit bank; tipplers; simple screening and sizing; railway sidings; aerial ropeways.
  - 7. Simple treatment of coking and bye-product ovens.
- Adopted by the Mining Education Advisory Board at their meeting of 27th January 1917. Copies of this circular may be obtained from the Secretary or from the Instructor.

B. HEATON,

Secretary.

Bengal Engineering College, Sibrur;

The 6th August 1919.

#### Statement No. 6.

Regulations made by the Board of Examiners under Rule 30 of the rules applying to coal-mines made under Section 20 of the Indian Mines Act, 1901, for the conduct of examinations for Colliery Managers' certificates of competency.

- (1) No member of the Board of Examiners shall act as a local examiner, except in emergent cases:
- (2) When possible one or more members of the Board of Examiners shall attend every examination on at least one of the days.
  - (3) So far as is practicable, the local examiners shall be:-
    - (a) An Inspector of Mines, who shall be Secretary to the local examiners.
    - (b) Two Mining Engineers or Colliery Managers who must be the holders of first class certificates. Provided that a Mining Professor may be appointed instead of one of the Mining Engineers or Managers.
- (4) The remuneration of each local non-official examiner shall be Rs. 150 for each examination, and a capitation fee of Rs. 2 for each first class candidate and Re. 1 for each second class candidate examined, and travelling expenses and halting allowances on the first class scale under the Civil Service Regulations; but an Inspector of Mines, acting as a local examiner, shall not be entitled to any fee or remuneration whatsoever, beyond the travelling expenses and halting allowances due to him in his official capacity.
- (5) The examinations will be advertised at least four months before the date of the examinations and applications, supported by original certificates, as to experience and character and fees will be received up to a date, duly advertised, one month prior to the examinations. No application which is not supported by the certificates and fees referred

## MISCELLANEOUS-contd.

## Statement No. 6-contd.

to above will be considered by the Board if submitted after the advertised date for receiving such applications and fees.

- (6) The subjects for examination shall be :-
  - (a) Arithmetic and handwriting.
  - (b) Practical and theoretical coal-mining, including surface and underground arrangements, sinking, timbering, ventilation, gases met with in coal-mines, a knowledge of plans, surveying and levelling, and of the various instruments used in mining. Questions may also be asked upon geology, sanitation, hydraulics, explosives, safety lamps and similar subjects. The candidates may also be required to show how to arrange the ventilation and haulage of a mine on a given plan.
  - (c) Practical mechanics, including steam, steam-engines, steam-boilers, pumps and strength of materials; and questions may be asked upon electricity and compressed air as applied to coal-mining.
  - (d) The Indian Mines Act, 1901, and rules made under the Act.
- (7) The examination shall be both written and oral and the subjects and conditions shall be the same for candidates for both classes of certificates; but the examination questions shall be made suitable for each class of certificate.

The examiners shall have power to eliminate the oral examination in the case of candidates who do not reach a standard in the written examination to be prescribed by the Board of Examiners.

(8) The following should be the maximum number of marks given for each subject :--

		ı	PIRST CLASS,	"		SECOND CLASS.	
Subject,		Papers.	Fina voce.	Total.	Papers.	Viva voce.	Total.
1		2	8	4	5	. 0	7
(a) Arithmetic and handwriting	•	50	***	50	<b>5</b> 0	100	<b>5</b> 0
(b) Mining		160	60	220	14)	80	220
(c) Mechanics	·Ì	110	40	150	100	50	150
(d) Indian Mines Act		60	20	80	<b>5</b> 0	30	80
TOTAL	٠. -	380	120	500	340	160	500

- (9) No candidate who fails to obtain 66 per cent of the total number of marks or 33 per cent in either of the subjects of mining or mechanics, shall be passed by the examiners, and if a candidate fails to obtain 33 per cent of the marks given for either of the subjects of Arithmetic and handwriting or the Indian Mines Act, any marks he may have obtained in such subjects shall not be included when the total is determined.
- (10) Before each examination each candidate shall declare whether he presents himself for a first or second class certificate. No candidate for a second class certificate shall be eligible at that examination for a first class certificate, but a candidate for a first class certificate, who does not reach the necessary standard, may, nevertheless, at the discretion of the local examiners, be recommended, to the Board of Examiners for a second class certificate, if, in-their opinion, he has done sufficiently well to deserve it.
- (11) The Scoretary to the local examiners shall report, by registered post, the result of the examination giving the number of marks obtained by each candidate in each subject, to the President of the Board of Examiners within one month of the close of the examination.
- (12) The questions which the local examiners intend to put in the examination papers shall be submitted in draft to the Board of Examiners, for approval, at least six weeks before the date of the examination. Answers to questions on Arithmetic and those involving calculations and all plottings and levellings must be submitted to the Board of Examiners along with the question papers.
- (13) At least one examination for first class candidates and at least one examination for second class candidates shall be held annually in one of the Bengal or Bihar and Orissa

#### MISCELLANEOUS—contd.

#### Statement No. 6-concld.

coal-fields; and in other parts of India examinations will be held whenever, in the opinion of the Board of Examiners, the number of candidates in a coal-mining centre justifies the holding of an examination.

- (14) No candidate will be allowed to take part in the examination until he has produced an authorization from the Board of Examiners.
- . (15) Every candidate before taking his seat must sign a register, in which he will be given a definite number. He must sign his name and write his registered number at the top of every page of the paper on which he writes the answers to the questions.
- (16) The number of the question must be given in bold figures before the answer to each question.
- (17) The calculations and work by which a result is obtained must be clearly shown in immediate connection with the answer to each question.
  - (18) Answers must be strictly confined to the questions asked.
  - (19) Sketches may be made to make answers clear.
- (20) When sketches are asked for, it should be understood that, unless otherwise stated, freehand sketches, with dimensions, are all that is necessary, and candidates should not spend time in making finished drawings.
- (21) Any candidate speaking to any other candidate during the examination, or using any book, notes or private paper, or acting in any manner which the examiners consider improper will be liable to be disqualified at their discretion. The Board of Examiners may in such a case use their discretion as to allowing the candidate to sit at any future examination.
- (22) When a candidate has completed the answers to the questions, or when the time allowed for answering the questions has elapsed, or he has been disqualified, he must hand the paper of questions and his answers to the examiners, and at once leave the examination room.
- (23) A time table will be supplied to each candidate at the commencement of the first day's examination.
- (24) The oral examination will be held at a subsequent date. Only those candidates who obtain a certain degree of proficiency in the written examination will be examined orally. Due notice of time and place will be sent to each candidate required by the examiners for oral examination.
- (25) The number of marks given for each question will be shown in brackets at the end of the question.
- (26) Ink and paper will be provided, and no paper other than the official paper provided may be used. Candidates must bring their own pens and pencils, drawing pens and drawing instruments, including a protractor.

All previous Regulations are hereby cancelled.

G. F. ADAMS,

Chief Inspector of Mines in India and ex-officio President of the Board of Examiners.

DHANBAD,
The 24th February 1919.

Statement No. 7.

No. 219-D.

GOVERNMENT OF INDIA.

## DEPARTMENT OF COMMERCE AND INDUSTRY.

Delhi, the 17th January 1920.

NOTIFICATION.

(MINES REGULATIONS.)

In exercise of the power conferred by section 20 of the Indian Mines Act, 1901 (VIII of 1901), Governor-General in Council is pleased to direct that in the rules regarding Mines

#### MISCELLANEOUS-contd.

#### Statement No. 7-concld.

Managers and their certificates published with the notification of the Government of India in the Department of Commerce and Industry, No. 2968-82 (G. & M.), dated the 21st April 1906, as subsequently amended, the following amendments shall be made, namely:—

- (1) For rule 29 of the said rules the following shall be substituted, namely:-
  - "29. Certificates of competency under these rules shall be granted by the Board of Examiners and their decision regarding the grant of such certificates shall be final. Certificates granted by the Board shall hold good throughout British India, and shall be of two classes, namely, first and second class."
- (2) Rules 38, 39 and 40 of the said rules are hereby cancelled.
- 2. The amendments shall take effect from the 30th June 1920.

A. H. LEY,

Secretary to the Government of India,

#### Statement No. 8.

#### LAND ACQUISITION (MINES) ACT, 1885.

Particulars required to be furnished by colliery owners to Local Governments when giving notice under Section IV of the Land Acquisition (Mines) Act, 1885, of their intention to work coal under land acquired for a railway:—

- (a) The name, residence and profession of the person giving the notice.
- (b) The name of the mine, together with that of the village and district in which the mine is situate.
- (c) The name of the railway line or of the siding and the main line to which the siding is attached, under which the mine is situate.
- (d) The names of the railway stations and the mileage between which the said siding or the said portion of the railway land, under which the mine is situate, falls.
- (e) The number and date of the declaration under which the land was acquired.
- (f) A tracing showing the boundaries of, and the area over which, the acquired land extends.