REPORT OF THE COMMITTEE ON INSTRUMENTATION FOR **DAMS & HYDRAULIC STRUCTURES** 

PART I 2 TT



MINISTRY OF IRRIGATION AND POWER GOVERNMENT OF INDIA NEW DELHI December, 1965 \*

सन्धमेव जयते

C.W. & P.C. No. 164

.

15th April 1968

.

The Report is in two parts.

,

.

Part I is a general report dealing with the specific terms of reference embodied in the Government Resolution.

Part II (Separate Volume) is a detailed report describing necessity for instrumentation of important structures, the objectives to be sought, the nature of the measurements to be made and a description of the various instruments generally adopted for such measurements.

(iii)

### TABLE OF CONTENTS

•

No.	ITEM	AGE
	Letter of Transmittal	IX XI
	PART I	
	(General Report)	
1.0	Term of reference-I	3
1.1	General review	3
1.2	General examination of data, results and interpretation	. 4
	A. Concrete Dams	4
	1. Displacements	4
	(a) Plumb line	4
	(b) Geodetic observations	5
	(c) Joint meters	5
	(d) Foundation deformation measuring devices.	5
	(e) Tilt measurement devices	6
	2. Stresses	6
	3. Strains	6
	4. Pore pressures	6
	5. Temperature	6
	6. Uplift pressure	6
	7. Seepage measurements	7
	8. Recommendations	8
	B. Masonry Dams	. 8
	1. Displacements	8
	(a) Plumb line	8
	(b) Geodetic observations	8
	(c) Joint meters	8
	(d) Foundation deformation measuring devices	9
	(e) Tilt measurement devices	9
	2. Stresses	9
	3 Strains	ģ
	4. Pore pressures	9
	5. Temperature	10
	6. Uplift pressure	10
	7. Seepage measurements	10
	8. Recommendations	10
		-
	C. Earth Dams $\ldots$ $\ldots$ $\ldots$ $\ldots$ $\ldots$ $\ldots$	10
	1. Displacements · · · · · · · · · · · · · · · · · · ·	10
	(a) Surface markers	10
	(b) Internal vertical displacement (cross arms)	10
	2. (a) Measurement of vertical strains	11
	(b) Horizontal strain (internal displacement).	11
	3. Pore pressure measurements	12
	(a) Stand pipes	12
	(b) Hydraulic piezometers	12
	4. Earth pressure cells	13
	5. Recommendations	14

No.		Ттем	Paée
	D. Other Structures		15
	1. Displacements	• • • • • • • • • •	15
	(a) Mechanical methods		15
•	(b) Optical methods		15
,	(c) Angular changes	• • • • • • • • • •	15
	2. Stresses	• • • • • • • • • •	16
	3. Strains (a) Mechanical measurement of strain	•••••••••	16
	(b) Electrical measurement of strain	• • • • • • • • • • •	16 16
	4. Dynamic measurements		16
	5. Temperature		16
	6. Visual observations	• • • • • • • • • • •	16
	7. Recommendations		17
<b>2</b> ·0 <sup>`</sup>	Term of Reference (ii)	• • • • • • • • • •	18
3.0	Term of Reference (iii)	• • • • • • • • • •	19
3.1	Instruments for measurement of displacement .		19
3 • 1 • 1	Concrete and masonry dams	• • • • • • • • • •	19
3 • 1 • 1 • 1	For geodetic observations		19
3 <u>·</u> 1·1·2	For plumb line observations	• • • • • • • • • •	19
3.1.1.3	For Joint movement observations		19
3.1.1.4	For observation of foundation deformations .	· · · · · · · · · · ·	19
3.1.1.5	For observation of tilt	• • • • • • • • • •	20
3 • 1 • 2	Earth dams		20
3.1.2.1		• • • • • • • • • • •	20
3.1.2.2	For internal vertical movement observations.	• • • • • • • • • •	20
3.1.2.3	For Internal horizontal movement observations	••••••••	20
3.1.3	Other structures		20
3.1.3.1	Optical measurements	• • • • • • • • • •	20
3.1.3.2	Mechanical measurements	• • • • • • • • • •	20
3.1.3.3	Electrical measurements	• • • • • • • • • •	21
	Dynamic measurements	• • • • • • • • • •	21
3.2	Instruments for measurement of stress	• • • • • • • • • •	21
3.2.1	For concrete dams	• • • • • • • • • •	21
3·2·2 3·2·3	For masonry dams	• • • • • • • • • •	21
3.2.3	Other structures	• • • • • • • • • • •	21
3.2.4	Instruments for measurement of strain	•••••••••	21
3.3.1	Concrete dams		21
3.3.1	Masonry dams	· · · · · · · · · · · ·	21
3.3.2	Earth dams		22
3.3.4	Other structures	· · · · · · · · · · · ·	22
3.4	Instruments for measurement of pore pressures in t	he interior and uplift pressures at foundation level	22 22
3.4.1	Concrete and masonry dams		22 22
3.4.2	Earth dams		22
	$\mathbf{h}$		-4

No.							-		. Ith	M	-				•					PAGE
8.5	Instruments for measu	reme	nt of	temj	perati	ıre		•	•	•	•	•	•	•	•	•	• '	•		22
3·5·1	Concrete and masonry	y dan	15	•	-•	•		•	•	•		•	•	•	•	•	•	• ·	•	22
3·5·2	Other structures	•	•		•		,	•		•	•	•	•	•		•	•			22
6.6	Instruments for measu	reme	at of a	appli	ieđ lo	ađs		•	•	•	•	•	•	•		•		•		22
<b>↓</b> ·0	Term of reference-IV	•	•	•		. •		•		•	•			•		•				- 24
5·0	Term of reference-V		•	•	•			•		•	•	•	•			•				26
	Present procedure		•	•	•	•		•	`•	•	•		•	•	•	•	•	•		26
	Discussion of the pres	ent p	roceđ	ure	•			•	•	•	•	•	•		•			•	•	20
	Recommendations		•	•	•	•		•	••	•	•	•		•	•	•	•			26
5·0	Term of reference-VI		•	•	•			•	•	•	•	•		•	•				•	28
7.0	Term of reference-VII				•	•		•	•					•		•	•	•		29

.

-

# PAGE

# Appendices

No.	Ітем	PAGE
	Appendices	,
<b>0</b> ·01	Copy of Resolution of Government of India, Ministry of Irrigation & Power, constituting the Committee .	33
0.02	Proforma statements A & B	35
0.03	Tabulation of information regarding instrumentation status at various projects facing	36
0.04	Copy of Resolution of Government of India, Ministry of Irrigation & Power, extending Committee's tenure to Sept. 30, 1965	37
0.02	Copy of Resolution of Government of India, Ministry of Irrigation & Power, extending Committee's tenure to Dec. 31, 1965	, 38
I-1 ·01	Copy of letter dated Feb. 23, 1965 from Prof. J. M. Raphael, University of Calif., U.S.A	39
I-1 ·02	Copy of letter dated March 10, 1965 from Dr. Roy W. Carlson, California, U.S.A.	40
I-2·01	Requirements of instruments for projects up to the end of Fourth Plan period	. 41
I-3·01	Specifications for Wilde T-3 Precision Theodolite for Triangulation	44
I-3 02	Specifications for Wilde N-3 Precision level	45
I-3 ·03	Specifications for Micrometer Slide and Microscope	46
I-3 ·04	Typical Specifications for Huggenberger Whittemore Gauge	47
I-3·05	Specifications for Carlson's Elastic Wire Jointmeter	48
1-3.06	Specifications for Huggenberger type Optical Clinometer	49
I-3·07	Specifications for Maihak vibrating wire type clinometer	50
I-3·08	Specifications for Milne-Shaw Seismograph (tiltmeter)	51
I-3·09	Specifications for Wilson slope Indicator	53
I-3·10	Typical Specifications for Dial Gauges	54
I-3 · 11	Typical Specifications for Mikrokater	· 55
I-3·12	Specifications for Carlson Elastic Wire Stressmeter	56
I-3·13	Specifications for Vibrating Wire Stress meter	57
I-3·14	Typical Specifications for Dydic Gauge	58
I-3·15	Specifications for Carlson Elastic Wire Strainmeters	59
I-3 · 16	Specifications for Maihak Vibrating Wire Strainmeter	60
I-3-17	Typical Specifications of SR-4 strain gauge	61
I-3 · 18	Specifications for Concrete Gauge	62
I-3 · 19	Specifications for Hydraulic Piezometers	63
I-3·20	Specifications for Carlson Resistance Thermometer	65
1-3.21	Specifications for Thermo-Couples	66
	Figures	
I-1 ·01	Deflection of Vertical Cantilevers	67
I-1·01 I-1·02	Variation of deflection with time . :	68
I-1 02	Variation of deflection with reservoir level	69
I-1·03	Comparison of Theoretical and observed deflections	,0
I-1·04 I-1·05	Uplift pressure profile	71
I-1·05	Variation of uplift pressure with time	72
I-1·00	Variation of seepage with time	73
t-t .0/	A Marthielder An machenDa Litzer annen	

## BHAKRA & BEAS DESIGNS ORGANIZATION, KAKA NAGAR, NEW DELHI-11

No. 1044-47/CDE December 28, 1965.

То

The Secretary to the Govt. of India, Ministry of Irrigation & Power, New Delhi-1.

SUBJECT :- Final Report of the Committee on Instrumentation of Dams & Structures.

Sir,

Pursuant to Resolution No. 20(31)/63-Policy, dated October 31, 1964, of the Government of India in the Ministry of Irrigation & Power, a Committee was constituted for the study of instrumentation of dams and structures in its various aspects. 1 have the pleasure to submit herewith the final report of this Committee.

The Report is in two parts. Part I is a general report dealing with the specific terms of reference embodied in the Government Resolution. Part II is a detailed statement of the necessity for instrumentation of important structures, the objectives to be sought, the nature of measurements to be made and a description of the various instruments generally adopted for such measurements. The Committee has felt it desirable to add Part II of the Report so as to provide the background in the context of which Part I of the Report has been written.

It is hoped that this Report will not only serve its direct purpose, *i.e.* to examine instrumentation in all its aspects including a review of the instrumentation already done in the country and to recommend the best ways and means for the effective implementation of measurement programmes in our hydraulic structures but will also be a useful technical reference for those who might plan similar programmes in the future.

Yours faithfully,

(P. S. BHATNAGAR) Chairman, Committee on Instrumentation of Dams & Structures.

Encl: Report in two parts.

Copy with enclosures to :

- (i) Chairman, Central Water & Power Commission, New Delhi.
- (ii) Member (Design & Research), Central Water & Power Commission.
- (iii) General Manager, Beas Project, Talwara.
- (iv) General Manager, Bhakra Dam, Nangal.
- (v) All Members of the Committee.

2-3 C.W. & P.C./66

#### INTRODUCTION

1. A Committee was constituted by the Government of India in the Ministry of Irrigation and Power by Resolution No. 20(31)/63-Policy, dated 31st October, 1964 (Appendix 0.01) for a study of instrumentation in various dams and hydraulic structures after visits to dams where necessary. The Resolution laid down the following terms of reference :---

- (i) To make a general review of the instrumentation done so far in various dams in the country including general examination of data and results obtained therefrom and their interpretation as indicative of structural action :
- (ii) To assess future requirements of instruments upto the end of Fourth Plan, with particular reference to the requests of the projects now under construction:
- (iii) To examine different types (such as Carlson elastic wire type, vibrating wire type etc.) of instruments and recommend the best suited for our projects;
- (iv) To recommend the best arrangement for recording, storage, analysis and interpretation of field readings from instruments;
- (v) To recommend the most suitable method of procurement of instruments for various State projects in the absence of indigenous products:
- (vi) To examine the need for maintaining a stock of such instruments in the country, so that the requirements of projects can be properly met and instrumentation receives due implementation without any setback to the construction programme; and
- (vii) To formulate a programme for the progressive manufacture of these instruments indigenously.

2. The Committee comprised the following members :---

- (i) Shri P. S. Bhatnagar, Chief Design Engineer. Bhakra & Beas Designs Organization, Kaka Nagar, New Delhi. Chairman.
- (ii) Shri K. R. Datye, Superintending Engineer, Deccan Irrigation Circle III, Nasik. Member
- (iii) Shri B. Pant, Chief Research Officer. Central Water & Power Research Station, Poona. Member

- (iv) Shri I. P. Kapila, Director Designs, Bhakra & Beas Designs Organization, Kaka Nagar, New Delhi. **Member**
- (v) Shri V. K. Sondhi, Deputy Director, Central Water & Power Commission.

Member-Secretary.

3. The Committee held the following meetings:-

Date of meeting	Place of meeting	Members attending
Dec. 15, 1964	Instrumentation Labo- ratory, C.W.&P.R.S., Poona.	
<b>Jan. 28, 1965</b>	Gandhi Sagar Dam, Circuit House.	Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi.
- March 2, 1965	Koyna Dam, Rest House, Koyna.	Shri P. S. Bhatnagar Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi,
April 27, 1965	Bhakra & Beas Designs Organisation, N. Delhi.	Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi,
July 16 &_ 17, 1965	Instrumentation Lab. C.W.& P.R.S., Poona.	Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi,
August 6 & 7, 1965.	Bhakra & Beas Designs Organization, N. Delhi.	Shri P. S. Bhatnagar Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi.
August 24 & 25, 1965.	Office of S.E., Deccan, Irrigation Circle III, Nasik.	Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi.
Oct. 20 & E 21, 1965.	bhakra & Beas Designs Organization, N. Delhi.	Shri P. S. Bhatnagar Shri I. P. Kapila Shri K. R. Datye Shri B. Pant Shri V. K. Sondhi
Nov. 9 & 10, 1965.	Inspection House, Maha- rashtra Govt., Poona.	Shri P. S. Bhatnagar Shri K. R. Datye Shri B. Pant Shri V. K. Sondhl.

4. The Members of the Committee visited the following projects :---

- (a) Gandhi Sagar (visited by I. P. Kapila, K. K. Datye, B. Pant & V. K. Sondhi on 28th/29th Jan. 1965).
- (b) Ranapartap Sagar Dam under construction (visited by I. P. Kapila, K. R. Datye, B. Pant & V. K. Sondhi on 28th/29th Jan. 1965).
- (c) Kotah Barrage (visited by I. P. Kapila, K. R. Datye, B. Pant & V. K. Sondhi on 28th/29th Jan. 1965).
- (d) Kunnu Syphon Aqueduct (visited by K. R. Datye and B. Pant on 30th January, 1965).
- (e) Koyna Dam & Power Plant (visited by all members on March 2, 1965).
- (f) Sharavathy Project (visited by P. S. Bhatnagar, I. P. Kapila, and V. K. Sondhi on 5th March 1965, and K. R. Datye on 31-10-1965 to 2-11-1965).
- (g) Bhakra Dam (visited by K. R. Datye, B. Pant and V. K. Sondhi on 29th/30th April, 1965).
- (h) Hirakud Dam (visited by K. R. Datye on 24th/ 25th May, 1965).
- (i) Rihand Dam (visited by V. K. Sondhi on 29th to 31st July, 1965).
- (j) Tungabhadra Dam (visited by V. K. Sondhi on 10th/11th August, 1965).

In addition, the Committee had the advantage of first hand information with Shri K. R. Datye regarding Gangapur, Bor and Girna Dams in Maharashtra where instrumentation has been carried out.

5. Authorities concerned with the River Valley Projects in the Centre and various States were requested to supply particulars of instrumentation affected at projects under their control. This information was sought in two proforma statements (Appendix 0.02). Replies from 46 authorities were received, out of which 27 indicated that either no structure was under their charge or no instrumentation was provided, and 19 (covering 30 structures) supplied some information. The information as supplied or as collected is in respect of the following structures :—

- (a) Concrete Dams Bhakra Dam Koyna Dam Rihand Dam
- (b) Masonry Dams Gandhi Sagar Dam Hirakud Dam Linganamakki Dam

Malampuza Dam Mani Muthar Dam Nagarjunasagar Dam Parambikulam Aliyar Project Tungabhadra Dam Walayar Dam

(c) Earth Dams Bor Dam Buggavagu Dam Dantiwada Dam Datla Tank Gangapur Dam Ghod Dam Girna Dam Hathmati Dam Hirakud Dam Jirgo Dam Kotah Barrage Linganamakki Dam Meshwa Dam Nalganga Dam Nanak Sagar Dam Sampana Dam Ukai Dam

(d) Other Structures
Bhira Tunnel
Koyna Head Race Tunnel
Koyna Power House Foundation
Koyna Pressure Shaft
Kunnu Syphon Aqueduct
Nagarjunasagar Right Canal Tunnel
Sharavathy Water Conductor System
Vir Dam.

The information is consolidated at Appendix 0.03.

6. As a result of detailed study of the information pertaining to instrumentation at various projects, discussions with project engineers, information obtained from persons outside India who are actively engaged in this work, discussion with representatives of manufacturers of instruments, and of the published literature on this subject, the Report of the Committee is submitted herewith. This report is in two parts. Part I is the general report dealing with the specific terms of reference embodied in the Resolution of the Government of India. Part II is the detailed report which deals with objectives of instrumentation, nature of measurements and their purpose and description of the various instruments generally adopted for such measurements. Detailed information pertaining to principles of working and construction, considerations governing location and layout, method of installation, observation and analysis of observed data has either been included or reference has been made to relevant technical publications. The Committee has felt it desirable to add Part II of the Report so as to provide the background in the context of which Part I of the Report has been written.

The Committee has not examined any measurements relating to stability of slopes within the reservoir area which affect the safety and utility of a structure, as this was outside the scope of the terms of reference. Measurements relating to meteorological data, and seismic characteristics of dams and structures have likewise not been examined as being outside the scope of the terms of reference of the Committee, except for the brief mention wherever considered necessary in this report.

7. The work of the Committee was seriously handicapped by the fact that the Chairman was hospitalised for a period of four months from April to the end of July 1965. On this account the period for the submission of the Committee Report was first extended up to the end of September 1965 and subsequently up to the end of Dec. 1965 by Government of India, Ministry of Irrigation & Power Resolution No. 20(31)/ 63-Policy, dated 6th July, 1965 (Appendix 0.04) and Resolution No. 20(31), dated 29th September, 1965 (Appendix 0.05) respectively.

### ACKNOWLEDGEMENTS

The Committee is specially indebted to Shri R. P. Sharma, Senior Design Engineer of Bhakra & Beas Designs Organization, New Delhi for his valuable contribution in the deliberations of the Committee and in compilation and editing the Committee Report.

The following officers also assisted in the work of the Committee:

Shri V. A. Parkash, Deputy Director and Shri N. C. Gupta, Asstt. Design Engineer, both of Bhakra & Beas Designs Organization, New Delhi; Shri Shiyekar, Asstt. Engineer of Deccan Irrigation Circle, Nasik; Shri A. S. Khot, Research Officer, Central Water & Power Research Station, Poona; Shri K. M. Nagbhushan, Asstt. Director and Shri R. N. Poddar, Asstt. Director, both of Central Water & Power Commission.

Typing of the final Report was done by Shri O. P. Gupta, Stenographer, Bhakra & Beas Designs Organization, New Delhi.